

Date 07/26/2002
Time 11:00 AM

Parametric Building Models

Page: 1

Cost Worksheet

PROJECT: MWL
PROJECT
PROJECT COMMENT:

GEOLOCATION: ALBUQUERQUE, NEW MEXICO

ESTIMATE BY: UA92T59
ESTIMATE DATE: 07/11/2002

ESCALATION MODIFIER: MID-POINT OF CONSTRUCTION

Date 07/26/2002
Time 11:00 AM

DD Form 1391 Cost Worksheet

Page: 2

1. AIR FORCE		FY 2004 Military Construction Project Data		2. Date 07/26/2002	
3. Installation and Location ALBUQUERQUE, NEW MEXICO			4. Project Title MWL		
5. Program Element	6. Category code 149-000	7. Project Number 1	8. Project Cost 197,000		
9. Cost Estimates					
Item	U/M	Quantity	Unit Cost	Cost (\$000)	

Primary Facilities				174,962
UnClass Soil Storage Warehouse 1	SF	569,999	51.58	(29,400)
UnClass Soil Storage Warehouse 2	SF	569,999	51.58	(29,400)
UnClass Soil Storage Warehouse 3	SF	569,999	51.58	(29,400)
Class Soil Storage Warehouse 1	SF	477,803	52.01	(24,850)
Class Soil Storage Warehouse 2	SF	477,803	52.01	(24,850)
UnClass Waste Storage Warehouse	SF	569,999	52.41	(29,875)
Classified Waste Storage Warehouse	SF	103,459	69.48	(7,188)

Supporting Facilities				2,695
MWL Storage Facility Office	SF	5,286	175.38	(927)
MWL Retrievable Storage Site Work	LS	--	--	(1,727)
Antiterrorism/Force Protection	LS	--	--	(42)

Subtotal		177,658
Contingency (5.00%)		8,883

Total Contract Cost		186,541
Supervision, Inspection & Overhead (5.70%)		10,633
Total Request		197,173
Total Request (Rounded)		197,000

Date 07/26/2002
Time 10:47 AM

Parametric Building Models
CONSTRUCTION COST SUMMARY REPORT

Page: 1

Project Name : MWL
Project Description :
Project Comment

GEOLOCATION ALBUQUERQUE, NEW MEXICO

Estimate by: UA92T59
Estimate Date: 07/11/2002

ESCALATION MODIFIER: MID-POINT OF CONSTRUCTION

CONSTRUCTION COST SUMMARY REPORT

Facility:	MWL Storage Facility Office	Cost
Model Type:	GENERAL ADMINISTRATIVE FACILITY	
Facility Direct Cost		\$684,704
Total Direct Cost		\$684,704
Facility:	MWL Retrievable Storage Site Work	Cost
Model Type:	Site Work	
Facility Direct Cost		\$1,220,322
Total Direct Cost		\$1,220,322
Facility:	Classified Waste Storage Warehouse	Cost
Model Type:	HIGH BAY WAREHOUSE	
Facility Direct Cost		\$5,080,123
Total Direct Cost		\$5,080,123
Facility:	Class Soil Storage Warehouse 1	Cost
Model Type:	HIGH BAY WAREHOUSE	
Facility Direct Cost		\$17,563,199
Total Direct Cost		\$17,563,199
Facility:	Class Soil Storage Warehouse 2	Cost
Model Type:	HIGH BAY WAREHOUSE	
Facility Direct Cost		\$17,563,199
Total Direct Cost		\$17,563,199
Facility:	UnClass Soil Storage Warehouse 1	Cost
Model Type:	HIGH BAY WAREHOUSE	
Facility Direct Cost		\$20,778,390
Total Direct Cost		\$20,778,390
Facility:	UnClass Soil Storage Warehouse 2	Cost
Model Type:	HIGH BAY WAREHOUSE	
Facility Direct Cost		\$20,778,390
Total Direct Cost		\$20,778,390
Facility:	UnClass Soil Storage Warehouse 3	Cost
Model Type:	HIGH BAY WAREHOUSE	
Facility Direct Cost		\$20,778,390
Total Direct Cost		\$20,778,390

Parametric Building Models

CONSTRUCTION COST SUMMARY REPORT

Facility: UnClass Waste Storage Warehouse
Model Type: HIGH BAY WAREHOUSE

	Cost
Facility Direct Cost	\$21,114,374
Total Direct Cost	\$21,114,374
Project Total Direct Cost	\$125,561,091
Markups	\$52,096,626
Project Marked Up Cost	\$177,657,717
Contingency 5.00%	\$8,882,886
SIOH 5.70%	\$10,632,814
Project Cost	\$197,173,417
Total Project Cost	\$197,173,417

This page left intentionally blank.

Date 07/26/2002
Time 10:48 AM

Parametric Building Models

Page: 1

PRORATED SYSTEM CONSTRUCTION COST

Project Name : MWL
Project Description :
Project Comment

GEOLOCATION ALBUQUERQUE, NEW MEXICO

Estimate by: UA92T59
Estimate Date: 07/11/2002

ESCALATION MODIFIER: MID-POINT OF CONSTRUCTION

Parametric Building Models

PRORATED SYSTEM CONSTRUCTION COST

Facility Name *UnClass Soil Storage Warehouse 1*

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	\$1,894,266	\$2,281,223	\$102,809	\$4,278,298	20.59%
02	SUPERSTRUCTURE	\$5,042,847	\$3,007,306	\$262,882	\$8,313,034	40.01%
03	EXTERIOR CLOSURE	\$701,640	\$206,167	\$12,075	\$919,882	4.43%
04	ROOFING	\$1,654,925	\$977,386	\$0	\$2,632,311	12.67%
05	INTERIOR CONSTRUCTION	\$542,503	\$375,824	\$0	\$918,326	4.42%
06	INTERIOR FINISHES	\$132,661	\$223,431	\$0	\$356,092	1.71%
08	PLUMBING	\$26,788	\$36,934	\$0	\$63,722	0.31%
09	H.V.A.C	\$581,857	\$221,010	\$338	\$803,205	3.87%
10	FIRE PROTECTION SYSTEMS	\$379,430	\$509,928	\$1,089	\$890,446	4.29%
11	ELECTRIC POWER & LIGHTING	\$518,835	\$681,901	\$144	\$1,200,880	5.78%
12	ELECTRICAL SYSTEMS	\$188,070	\$206,109	\$0	\$394,179	1.90%
13	EQUIPMENT	\$5,426	\$2,546	\$41	\$8,013	0.04%
Facility Total		\$11,669,247	\$8,729,765	\$379,378	\$20,778,390	100%

Facility Name *UnClass Soil Storage Warehouse 2*

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	\$1,894,266	\$2,281,223	\$102,809	\$4,278,298	20.59%
02	SUPERSTRUCTURE	\$5,042,847	\$3,007,306	\$262,882	\$8,313,034	40.01%
03	EXTERIOR CLOSURE	\$701,640	\$206,167	\$12,075	\$919,882	4.43%
04	ROOFING	\$1,654,925	\$977,386	\$0	\$2,632,311	12.67%
05	INTERIOR CONSTRUCTION	\$542,503	\$375,824	\$0	\$918,326	4.42%
06	INTERIOR FINISHES	\$132,661	\$223,431	\$0	\$356,092	1.71%
08	PLUMBING	\$26,788	\$36,934	\$0	\$63,722	0.31%
09	H.V.A.C	\$581,857	\$221,010	\$338	\$803,205	3.87%
10	FIRE PROTECTION SYSTEMS	\$379,430	\$509,928	\$1,089	\$890,446	4.29%
11	ELECTRIC POWER & LIGHTING	\$518,835	\$681,901	\$144	\$1,200,880	5.78%
12	ELECTRICAL SYSTEMS	\$188,070	\$206,109	\$0	\$394,179	1.90%
13	EQUIPMENT	\$5,426	\$2,546	\$41	\$8,013	0.04%
Facility Total		\$11,669,247	\$8,729,765	\$379,378	\$20,778,390	100%

Facility Name *UnClass Soil Storage Warehouse 3*

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	\$1,894,266	\$2,281,223	\$102,809	\$4,278,298	20.59%
02	SUPERSTRUCTURE	\$5,042,847	\$3,007,306	\$262,882	\$8,313,034	40.01%
03	EXTERIOR CLOSURE	\$701,640	\$206,167	\$12,075	\$919,882	4.43%
04	ROOFING	\$1,654,925	\$977,386	\$0	\$2,632,311	12.67%
05	INTERIOR CONSTRUCTION	\$542,503	\$375,824	\$0	\$918,326	4.42%
06	INTERIOR FINISHES	\$132,661	\$223,431	\$0	\$356,092	1.71%
08	PLUMBING	\$26,788	\$36,934	\$0	\$63,722	0.31%
09	H.V.A.C	\$581,857	\$221,010	\$338	\$803,205	3.87%
10	FIRE PROTECTION SYSTEMS	\$379,430	\$509,928	\$1,089	\$890,446	4.29%
11	ELECTRIC POWER & LIGHTING	\$518,835	\$681,901	\$144	\$1,200,880	5.78%
12	ELECTRICAL SYSTEMS	\$188,070	\$206,109	\$0	\$394,179	1.90%
13	EQUIPMENT	\$5,426	\$2,546	\$41	\$8,013	0.04%
Facility Total		\$11,669,247	\$8,729,765	\$379,378	\$20,778,390	100%

Parametric Building Models

PRORATED SYSTEM CONSTRUCTION COST

Facility Name *Class Soil Storage Warehouse 1*

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	\$1,588,534	\$1,912,914	\$86,206	\$3,587,654	20.43%
02	SUPERSTRUCTURE	\$4,228,015	\$2,521,381	\$220,405	\$6,969,801	39.68%
03	EXTERIOR CLOSURE	\$630,330	\$182,673	\$10,777	\$823,780	4.69%
04	ROOFING	\$1,387,549	\$819,528	\$0	\$2,207,077	12.57%
05	INTERIOR CONSTRUCTION	\$454,711	\$315,195	\$0	\$769,906	4.38%
06	INTERIOR FINISHES	\$112,296	\$188,580	\$0	\$300,876	1.71%
08	PLUMBING	\$22,889	\$31,747	\$0	\$54,636	0.31%
09	H.V.A.C	\$476,800	\$186,894	\$301	\$663,995	3.78%
10	FIRE PROTECTION SYSTEMS	\$318,103	\$427,509	\$913	\$746,525	4.25%
11	ELECTRIC POWER & LIGHTING	\$490,290	\$614,983	\$330	\$1,105,603	6.29%
12	ELECTRICAL SYSTEMS	\$153,956	\$171,378	\$0	\$325,334	1.85%
13	EQUIPMENT	\$5,426	\$2,546	\$41	\$8,013	0.05%
Facility Total		\$9,868,899	\$7,375,327	\$318,973	\$17,563,199	100%

Facility Name *Class Soil Storage Warehouse 2*

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	\$1,588,534	\$1,912,914	\$86,206	\$3,587,654	20.43%
02	SUPERSTRUCTURE	\$4,228,015	\$2,521,381	\$220,405	\$6,969,801	39.68%
03	EXTERIOR CLOSURE	\$630,330	\$182,673	\$10,777	\$823,780	4.69%
04	ROOFING	\$1,387,549	\$819,528	\$0	\$2,207,077	12.57%
05	INTERIOR CONSTRUCTION	\$454,711	\$315,195	\$0	\$769,906	4.38%
06	INTERIOR FINISHES	\$112,296	\$188,580	\$0	\$300,876	1.71%
08	PLUMBING	\$22,889	\$31,747	\$0	\$54,636	0.31%
9	H.V.A.C	\$476,800	\$186,894	\$301	\$663,995	3.78%
10	FIRE PROTECTION SYSTEMS	\$318,103	\$427,509	\$913	\$746,525	4.25%
11	ELECTRIC POWER & LIGHTING	\$490,290	\$614,983	\$330	\$1,105,603	6.29%
12	ELECTRICAL SYSTEMS	\$153,956	\$171,378	\$0	\$325,334	1.85%
13	EQUIPMENT	\$5,426	\$2,546	\$41	\$8,013	0.05%
Facility Total		\$9,868,899	\$7,375,327	\$318,973	\$17,563,199	100%

Facility Name *UnClass Waste Storage Warehouse*

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	\$1,894,266	\$2,281,223	\$102,809	\$4,278,298	20.26%
02	SUPERSTRUCTURE	\$5,042,847	\$3,007,306	\$262,882	\$8,313,034	39.37%
03	EXTERIOR CLOSURE	\$1,007,005	\$236,786	\$12,075	\$1,255,867	5.95%
04	ROOFING	\$1,654,925	\$977,386	\$0	\$2,632,311	12.47%
05	INTERIOR CONSTRUCTION	\$542,503	\$375,824	\$0	\$918,326	4.35%
06	INTERIOR FINISHES	\$132,661	\$223,431	\$0	\$356,092	1.69%
08	PLUMBING	\$26,788	\$36,934	\$0	\$63,722	0.30%
09	H.V.A.C	\$581,857	\$221,010	\$338	\$803,205	3.80%
10	FIRE PROTECTION SYSTEMS	\$379,430	\$509,928	\$1,089	\$890,446	4.22%
11	ELECTRIC POWER & LIGHTING	\$518,835	\$681,901	\$144	\$1,200,880	5.69%
12	ELECTRICAL SYSTEMS	\$188,070	\$206,109	\$0	\$394,179	1.87%
13	EQUIPMENT	\$5,426	\$2,546	\$41	\$8,013	0.04%
Facility Total		\$11,974,613	\$8,760,384	\$379,378	\$21,114,374	100%

Parametric Building Models

PRORATED SYSTEM CONSTRUCTION COST

Facility Name *Classified Waste Storage Warehouse*

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	\$337,475	\$415,949	\$18,477	\$771,901	15.19%
02	SUPERSTRUCTURE	\$1,318,050	\$1,075,924	\$53,848	\$2,447,822	48.18%
03	EXTERIOR CLOSURE	\$388,508	\$80,391	\$4,234	\$473,133	9.31%
04	ROOFING	\$301,898	\$178,514	\$0	\$480,412	9.46%
05	INTERIOR CONSTRUCTION	\$98,270	\$69,026	\$0	\$167,296	3.29%
06	INTERIOR FINISHES	\$29,609	\$47,075	\$0	\$76,683	1.51%
08	PLUMBING	\$7,959	\$8,096	\$0	\$16,055	0.32%
09	H.V.A.C	\$97,334	\$57,712	\$174	\$155,220	3.06%
10	FIRE PROTECTION SYSTEMS	\$69,203	\$93,004	\$199	\$162,405	3.20%
11	ELECTRIC POWER & LIGHTING	\$109,082	\$133,854	\$64	\$243,001	4.78%
12	ELECTRICAL SYSTEMS	\$38,261	\$39,922	\$0	\$78,183	1.54%
13	EQUIPMENT	\$5,426	\$2,546	\$41	\$8,013	0.16%
Facility Total		\$2,801,073	\$2,202,014	\$77,037	\$5,080,123	100%

Facility Name *MWL Storage Facility Office*

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	\$13,493	\$16,801	\$969	\$31,264	4.57%
02	SUPERSTRUCTURE	\$39,446	\$37,856	\$2,065	\$79,367	11.59%
03	EXTERIOR CLOSURE	\$69,894	\$54,659	\$227	\$124,781	18.22%
04	ROOFING	\$12,721	\$8,204	\$0	\$20,925	3.06%
05	INTERIOR CONSTRUCTION	\$25,323	\$24,540	\$10	\$49,873	7.28%
06	INTERIOR FINISHES	\$20,977	\$22,010	\$197	\$43,184	6.31%
07	CONVEYING SYSTEMS	\$6,069	\$598	\$0	\$6,667	0.97%
08	PLUMBING	\$7,303	\$10,158	\$0	\$17,460	2.55%
09	H.V.A.C	\$78,701	\$78,368	\$7	\$157,076	22.94%
10	FIRE PROTECTION SYSTEMS	\$4,875	\$6,646	\$0	\$11,521	1.68%
11	ELECTRIC POWER & LIGHTING	\$57,984	\$55,436	\$44	\$113,463	16.57%
12	ELECTRICAL SYSTEMS	\$12,246	\$15,118	\$0	\$27,364	4.00%
13	EQUIPMENT	\$746	\$31	\$0	\$778	0.11%
15	SPECIAL CONSTRUCTION	\$869	\$113	\$0	\$982	0.14%
Facility Total		\$350,648	\$330,537	\$3,519	\$684,704	100%

Facility Name *MWL Retrievable Storage Site Work*


System	Description	Material	Labor	Equipment	Total	% of Total
17	SITE PREPARATION	\$16,542	\$124,666	\$81,164	\$222,372	18.22%
18	SITE IMPROVEMENTS	\$305,687	\$68,238	\$28,776	\$402,701	33.00%
19	SITE CIVIL/MECHANICAL UTILITIES	\$42,364	\$38,352	\$5,218	\$85,934	7.04%
20	SITE ELECTRICAL UTILITIES	\$314,780	\$182,813	\$11,721	\$509,315	41.74%
Facility Total		\$679,374	\$414,069	\$126,879	\$1,220,322	100%

Parametric Building Models **PRORATED SYSTEM CONSTRUCTION COST**

Facilities Total	\$70,551,248	\$52,646,952	\$2,362,892	\$125,561,092	100%
				2	
	Total Direct Cost			\$125,561,092	
	Comparative Supporting Facilities				
	PAVEMENT			\$0	
	SITE IMPROVEMENTS			\$0	
	UTILITIES			\$0	
				<hr/>	
				\$0	
	Project Total Direct Cost			\$125,561,092	
	Markups			\$52,096,626	
	Project Marked Up Cost			<hr/>	
				\$177,657,718	
	Contengency			5.00%	\$8,882,886
	SIOH			5.70%	\$10,632,814
				<hr/>	
	Program Amount			\$197,173,418	

This page left intentionally blank.

Paces



Project Summary Report

PArametric
Cost
Engineering
System

Notes:

All costs are 'Direct Costs' except as indicated at the Project level.
Markups are added to the Project level direct costs to arrive at the Total Project
All costs are listed in the order:
Material, Labor, Equipment, Total. (M,L,E,T)

Project:		Name:	MWL	Service:	AIR FORCE
Start	07/11/2002	Descr:		Est. By:	UA92T59
Num:	1	Loc:	ALBUQUERQUE, NEW MEXICO		
		Comments			

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>		
FSA:	ID:	Name:	Building Shell						
Facility Type:	Primary	ID: 9	Name:	UnClass Soil Storage Warehouse 1					
Assm:	01010103	Descr:	1'0" X 3'0" Strip Footing 3000 PSI	UOM:	LF	\$11.15	\$10.90	\$0.17	\$22.22
				Qty:	4622	\$51,550	\$50,376	\$784	\$102,709
Assm:	01010105	Descr:	1'6" X 4'0" Strip Footing 3000 PSI	UOM:	LF	\$21.62	\$17.86	\$0.29	\$39.77
				Qty:	2558	\$55,296	\$45,684	\$748	\$101,728
Assm:	01010112	Descr:	1'3" X 2'6" Grade Beam 4000 PSI	UOM:	LF	\$20.15	\$26.26	\$0.21	\$46.63
				Qty:	4622	\$93,158	\$121,396	\$959	\$215,512
Assm:	01010117	Descr:	16" Masonry Wall Foundation - 24" Deep Wall	UOM:	LF	\$14.13	\$21.63	\$0.07	\$35.83
				Qty:	5116	\$72,275	\$110,653	\$377	\$183,305
Assm:	01010201	Descr:	Spread Footing	UOM:	CY	\$73.57	\$45.75	\$2.16	\$121.48
				Qty:	1360	\$100,050	\$62,224	\$2,937	\$165,211
Assm:	01010212	Descr:	Column Piers 2'0" X 2'0" X 3'0" High	UOM:	EA	\$87.34	\$173.72	\$1.69	\$262.75
				Qty:	245	\$21,399	\$42,561	\$414	\$64,374
Assm:	01010241	Descr:	Spread Footing, Reinforcing Steel	UOM:	TON	\$551.26	\$645.22	\$0.00	\$1,196.47
				Qty:	15	\$8,164	\$9,556	\$0	\$17,720
Assm:	01029050	Descr:	Tie Beams (Seismic Modification)	UOM:	LF	\$14.64	\$18.55	\$0.16	\$33.35
				Qty:	13991	\$204,791	\$259,584	\$2,262	\$466,637
Assm:	01030104	Descr:	7" Standard Slab On Grade	UOM:	SF	\$2.01	\$2.62	\$0.16	\$4.79
				Qty:	570581	\$1,146,868	\$1,495,550	\$91,464	\$2,733,882

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 01030115	Descr: Loading Dock Apron	UOM: SF	\$3.89	\$2.31	\$0.08	\$6.28
		Qty: 36155	\$140,715	\$83,641	\$2,863	\$227,220
Assm: 02020204	Descr: 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	UOM: SF	\$5.99	\$8.06	\$0.09	\$14.14
		Qty: 235108	\$1,408,438	\$1,894,030	\$22,194	\$3,324,662
Assm: 02020313	Descr: Precast/Prestressed Roof Members	UOM: SF	\$4.96	\$1.19	\$0.34	\$6.49
		Qty: 634056	\$3,145,171	\$754,463	\$215,325	\$4,114,960
Assm: 02020314	Descr: 3" Topping Slab	UOM: SF	\$0.77	\$0.57	\$0.04	\$1.38
		Qty: 634056	\$489,238	\$358,812	\$25,362	\$873,412
Assm: 03010103	Descr: Tilt-Up Wall Panel 5-1/2" Thick	UOM: SF	\$11.02	\$1.21	\$0.17	\$12.40
		Qty: 42194	\$465,134	\$51,004	\$7,215	\$523,353
Assm: 03010147	Descr: Additional Vertical Reinforcement And Grouting; Seismic	UOM: SF	\$0.23	\$0.36	\$0.03	\$0.62
		Qty: 42194	\$9,679	\$15,270	\$1,063	\$26,013
Assm: 03010205	Descr: Loose Fill 8" Block Insulation	UOM: SF	\$0.51	\$0.46	\$0.00	\$0.98
		Qty: 42194	\$21,548	\$19,612	\$0	\$41,160
Assm: 03010312	Descr: Paint CMU/Concrete	UOM: SF	\$0.19	\$0.53	\$0.00	\$0.72
		Qty: 42194	\$7,819	\$22,494	\$0	\$30,312
Assm: 03010501	Descr: Fixed Blade Exterior Louver With Baked Enamel Finish	UOM: SF	\$29.84	\$12.28	\$0.00	\$42.12
		Qty: 956	\$28,526	\$11,738	\$0	\$40,264
Assm: 03030101	Descr: 3'0" X 7'0" Aluminum And Glass Door	UOM: EA	\$608.95	\$579.12	\$0.00	\$1,188.07
		Qty: 3	\$1,827	\$1,737	\$0	\$3,564
Assm: 03030202	Descr: 3'0" X 7'0" Hollow Metal Door W/Frame	UOM: EA	\$1,287.09	\$468.13	\$0.00	\$1,755.22
		Qty: 20	\$25,742	\$9,363	\$0	\$35,104

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 03030204	Descr: 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	UOM: EA	\$2,328.71	\$734.80	\$0.00	\$3,063.51
		Qty: 3	\$6,986	\$2,204	\$0	\$9,191
Assm: 03040103	Descr: 20'0" X 14'0" Metal Overhead Door	UOM: EA	\$3,536.29	\$1,914.35	\$99.90	\$5,550.54
		Qty: 38	\$134,379	\$72,745	\$3,796	\$210,921
Assm: 04010108	Descr: Standing Seam Metal Roof	UOM: SF	\$2.03	\$1.26	\$0.00	\$3.29
		Qty: 634056	\$1,287,768	\$797,706	\$0	\$2,085,474
Assm: 04010302	Descr: Rigid Insulation 1-1/2" Thick	UOM: SF	\$0.35	\$0.24	\$0.00	\$0.59
		Qty: 634056	\$223,378	\$152,871	\$0	\$376,249
Assm: 04010503	Descr: Skylights, Plastic Insulated Domes	UOM: SF	\$23.64	\$4.31	\$0.00	\$27.94
		Qty: 6071	\$143,492	\$26,159	\$0	\$169,652
Assm: 04010601	Descr: 5" Box Gutters With Downspouts	UOM: LF	\$1.59	\$3.61	\$0.00	\$5.20
		Qty: 180	\$287	\$650	\$0	\$937
Assm: 08020101	Descr: Copper Pipe & Fittings	UOM: EA	\$203.76	\$720.72	\$0.00	\$924.48
		Qty: 24	\$4,890	\$17,297	\$0	\$22,188
Assm: 08020201	Descr: Valves & Hydrants	UOM: EA	\$90.94	\$25.08	\$0.00	\$116.03
		Qty: 13	\$1,182	\$326	\$0	\$1,508
Assm: 08020401	Descr: Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	UOM: EA	\$78.67	\$82.34	\$0.00	\$161.01
		Qty: 24	\$1,888	\$1,976	\$0	\$3,864
Assm: 08030101	Descr: Waste Pipe & Fittings	UOM: EA	\$180.14	\$361.88	\$0.00	\$542.02
		Qty: 30	\$5,404	\$10,856	\$0	\$16,261
Assm: 08030202	Descr: PVC Vent Piping	UOM: EA	\$13.95	\$47.57	\$0.00	\$61.51
		Qty: 30	\$418	\$1,427	\$0	\$1,845

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 08030305	Descr: Heavy Duty Cast Iron Floor Drains	UOM: EA	\$409.55	\$63.67	\$0.00	\$473.21
		Qty: 6	\$2,457	\$382	\$0	\$2,839
Assm: 08050102	Descr: Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	UOM: EA	\$299.10	\$172.74	\$0.00	\$471.84
		Qty: 2	\$598	\$345	\$0	\$944
Assm: 08050108	Descr: Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	UOM: EA	\$400.59	\$43.19	\$0.00	\$443.77
		Qty: 3	\$1,202	\$130	\$0	\$1,331
Assm: 08060201	Descr: Acid Waste System For Battery & Acid Rooms	UOM: EA	\$2,609.25	\$939.01	\$0.00	\$3,548.25
		Qty: 2	\$5,218	\$1,878	\$0	\$7,097
Assm: 08060204	Descr: Special Plumbing For Battery And Acid Rooms	UOM: EA	\$362.85	\$935.23	\$0.00	\$1,298.08
		Qty: 2	\$726	\$1,870	\$0	\$2,596
Assm: 08060304	Descr: Interceptors For Battery & Acid Rooms	UOM: EA	\$1,401.67	\$222.85	\$0.00	\$1,624.52
		Qty: 2	\$2,803	\$446	\$0	\$3,249
Assm: 09010211	Descr: 18000 MBH Gas Supply	UOM: EA	\$10,823.28	\$10,577.38	\$148.33	\$21,548.98
		Qty: 1	\$10,823	\$10,577	\$148	\$21,549
Assm: 09020403	Descr: Gas Fired Unit Heater, 300 MBH, Spark Ignition	UOM: EA	\$3,016.12	\$839.47	\$1.70	\$3,857.29
		Qty: 112	\$337,806	\$94,021	\$190	\$432,017
Assm: 09030209	Descr: 15 Ton Condensing Unit With Refrigerant Piping	UOM: EA	\$8,123.97	\$3,365.04	\$0.00	\$11,489.01
		Qty: 2	\$16,248	\$6,730	\$0	\$22,978
Assm: 09040703	Descr: Toilet Exhaust .2 MCFM	UOM: MCFM	\$1,116.15	\$1,667.16	\$0.00	\$2,783.31
		Qty: 1	\$659	\$984	\$0	\$1,642
Assm: 09040727	Descr: Ventilation System, 64.8 MCFM	UOM: MCFM	\$418.17	\$71.07	\$0.00	\$489.24
		Qty: 359	\$150,205	\$25,530	\$0	\$175,735

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 09040765	Descr: 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	UOM: MCFM	\$3,520.33	\$790.73	\$0.00	\$4,311.06
		Qty: 10	\$34,781	\$7,812	\$0	\$42,593
Assm: 09049907	Descr: Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	UOM: MCFM	\$1,370.16	\$1,955.73	\$0.00	\$3,325.89
		Qty: 0	\$356	\$508	\$0	\$865
Assm: 09049921	Descr: 2.0 MCFM Air Dist Sys With Heat Pump	UOM: MCFM	\$3,706.36	\$4,390.65	\$0.00	\$8,097.01
		Qty: 2	\$8,636	\$10,230	\$0	\$18,866
Assm: 09049923	Descr: 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	UOM: MCFM	\$1,645.75	\$4,920.50	\$0.00	\$6,566.24
		Qty: 2	\$2,847	\$8,512	\$0	\$11,360
Assm: 09060107	Descr: Control System For Cooling Unit	UOM: EA	\$122.32	\$58.85	\$0.00	\$181.17
		Qty: 2	\$245	\$118	\$0	\$362
Assm: 09060182	Descr: Controls For Ventilating System	UOM: EA	\$19,211.52	\$29,488.79	\$0.00	\$48,700.31
		Qty: 1	\$19,212	\$29,489	\$0	\$48,700
Assm: 09070201	Descr: Test & Balance, Cent Fan/Utility Set	UOM: EA	\$0.00	\$206.44	\$0.00	\$206.44
		Qty: 35	\$0	\$7,225	\$0	\$7,225
Assm: 09070202	Descr: Test & Balance H&V Unit/In Line Fan	UOM: EA	\$0.00	\$309.73	\$0.00	\$309.73
		Qty: 58	\$0	\$17,964	\$0	\$17,964
Assm: 09070206	Descr: Test & Balance Air Handler, Low Pressure	UOM: EA	\$0.00	\$413.28	\$0.00	\$413.28
		Qty: 3	\$0	\$1,240	\$0	\$1,240
Assm: 09070211	Descr: Test & Balance Vav Box	UOM: EA	\$39.90	\$68.74	\$0.00	\$108.64
		Qty: 1	\$40	\$69	\$0	\$109
Assm: 10010104	Descr: Fire Prot Water Supply, (40'H) Ord Haz Fac	UOM: EA	\$48.03	\$21.35	\$0.22	\$69.60
		Qty: 4962	\$238,327	\$105,928	\$1,089	\$345,344

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 10020101	Descr: Exposed Sprinkler System For A Lg Facility - Ord. Haz.	UOM: EA	\$28.44	\$81.42	\$0.00	\$109.86
		Qty: 4962	\$141,102	\$404,000	\$0	\$545,102
Assm: 11010108	Descr: Electrical 2500A Main Transformer	UOM: EA	\$29,512.44	\$4,886.87	\$96.72	\$34,496.03
		Qty: 1	\$29,512	\$4,887	\$97	\$34,496
Assm: 11010211	Descr: Electrical 2500A Secondary	UOM: EA	\$37,780.63	\$23,682.69	\$47.01	\$61,510.33
		Qty: 1	\$37,781	\$23,683	\$47	\$61,510
Assm: 11010311	Descr: Electrical 2500A Main Switchboard	UOM: EA	\$91,215.75	\$9,632.58	\$0.00	\$100,848.33
		Qty: 1	\$91,216	\$9,633	\$0	\$100,848
Assm: 11010403	Descr: (45-90 Amps 480V) 75 KVA Dry Type Transformer	UOM: EA	\$2,149.90	\$1,038.62	\$0.00	\$3,188.52
		Qty: 9	\$19,349	\$9,348	\$0	\$28,697
Assm: 11010502	Descr: Panelbd 208V 100A 30 Cir Mlo W/Bkr	UOM: EA	\$1,153.60	\$899.36	\$0.00	\$2,052.95
		Qty: 8	\$9,229	\$7,195	\$0	\$16,424
Assm: 11010507	Descr: Panelbd 208V 225A 42 Cir Mlo W/Bkr	UOM: EA	\$1,772.16	\$2,235.15	\$0.00	\$4,007.30
		Qty: 8	\$14,177	\$17,881	\$0	\$32,058
Assm: 11010516	Descr: Panelbd 208V 225A MCB 42 Cir W/Bkr	UOM: EA	\$2,088.56	\$2,391.53	\$0.00	\$4,480.09
		Qty: 1	\$2,089	\$2,392	\$0	\$4,480
Assm: 11010561	Descr: Panelbd 480V 600A MCB 42 Cir W/Bkr	UOM: EA	\$7,082.74	\$3,958.17	\$0.00	\$11,040.92
		Qty: 2	\$14,165	\$7,916	\$0	\$22,082
Assm: 11010604	Descr: Enclosed Cir Bkr 600V 225A	UOM: EA	\$1,805.61	\$1,767.07	\$0.00	\$3,572.68
		Qty: 1	\$1,806	\$1,767	\$0	\$3,573
Assm: 12010102	Descr: Fire Alarm System - Rate Of Rise Heat Detectors	UOM: OUT	\$102.32	\$374.83	\$0.00	\$477.15
		Qty: 192	\$19,646	\$71,968	\$0	\$91,614

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 12010119	Descr: 16 Zone FACP, Annun And Transmitter	UOM:	EA	\$6,181.75	\$3,465.03	\$0.00	\$9,646.78
		Qty:	2	\$12,363	\$6,930	\$0	\$19,294
Assm: 12010301	Descr: Telephone System, 2 Pair	UOM:	EA	\$42.39	\$176.98	\$0.00	\$219.38
		Qty:	55	\$2,332	\$9,734	\$0	\$12,066
Assm: 12010402	Descr: Public Address For Large Warehouse	UOM:	SF	\$0.03	\$0.07	\$0.00	\$0.10
		Qty:	570584	\$16,889	\$40,968	\$0	\$57,857
Assm: 12010601	Descr: Clock System	UOM:	EA	\$222.34	\$177.74	\$0.00	\$400.08
		Qty:	25	\$5,559	\$4,444	\$0	\$10,002
Assm: 12010602	Descr: Time Clock System	UOM:	EA	\$334.18	\$866.03	\$0.00	\$1,200.22
		Qty:	9	\$3,008	\$7,794	\$0	\$10,802
Assm: 12020221	Descr: Battery Charger	UOM:	EA	\$1,043.18	\$619.45	\$0.00	\$1,662.63
		Qty:	34	\$35,468	\$21,061	\$0	\$56,529
Assm: 12020401	Descr: Lightning Protection System	UOM:	EA	\$78.54	\$141.38	\$0.00	\$219.92
		Qty:	30	\$2,356	\$4,241	\$0	\$6,598
Assm: 12020601	Descr: Energy Management Control System	UOM:	PTS	\$932.47	\$401.74	\$0.00	\$1,334.21
		Qty:	97	\$90,449	\$38,969	\$0	\$129,418

FSA: **ID:** CVN **Name:** COVERED EXTERIOR ENTRYWAY

Facility Type: Primary **ID:** 9 **Name:** UnClass Soil Storage Warehouse 1

Assm: 06039002	Descr: Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
		Qty:	108	\$623	\$705	\$0	\$1,327
Assm: 11020229	Descr: 100W Hps Wall Mount	UOM:	EA	\$175.34	\$236.30	\$0.00	\$411.64
		Qty:	1	\$175	\$236	\$0	\$412

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 11020235	Descr: 150 Watt Hps Recessed Fixture	UOM:	EA	\$215.09	\$246.25	\$0.00	\$461.34
		Qty:	1	\$215	\$246	\$0	\$461

FSA: ID: CVT **Name:** COVERED EXTERIOR LOADING DOCK W/LEVELER

Facility Type: Primary **ID:** 9 **Name:** UnClass Soil Storage Warehouse 1

Assm: 06039002	Descr: Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
		Qty:	1061	\$6,117	\$6,923	\$0	\$13,039

Assm: 11020136	Descr: Equipment Connections For Up To 5 HP	UOM:	EA	\$267.15	\$527.09	\$0.00	\$794.24
		Qty:	1	\$267	\$527	\$0	\$794

Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM:	EA	\$200.94	\$375.90	\$0.00	\$576.85
		Qty:	4	\$804	\$1,504	\$0	\$2,307

Assm: 11020280	Descr: Dock Lights	UOM:	EA	\$123.71	\$227.24	\$0.00	\$350.95
		Qty:	2	\$247	\$454	\$0	\$702

Assm: 13010602	Descr: 6'0" X 8'0" Long 10 Ton Capacity With Stairs	UOM:	DOCK	\$4,942.83	\$1,428.71	\$40.13	\$6,411.67
		Qty:	1	\$4,943	\$1,429	\$40	\$6,412

Assm: 13010606	Descr: 24" Deep Dock Leveler Pit Wall W/Stl Angle	UOM:	EA	\$483.17	\$1,116.94	\$1.04	\$1,601.14
		Qty:	1	\$483	\$1,117	\$1	\$1,601

FSA: ID: MEL **Name:** MECHANICAL, ELECTRICAL, & BUILDING SUPPORT

Facility Type: Primary **ID:** 9 **Name:** UnClass Soil Storage Warehouse 1

Assm: 05010114	Descr: Non-Load Bearing 8 X 8 X 16 Concrete Block	UOM:	SF	\$2.34	\$5.03	\$0.00	\$7.37
		Qty:	337	\$788	\$1,695	\$0	\$2,483

Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
		Qty:	668	\$192	\$479	\$0	\$671

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06030301	Descr: 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	UOM:	SF	\$0.32	\$0.59	\$0.00	\$0.92
		Qty:	56	\$18	\$33	\$0	\$51
Assm: 06030704	Descr: Suspension System For Gypsum Board Ceiling	UOM:	SF	\$0.75	\$4.08	\$0.00	\$4.83
		Qty:	56	\$42	\$228	\$0	\$270
Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
		Qty:	2	\$62	\$341	\$0	\$403
Assm: 11020156	Descr: 120V 20A Single Pole Switch	UOM:	EA	\$25.89	\$148.76	\$0.00	\$174.65
		Qty:	1	\$26	\$149	\$0	\$175
Assm: 11020276	Descr: Porcelain Lamp Holder	UOM:	EA	\$21.47	\$177.99	\$0.00	\$199.46
		Qty:	1	\$21	\$178	\$0	\$199

FSA: **ID:** SRM **Name:** STOCKROOM

Facility Type: Primary **ID:** 9 **Name:** UnClass Soil Storage Warehouse 1

Assm: 05010112	Descr: Non-Load Brg Partition Of 8 X 6 X 16 Concrete	UOM:	SF	\$1.97	\$3.68	\$0.00	\$5.65
		Qty:	18778	\$36,906	\$69,184	\$0	\$106,090
Assm: 05010126	Descr: Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	UOM:	SF	\$1.68	\$1.66	\$0.00	\$3.34
		Qty:	139792	\$234,655	\$231,565	\$0	\$466,220
Assm: 05010127	Descr: Wire Mesh Partitions, 4' Wide X 20' High	UOM:	SF	\$3.37	\$1.04	\$0.00	\$4.41
		Qty:	3901	\$13,144	\$4,039	\$0	\$17,184
Assm: 05039014	Descr: Sliding Metal Clad Door (With Motor)	UOM:	SF	\$35.54	\$9.59	\$0.00	\$45.13
		Qty:	7231	\$257,009	\$69,340	\$0	\$326,349
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
		Qty:	11265	\$3,235	\$8,084	\$0	\$11,319

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06029001	Descr: Concrete Floor Sealer	UOM: SF	\$0.04	\$0.05	\$0.00	\$0.08
		Qty: 568936	\$20,994	\$27,252	\$0	\$48,246
Assm: 06029003	Descr: Floor Hardener, Non-Metallic Light Service	UOM: SF	\$0.18	\$0.32	\$0.00	\$0.49
		Qty: 568936	\$101,441	\$179,727	\$0	\$281,168
Assm: 11020103	Descr: Duplex Receptacle Long Run	UOM: EA	\$48.69	\$297.44	\$0.00	\$346.13
		Qty: 240	\$11,687	\$71,386	\$0	\$83,072
Assm: 11020136	Descr: Equipment Connections For Up To 5 HP	UOM: EA	\$267.15	\$527.09	\$0.00	\$794.24
		Qty: 175	\$46,751	\$92,240	\$0	\$138,991
Assm: 11020229	Descr: 100W Hps Wall Mount	UOM: EA	\$175.34	\$236.30	\$0.00	\$411.64
		Qty: 72	\$12,625	\$17,013	\$0	\$29,638
Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM: EA	\$200.94	\$375.90	\$0.00	\$576.85
		Qty: 931	\$187,080	\$349,963	\$0	\$537,043
Assm: 11020255	Descr: High Bay 400W Hps Fixture With Quartz Standby	UOM: EA	\$296.72	\$467.99	\$0.00	\$764.70
		Qty: 125	\$37,089	\$58,498	\$0	\$95,588
Assm: 11020272	Descr: Exit Light With Battery Backup	UOM: EA	\$117.22	\$212.56	\$0.00	\$329.78
		Qty: 21	\$2,462	\$4,464	\$0	\$6,925

FSA: **ID:** **Name:** Building Shell

Facility Type: Supporting **ID:** 13 **Name:** MWL Storage Facility Office

Assm: 01010103	Descr: 1'0" X 3'0" Strip Footing 3000 PSI	UOM: LF	\$11.15	\$10.90	\$0.17	\$22.22
		Qty: 29	\$328	\$320	\$5	\$653
Assm: 01010105	Descr: 1'6" X 4'0" Strip Footing 3000 PSI	UOM: LF	\$21.62	\$17.86	\$0.29	\$39.77
		Qty: 69	\$1,483	\$1,225	\$20	\$2,728

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 01010201	Descr: Spread Footing	UOM: CY	\$73.57	\$45.75	\$2.16	\$121.48
		Qty: 4	\$294	\$183	\$9	\$486
Assm: 01010241	Descr: Spread Footing, Reinforcing Steel	UOM: TON	\$551.26	\$645.22	\$0.00	\$1,196.47
		Qty: 0	\$61	\$71	\$0	\$132
Assm: 01010277	Descr: Spread Footing Column Bolts	UOM: EA	\$1.22	\$4.37	\$0.00	\$5.59
		Qty: 28	\$34	\$122	\$0	\$156
Assm: 01029050	Descr: Tie Beams (Seismic Modification)	UOM: LF	\$14.64	\$18.55	\$0.16	\$33.35
		Qty: 130	\$1,897	\$2,405	\$21	\$4,323
Assm: 01030103	Descr: 6" Standard Slab On Grade	UOM: SF	\$1.70	\$2.17	\$0.16	\$4.03
		Qty: 5286	\$8,968	\$11,491	\$842	\$21,301
Assm: 01030601	Descr: Drainage	UOM: LF	\$2.28	\$5.23	\$0.39	\$7.89
		Qty: 188	\$428	\$983	\$73	\$1,484
Assm: 02020115	Descr: Med Span, Lt Ld, Stl Frm, Mtl Joist	UOM: SF	\$4.52	\$2.20	\$0.31	\$7.04
		Qty: 5286	\$23,918	\$11,639	\$1,642	\$37,199
Assm: 02020136	Descr: Structural Steel, Lt Load, Columns	UOM: SF	\$0.61	\$0.20	\$0.05	\$0.86
		Qty: 3491	\$2,139	\$706	\$163	\$3,008
Assm: 02020351	Descr: 102 MM (4") MEDIUMREINFORCED CONCRETE ROOF	UOM: SF	\$2.53	\$4.83	\$0.05	\$7.41
		Qty: 5286	\$13,389	\$25,511	\$260	\$39,160
Assm: 03010117	Descr: 8 X 8 X 16 Split Rib Block	UOM: SF	\$4.36	\$6.25	\$0.02	\$10.64
		Qty: 4698	\$20,506	\$29,360	\$109	\$49,974
Assm: 03010141	Descr: 3-5/8" Mtl. Stud Non-Load Bearing	UOM: SF	\$0.18	\$0.62	\$0.00	\$0.79
		Qty: 4698	\$827	\$2,890	\$0	\$3,717

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 03010147	Descr: Additional Vertical Reinforcement And Grouting; Seismic	UOM: SF	\$0.23	\$0.36	\$0.03	\$0.62
		Qty: 4698	\$1,078	\$1,700	\$118	\$2,896
Assm: 03010211	Descr: 4" Batt Insulation W/Vapor Barrier	UOM: SF	\$0.29	\$0.35	\$0.00	\$0.64
		Qty: 4698	\$1,350	\$1,650	\$0	\$3,000
Assm: 03010310	Descr: 5/8" Gypsum Board/Installed/Taped & Finished	UOM: SF	\$0.31	\$0.59	\$0.00	\$0.90
		Qty: 4698	\$1,436	\$2,793	\$0	\$4,230
Assm: 03010311	Descr: Paint to Gypsum Board Walls Using Roller	UOM: SF	\$0.10	\$0.28	\$0.00	\$0.38
		Qty: 4698	\$479	\$1,300	\$0	\$1,779
Assm: 03010501	Descr: Fixed Blade Exterior Louver With Baked Enamel Finish	UOM: SF	\$29.84	\$12.28	\$0.00	\$42.12
		Qty: 122	\$3,640	\$1,498	\$0	\$5,138
Assm: 03010801	Descr: Gypsum Plaster Exterior Soffits	UOM: SF	\$1.00	\$3.74	\$0.02	\$4.76
		Qty: 20	\$20	\$75	\$0	\$95
Assm: 03020172	Descr: 9.525 mm (3/8") Mono TTG	UOM: SF	\$26.00	\$8.47	\$0.00	\$34.47
		Qty: 1378	\$35,829	\$11,665	\$0	\$47,494
Assm: 03030104	Descr: 6'0" X 7'0" Pair Aluminum And Glass Doors With Transom	UOM: EA	\$1,483.46	\$890.91	\$0.00	\$2,374.37
		Qty: 1	\$1,483	\$891	\$0	\$2,374
Assm: 03030204	Descr: 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	UOM: EA	\$2,328.71	\$734.80	\$0.00	\$3,063.51
		Qty: 1	\$2,329	\$735	\$0	\$3,064
Assm: 03030250	Descr: 18 GA HM EXTERIOR DOOR 914 MM X 2134 MM (3'-0 X 7'-0)	UOM: EA	\$305.73	\$34.14	\$0.00	\$339.87
		Qty: 3	\$917	\$102	\$0	\$1,020
Assm: 04010108	Descr: Standing Seam Metal Roof	UOM: SF	\$2.03	\$1.26	\$0.00	\$3.29
		Qty: 5286	\$10,736	\$6,650	\$0	\$17,386

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 04010302	Descr: Rigid Insulation 1-1/2" Thick	UOM: SF	\$0.35	\$0.24	\$0.00	\$0.59
		Qty: 5286	\$1,862	\$1,274	\$0	\$3,137
Assm: 04010601	Descr: 5" Box Gutters With Downspouts	UOM: LF	\$1.59	\$3.61	\$0.00	\$5.20
		Qty: 77	\$123	\$279	\$0	\$402
Assm: 08020101	Descr: Copper Pipe & Fittings	UOM: EA	\$203.76	\$720.72	\$0.00	\$924.48
		Qty: 5	\$1,019	\$3,604	\$0	\$4,622
Assm: 08020201	Descr: Valves & Hydrants	UOM: EA	\$90.94	\$25.08	\$0.00	\$116.03
		Qty: 2	\$182	\$50	\$0	\$232
Assm: 08020401	Descr: Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	UOM: EA	\$78.67	\$82.34	\$0.00	\$161.01
		Qty: 5	\$393	\$412	\$0	\$805
Assm: 08020502	Descr: Domestic Water Supply Specialties, 1"	UOM: EA	\$136.23	\$39.26	\$0.00	\$175.49
		Qty: 1	\$136	\$39	\$0	\$175
Assm: 08030101	Descr: Waste Pipe & Fittings	UOM: EA	\$180.14	\$361.88	\$0.00	\$542.02
		Qty: 6	\$1,081	\$2,171	\$0	\$3,252
Assm: 08030201	Descr: C.I. No Hub Vent Pipe System	UOM: EA	\$10.99	\$57.80	\$0.00	\$68.80
		Qty: 5	\$55	\$289	\$0	\$344
Assm: 08030303	Descr: Medium Duty And Heavy Duty Cast Iron Floor Drains	UOM: EA	\$283.27	\$71.63	\$0.00	\$354.90
		Qty: 1	\$283	\$72	\$0	\$355
Assm: 09010206	Descr: 900 MBH Gas Supply	UOM: EA	\$1,779.16	\$2,109.91	\$0.00	\$3,889.07
		Qty: 1	\$1,779	\$2,110	\$0	\$3,889
Assm: 09020215	Descr: HOT WATER BOILER, GAS FIRED 203 MBH	UOM: EA	\$1,755.65	\$1,085.34	\$0.00	\$2,840.99
		Qty: 1	\$1,756	\$1,085	\$0	\$2,841

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 09030102	Descr: 20 Ton Air Cooled Recip. Chiller W/Mech. Room Piping	UOM: EA	\$24,028.22	\$10,209.00	\$7.16	\$34,244.37
		Qty: 1	\$24,028	\$10,209	\$7	\$34,244
Assm: 09040302	Descr: Hot And Chilled Water Distribution System - 540 MBH	UOM: MBH	\$12.68	\$14.26	\$0.00	\$26.93
		Qty: 142	\$1,800	\$2,024	\$0	\$3,825
Assm: 09040720	Descr: Ventilation System, Mechanical Room 4.695 MCFM	UOM: MCFM	\$228.93	\$60.10	\$0.00	\$289.04
		Qty: 1	\$114	\$30	\$0	\$145
Assm: 09049001	Descr: Exhaust Ventilation System	UOM: MCFM	\$231.80	\$77.09	\$0.00	\$308.89
		Qty: 1	\$130	\$43	\$0	\$173
Assm: 09049902	Descr: .8 MCFM AIR DIST SYS FOR FAN COIL UNIT	UOM: MCFM	\$3,444.79	\$1,186.52	\$0.00	\$4,631.30
		Qty: 0	\$276	\$95	\$0	\$371
Assm: 09049906	Descr: 0 - .3 MCFM Vav Assembly	UOM: MCFM	\$1,285.27	\$1,323.87	\$0.00	\$2,609.14
		Qty: 1	\$655	\$675	\$0	\$1,331
Assm: 09049907	Descr: Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	UOM: MCFM	\$1,370.16	\$1,955.73	\$0.00	\$3,325.89
		Qty: 2	\$2,727	\$3,892	\$0	\$6,619
Assm: 09049908	Descr: Air Dist Sys .8 - 1.2 MCFM Vav With Hot Water Heating	UOM: MCFM	\$1,287.00	\$2,135.60	\$0.00	\$3,422.61
		Qty: 3	\$4,144	\$6,877	\$0	\$11,021
Assm: 09049909	Descr: Air Dist Sys 1.2 - 2.8 MCFM Vav With Hot Water Heating	UOM: MCFM	\$1,242.71	\$2,340.45	\$0.00	\$3,583.16
		Qty: 4	\$4,673	\$8,800	\$0	\$13,473
Assm: 09049938	Descr: 7.5-9.2 MCFM AHU Low Pressure W/Vav Boxes	UOM: MCFM	\$1,375.34	\$2,640.94	\$0.00	\$4,016.29
		Qty: 1	\$1,252	\$2,403	\$0	\$3,655
Assm: 09049945	Descr: 13.2 MCFM A.D.S. WITH RETURN AIR FAN	UOM: MCFM	\$1,284.64	\$1,472.93	\$0.00	\$2,757.57
		Qty: 1	\$1,683	\$1,930	\$0	\$3,612

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 09049953	Descr: Air Dist, 20 MCFM Air Handler, Med Pressure Supply	UOM: MCFM		\$2,309.17	\$4,605.55	\$0.00	\$6,914.72
		Qty: 2		\$5,057	\$10,086	\$0	\$15,143
Assm: 09060101	Descr: Vav Boxes Controls, Portion Of Electric A.C. Controls	UOM: EA		\$1,783.44	\$1,630.37	\$0.00	\$3,413.81
		Qty: 9		\$16,051	\$14,673	\$0	\$30,724
Assm: 09060149	Descr: Heat Generation System Controls For Heat Exchgr, Xtra	UOM: EA		\$2,928.43	\$608.69	\$0.00	\$3,537.12
		Qty: 1		\$2,928	\$609	\$0	\$3,537
Assm: 09060175	Descr: Cooling Generation System Controls	UOM: EA		\$1,815.28	\$943.55	\$0.00	\$2,758.83
		Qty: 1		\$1,815	\$944	\$0	\$2,759
Assm: 09070101	Descr: Water Test & Balance Water Main Balancing Valves	UOM: EA		\$0.00	\$52.51	\$0.00	\$52.51
		Qty: 1		\$0	\$53	\$0	\$53
Assm: 09070103	Descr: Water, Test & Balance Air Cooled Condenser	UOM: EA		\$0.00	\$122.56	\$0.00	\$122.56
		Qty: 1		\$0	\$123	\$0	\$123
Assm: 09070107	Descr: Water, Test & Balance Fan Coil, Fin Tube	UOM: EA		\$0.00	\$70.02	\$0.00	\$70.02
		Qty: 21		\$0	\$1,470	\$0	\$1,470
Assm: 09070109	Descr: Water, Test & Balance Pump	UOM: EA		\$0.00	\$154.05	\$0.00	\$154.05
		Qty: 1		\$0	\$154	\$0	\$154
Assm: 09070201	Descr: Test & Balance, Cent Fan/Utility Set	UOM: EA		\$0.00	\$206.44	\$0.00	\$206.44
		Qty: 1		\$0	\$206	\$0	\$206
Assm: 09070206	Descr: Test & Balance Air Handler, Low Pressure	UOM: EA		\$0.00	\$413.28	\$0.00	\$413.28
		Qty: 1		\$0	\$413	\$0	\$413
Assm: 09070211	Descr: Test & Balance Vav Box	UOM: EA		\$39.90	\$68.74	\$0.00	\$108.64
		Qty: 7		\$279	\$481	\$0	\$760

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 09070212	Descr: Test & Balance Register Average Ceiling Height	UOM:	EA	\$0.00	\$41.31	\$0.00	\$41.31
		Qty:	58	\$0	\$2,396	\$0	\$2,396
Assm: 10010105	Descr: Fire Protection Water Supply	UOM:	EA	\$37.08	\$6.70	\$0.00	\$43.77
		Qty:	46	\$1,705	\$308	\$0	\$2,014
Assm: 10020102	Descr: Concealed Sprinkler Heads, Pipes & Fittings - Ord. Haz.	UOM:	EA	\$45.50	\$128.81	\$0.00	\$174.31
		Qty:	46	\$2,093	\$5,925	\$0	\$8,018
Assm: 10030101	Descr: 6" Standpipe System	UOM:	EA	\$997.75	\$371.80	\$0.00	\$1,369.55
		Qty:	1	\$998	\$372	\$0	\$1,370
Assm: 10040101	Descr: 5 Pound All Purpose Abc Type Fire Extinguishers	UOM:	EA	\$39.56	\$20.19	\$0.00	\$59.76
		Qty:	2	\$79	\$40	\$0	\$120
Assm: 11010101	Descr: Undergrd 200 Amp Main Transformer	UOM:	EA	\$8,818.14	\$1,739.91	\$33.61	\$10,591.66
		Qty:	1	\$8,818	\$1,740	\$34	\$10,592
Assm: 11010204	Descr: Undergrd 200 Amp Secondary	UOM:	EA	\$1,270.14	\$1,438.27	\$10.07	\$2,718.48
		Qty:	1	\$1,270	\$1,438	\$10	\$2,718
Assm: 11010304	Descr: Undergrd 200 Amp Main Switchboard	UOM:	EA	\$12,768.04	\$1,722.21	\$0.00	\$14,490.25
		Qty:	1	\$12,768	\$1,722	\$0	\$14,490
Assm: 11010401	Descr: (10-30 Amps 480V) 25 KVA Dry Type Transformer	UOM:	EA	\$1,291.40	\$674.69	\$0.00	\$1,966.09
		Qty:	2	\$2,583	\$1,349	\$0	\$3,932
Assm: 11010501	Descr: Panelbd 208V 100A 24 Cir Mlo W/Bkr	UOM:	EA	\$882.61	\$1,140.56	\$0.00	\$2,023.17
		Qty:	1	\$883	\$1,141	\$0	\$2,023
Assm: 11010506	Descr: Panelbd 208V 225A 36 Cir Mlo W/Bkr	UOM:	EA	\$1,554.41	\$2,086.31	\$0.00	\$3,640.72
		Qty:	1	\$1,554	\$2,086	\$0	\$3,641

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 11010507	Descr: Panelbd 208V 225A 42 Cir Mlo W/Bkr	UOM:	EA	\$1,772.16	\$2,235.15	\$0.00	\$4,007.30
		Qty:	1	\$1,772	\$2,235	\$0	\$4,007
Assm: 11010536	Descr: Panelbd 480V 225A 36 Cir Mlo W/Bkr	UOM:	EA	\$2,296.82	\$2,123.79	\$0.00	\$4,420.61
		Qty:	1	\$2,297	\$2,124	\$0	\$4,421
Assm: 11010602	Descr: Enclosed Cir Bkr 600V 60A	UOM:	EA	\$691.57	\$1,188.21	\$0.00	\$1,879.78
		Qty:	1	\$692	\$1,188	\$0	\$1,880
Assm: 11010609	Descr: Enclosed Cir Bkr 600V 30A	UOM:	EA	\$260.10	\$281.26	\$0.00	\$541.36
		Qty:	2	\$520	\$563	\$0	\$1,083
Assm: 11010701	Descr: MCC Starter 10HP (20-30 Amps) Fvnr Size 1	UOM:	EA	\$1,067.87	\$581.73	\$0.00	\$1,649.60
		Qty:	2	\$2,136	\$1,163	\$0	\$3,299
Assm: 11010702	Descr: MCC Starter 25HP (60-80 Amps) Fvnr Size 2	UOM:	EA	\$1,511.61	\$655.73	\$0.00	\$2,167.34
		Qty:	1	\$1,512	\$656	\$0	\$2,167
Assm: 12010102	Descr: Fire Alarm System - Rate Of Rise Heat Detectors	UOM:	OUT	\$102.32	\$374.83	\$0.00	\$477.15
		Qty:	5	\$512	\$1,874	\$0	\$2,386
Assm: 12010112	Descr: 8 Zone Fire Alarm Panel And Remote Annunciator	UOM:	EA	\$1,423.01	\$1,578.16	\$0.00	\$3,001.17
		Qty:	1	\$1,423	\$1,578	\$0	\$3,001
Assm: 12010301	Descr: Telephone System, 2 Pair	UOM:	EA	\$42.39	\$176.98	\$0.00	\$219.38
		Qty:	32	\$1,357	\$5,663	\$0	\$7,020
Assm: 12010401	Descr: Sound And Public Address	UOM:	SF	\$0.44	\$0.30	\$0.00	\$0.75
		Qty:	5286	\$2,351	\$1,612	\$0	\$3,962
Assm: 12010601	Descr: Clock System	UOM:	EA	\$222.34	\$177.74	\$0.00	\$400.08
		Qty:	1	\$222	\$178	\$0	\$400

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 12020231	Descr: Exit Lighting	UOM:	EA	\$118.06	\$331.48	\$0.00	\$449.54
		Qty:	3	\$354	\$994	\$0	\$1,349
Assm: 12020303	Descr: Transformer Grounding	UOM:	EA	\$40.06	\$100.74	\$0.00	\$140.80
		Qty:	1	\$40	\$101	\$0	\$141
Assm: 12020401	Descr: Lightning Protection System	UOM:	EA	\$78.54	\$141.38	\$0.00	\$219.92
		Qty:	5	\$393	\$707	\$0	\$1,100
Assm: 12020601	Descr: Energy Management Control System	UOM:	PTS	\$932.47	\$401.74	\$0.00	\$1,334.21
		Qty:	6	\$5,595	\$2,410	\$0	\$8,005
FSA:	ID: BSP	Name:	BUILDING SUPPORT AREA				
Facility Type:	Supporting	ID: 13	Name:	MWL Storage Facility Office			
Assm: 05010101	Descr: Mtl Stud Partition, 3-5/8"	UOM:	SF	\$0.18	\$0.62	\$0.00	\$0.79
		Qty:	5	\$1	\$3	\$0	\$4
Assm: 05010102	Descr: Mtl Stud Partition, 3-5/8", Sound Rated	UOM:	SF	\$0.59	\$0.94	\$0.00	\$1.54
		Qty:	22	\$13	\$21	\$0	\$34
Assm: 05010112	Descr: Non-Load Brg Partition Of 8 X 6 X 16 Concrete	UOM:	SF	\$1.97	\$3.68	\$0.00	\$5.65
		Qty:	11	\$22	\$41	\$0	\$62
Assm: 05010113	Descr: Non-Load Brg Partition Of 8 X 8 X 16 Concrete	UOM:	SF	\$2.08	\$3.86	\$0.00	\$5.94
		Qty:	71	\$148	\$274	\$0	\$422
Assm: 05010401	Descr: Aluminum Balcony Rail	UOM:	LF	\$81.26	\$18.89	\$0.40	\$100.55
		Qty:	1	\$81	\$19	\$0	\$101
Assm: 05010504	Descr: Fixed Type Window With Aluminum Frm - 3/4" Clear Glass	UOM:	SF	\$16.81	\$6.30	\$0.00	\$23.11
		Qty:	2	\$34	\$13	\$0	\$46

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 05010601	Descr: Storefront With Lt Aluminum Frm - 3/8" Clear Glass	UOM:	SF	\$13.29	\$10.81	\$0.00	\$24.11
		Qty:	3	\$40	\$32	\$0	\$72
Assm: 05040101	Descr: Urinal Screens	UOM:	EA	\$111.66	\$62.36	\$0.00	\$174.02
		Qty:	1	\$112	\$62	\$0	\$174
Assm: 05040102	Descr: Toilet Partition And Accessories	UOM:	EA	\$708.99	\$197.03	\$0.00	\$906.02
		Qty:	1	\$709	\$197	\$0	\$906
Assm: 05040106	Descr: Lavaratory Accessories	UOM:	EA	\$409.42	\$46.78	\$0.00	\$456.20
		Qty:	1	\$409	\$47	\$0	\$456
Assm: 05040301	Descr: Porcelain Enamel Chalkboard	UOM:	SF	\$16.66	\$22.28	\$0.00	\$38.94
		Qty:	1	\$17	\$22	\$0	\$39
Assm: 05040403	Descr: Bronze Letters With Satin Finish 8" High	UOM:	EA	\$34.43	\$22.28	\$0.00	\$56.71
		Qty:	1	\$34	\$22	\$0	\$57
Assm: 05040406	Descr: Aluminum Framed Glass Covered Directory Board	UOM:	EA	\$161.15	\$267.31	\$0.00	\$428.47
		Qty:	1	\$161	\$267	\$0	\$428
Assm: 05040601	Descr: 10" Wide Stock Prefinished Shelves With Supports	UOM:	LF	\$3.84	\$4.29	\$0.00	\$8.13
		Qty:	1	\$4	\$4	\$0	\$8
Assm: 06010301	Descr: 5/8" Gypsum Board On 7/8" Furring Channel	UOM:	SF	\$0.73	\$3.09	\$0.00	\$3.83
		Qty:	17	\$12	\$53	\$0	\$65
Assm: 06010303	Descr: Two Layers Of 5/8" Fire Resistant Gypsum Board	UOM:	SF	\$1.04	\$1.29	\$0.00	\$2.33
		Qty:	3	\$3	\$4	\$0	\$7
Assm: 06010304	Descr: 5/8" Gypsum Board/Installed/Taped & Finished	UOM:	SF	\$0.31	\$0.59	\$0.00	\$0.90
		Qty:	8	\$2	\$5	\$0	\$7

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06010401	Descr: 4-1/4" X 4-1/4" Ceramic Tile To Walls	UOM:	SF	\$2.53	\$2.54	\$0.00	\$5.07
		Qty:	27	\$68	\$69	\$0	\$137
Assm: 06010501	Descr: Paint To Gypsum Board Walls Using Roller	UOM:	SF	\$0.10	\$0.28	\$0.00	\$0.38
		Qty:	53	\$5	\$15	\$0	\$20
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
		Qty:	49	\$14	\$35	\$0	\$49
Assm: 06010602	Descr: Medium Weight Vinyl Wallcovering With Fabric Backing	UOM:	SF	\$0.63	\$0.55	\$0.00	\$1.18
		Qty:	24	\$15	\$13	\$0	\$28
Assm: 06020101	Descr: Thin Set Natural Clay Ceramic Tile Floor And Base	UOM:	SF	\$6.69	\$3.84	\$0.00	\$10.53
		Qty:	15	\$100	\$58	\$0	\$158
Assm: 06020401	Descr: Vinyl Tile 1/8" X 12" X 12"	UOM:	SF	\$2.96	\$0.82	\$0.00	\$3.78
		Qty:	7	\$21	\$6	\$0	\$26
Assm: 06020501	Descr: Commercial Grade 26 Oz. Nylon Carpet	UOM:	SY	\$14.84	\$6.16	\$0.00	\$21.00
		Qty:	4	\$59	\$25	\$0	\$84
Assm: 06020601	Descr: Floor Pavers 8x4, 1" To 1-1/4" Thick	UOM:	SF	\$3.06	\$9.31	\$0.00	\$12.37
		Qty:	13	\$40	\$121	\$0	\$161
Assm: 06030302	Descr: 5/8" Gypsum Wallboard Ceiling, 3 Layers, Over 8 Ft.	UOM:	SF	\$0.78	\$1.47	\$0.00	\$2.25
		Qty:	26	\$20	\$38	\$0	\$58
Assm: 06030402	Descr: 2' X 2' Or 2' X 4' Fiberglass Acoustical Ceiling Tiles	UOM:	SF	\$0.43	\$0.42	\$0.00	\$0.85
		Qty:	56	\$24	\$23	\$0	\$47
Assm: 06030601	Descr: Painting To Drywall Or Plaster Using Rollers, 2 Coats	UOM:	SF	\$0.10	\$0.28	\$0.00	\$0.38
		Qty:	26	\$3	\$7	\$0	\$10

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06030703	Descr: T-Bar Ceiling Suspension System 2' X 4' Grid	UOM: SF	\$0.31	\$0.37	\$0.00	\$0.67
		Qty: 56	\$17	\$21	\$0	\$38
Assm: 06030704	Descr: Suspension System For Gypsum Board Ceiling	UOM: SF	\$0.75	\$4.08	\$0.00	\$4.83
		Qty: 26	\$20	\$106	\$0	\$126
Assm: 11020101	Descr: 120 Volt, 20 Amp Duplex Receptacle - Stud Partition	UOM: EA	\$26.43	\$164.10	\$0.00	\$190.53
		Qty: 2	\$53	\$328	\$0	\$381
Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM: EA	\$31.01	\$170.59	\$0.00	\$201.60
		Qty: 1	\$31	\$171	\$0	\$202
Assm: 11020107	Descr: 120 Volt, 15 Amp Duplex Ground Fault Receptacle	UOM: EA	\$51.22	\$154.98	\$0.00	\$206.20
		Qty: 1	\$51	\$155	\$0	\$206
Assm: 11020137	Descr: Equipment Connections For Up To 10 HP	UOM: EA	\$301.38	\$572.98	\$0.00	\$874.36
		Qty: 1	\$301	\$573	\$0	\$874
Assm: 11020138	Descr: 480 Volt Equipment Connections For Motors - 15 To 25 HP	UOM: EA	\$342.85	\$508.54	\$0.00	\$851.40
		Qty: 1	\$343	\$509	\$0	\$851
Assm: 11020139	Descr: 480 Volt Equipment Connections For Motors - 30 TO 40 HP	UOM: EA	\$370.76	\$524.17	\$0.00	\$894.93
		Qty: 1	\$371	\$524	\$0	\$895
Assm: 11020201	Descr: Four Foot Strip Fluorescent Fixture	UOM: EA	\$54.85	\$176.03	\$0.00	\$230.87
		Qty: 1	\$55	\$176	\$0	\$231
Assm: 11020202	Descr: 2' X 4' Lay-In Fluorescent Fixture	UOM: EA	\$69.29	\$182.23	\$0.00	\$251.52
		Qty: 1	\$69	\$182	\$0	\$252
Assm: 11020220	Descr: Ceiling Recessed Incandescent 100 Watt Fixture	UOM: EA	\$72.89	\$144.66	\$0.00	\$217.55
		Qty: 1	\$73	\$145	\$0	\$218

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>		
Assm:	11029011	Descr:	Fire Alarm Pull Station	UOM:	EA	\$41.30	\$155.77	\$0.00	\$197.07
				Qty:	1	\$41	\$156	\$0	\$197

FSA: **ID:** DET **Name:** DEPOT MAINTENANCE ROOM

Facility Type: Supporting **ID:** 13 **Name:** MWL Storage Facility Office

Assm:	05010113	Descr:	Non-Load Brg Partition Of 8 X 8 X 16 Concrete	UOM:	SF	\$2.08	\$3.86	\$0.00	\$5.94
				Qty:	2493	\$5,195	\$9,616	\$0	\$14,811

Assm:	05020101	Descr:	3'0" X 7'0" Hollow Metal Door	UOM:	EA	\$441.64	\$173.13	\$0.00	\$614.77
				Qty:	2	\$883	\$346	\$0	\$1,230

Assm:	05030101	Descr:	Coiling Overhead Door	UOM:	EA	\$1,101.78	\$1,107.72	\$0.00	\$2,209.50
				Qty:	3	\$3,305	\$3,323	\$0	\$6,629

Assm:	06010502	Descr:	Paint To Concrete Block Using Brushes, Two Coats	UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
				Qty:	2063	\$592	\$1,480	\$0	\$2,073

Assm:	06020801	Descr:	Epoxy Floor Coating	UOM:	SF	\$2.87	\$2.58	\$0.10	\$5.56
				Qty:	1800	\$5,169	\$4,650	\$187	\$10,005

Assm:	11020103	Descr:	Duplex Receptacle Long Run	UOM:	EA	\$48.69	\$297.44	\$0.00	\$346.13
				Qty:	15	\$730	\$4,462	\$0	\$5,192

Assm:	11020136	Descr:	Equipment Connections For Up To 5 HP	UOM:	EA	\$267.15	\$527.09	\$0.00	\$794.24
				Qty:	3	\$801	\$1,581	\$0	\$2,383

Assm:	11020254	Descr:	High Bay 400W Hps Fixture	UOM:	EA	\$200.94	\$375.90	\$0.00	\$576.85
				Qty:	7	\$1,407	\$2,631	\$0	\$4,038

Assm:	11020255	Descr:	High Bay 400W Hps Fixture With Quartz Standby	UOM:	EA	\$296.72	\$467.99	\$0.00	\$764.70
				Qty:	2	\$593	\$936	\$0	\$1,529

FSA: **ID:** DPS **Name:** DATA SUPPLY ROOM

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Facility Type:	Supporting	ID: 13	Name: MWL Storage Facility Office				
Assm: 05010101	Descr: Mtl Stud Partition, 3-5/8"			UOM: SF	\$0.18	\$0.62	\$0.00
				Qty: 188	\$33	\$116	\$0
Assm: 05020208	Descr: 3'0" X 7'0" S.C. Wood Door W/Wd. Frame & Glazing			UOM: EA	\$439.36	\$209.37	\$0.00
				Qty: 1	\$439	\$209	\$0
Assm: 06010302	Descr: 5/8" Gypsum Board On Furring Channel W/Rigid Insulation			UOM: SF	\$0.85	\$3.24	\$0.00
				Qty: 607	\$516	\$1,965	\$0
Assm: 06010304	Descr: 5/8" Gypsum Board/Installed/Taped & Finished			UOM: SF	\$0.31	\$0.59	\$0.00
				Qty: 416	\$127	\$247	\$0
Assm: 06010501	Descr: Paint To Gypsum Board Walls Using Roller			UOM: SF	\$0.10	\$0.28	\$0.00
				Qty: 94	\$10	\$26	\$0
Assm: 06010701	Descr: 4' X 8' X 1" Fiberglass Sound Absorbing Panels			UOM: SF	\$1.56	\$0.58	\$0.00
				Qty: 929	\$1,446	\$543	\$0
Assm: 06020502	Descr: Commercial Grade 35 Oz. Nylon			UOM: SY	\$18.07	\$6.16	\$0.00
				Qty: 64	\$1,156	\$394	\$0
Assm: 06030402	Descr: 2' X 2' Or 2' X 4' Fiberglass Acoustical Ceiling Tiles			UOM: SF	\$0.43	\$0.42	\$0.00
				Qty: 576	\$246	\$241	\$0
Assm: 06030703	Descr: T-Bar Ceiling Suspension System 2' X 4' Grid			UOM: SF	\$0.31	\$0.37	\$0.00
				Qty: 576	\$176	\$213	\$0
Assm: 11020103	Descr: Duplex Receptacle Long Run			UOM: EA	\$48.69	\$297.44	\$0.00
				Qty: 7	\$341	\$2,082	\$0
Assm: 11020205	Descr: Fluorescent Troffer W/Parabolic Baffle			UOM: EA	\$66.91	\$186.76	\$0.00
				Qty: 10	\$669	\$1,868	\$0

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>		
FSA:	ID: FLS	Name:	FIRE STATION LOCKERS AND SHOWERS						
Facility Type:	Supporting	ID: 13	Name:	MWL Storage Facility Office					
Assm:	05010118	Descr:	8 X 8 X 16 Load Bearing Concrete Masonry Unit Wall	UOM:	SF	\$4.07	\$5.38	\$0.02	\$9.47
				Qty:	334	\$1,359	\$1,798	\$8	\$3,164
Assm:	05020101	Descr:	3'0" X 7'0" Hollow Metal Door	UOM:	EA	\$441.64	\$173.13	\$0.00	\$614.77
				Qty:	1	\$442	\$173	\$0	\$615
Assm:	05020116	Descr:	3'0" X 7'0" S.C. Wood Door W/H.M. Frame W/Passage Set	UOM:	EA	\$214.34	\$167.64	\$0.00	\$381.99
				Qty:	1	\$214	\$168	\$0	\$382
Assm:	05040101	Descr:	Urinal Screens	UOM:	EA	\$111.66	\$62.36	\$0.00	\$174.02
				Qty:	1	\$112	\$62	\$0	\$174
Assm:	05040102	Descr:	Toilet Partition And Accessories	UOM:	EA	\$708.99	\$197.03	\$0.00	\$906.02
				Qty:	1	\$709	\$197	\$0	\$906
Assm:	05040401	Descr:	Door Sign, 3" X 8"	UOM:	EA	\$8.77	\$7.35	\$0.00	\$16.12
				Qty:	1	\$9	\$7	\$0	\$16
Assm:	05040501	Descr:	12" X 15" X 36" Double Tier Lockers	UOM:	EA	\$70.41	\$8.44	\$0.00	\$78.84
				Qty:	8	\$563	\$67	\$0	\$631
Assm:	05050201	Descr:	Plastic Laminate Cabinets With Countertop And Drawers	UOM:	LF	\$135.86	\$32.22	\$0.00	\$168.08
				Qty:	6	\$815	\$193	\$0	\$1,008
Assm:	05050204	Descr:	Bathroom Vanity 30" Wide X 24" Deep X 34" High	UOM:	LF	\$91.83	\$22.89	\$0.00	\$114.71
				Qty:	6	\$551	\$137	\$0	\$688
Assm:	06010311	Descr:	1/2" WP Gypsum Board/Installed/Taped & Finished	UOM:	SF	\$0.35	\$0.59	\$0.00	\$0.94
				Qty:	516	\$179	\$307	\$0	\$486

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06010401	Descr: 4-1/4" X 4-1/4" Ceramic Tile To Walls	UOM: SF		\$2.53	\$2.54	\$0.00	\$5.07
		Qty: 735		\$1,859	\$1,869	\$0	\$3,727
Assm: 06010505	Descr: Paint To Concrete Walls-One Coat Primer, One Coat Paint	UOM: SF		\$0.19	\$0.53	\$0.00	\$0.72
		Qty: 333		\$62	\$178	\$0	\$239
Assm: 06020101	Descr: Thin Set Natural Clay Ceramic Tile Floor And Base	UOM: SF		\$6.69	\$3.84	\$0.00	\$10.53
		Qty: 280		\$1,874	\$1,074	\$0	\$2,948
Assm: 06030301	Descr: 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	UOM: SF		\$0.32	\$0.59	\$0.00	\$0.92
		Qty: 336		\$108	\$200	\$0	\$308
Assm: 06030601	Descr: Painting To Drywall Or Plaster Using Rollers, 2 Coats	UOM: SF		\$0.10	\$0.28	\$0.00	\$0.38
		Qty: 336		\$34	\$93	\$0	\$127
Assm: 06030704	Descr: Suspension System For Gypsum Board Ceiling	UOM: SF		\$0.75	\$4.08	\$0.00	\$4.83
		Qty: 336		\$252	\$1,371	\$0	\$1,623
Assm: 08010101	Descr: Floor Mounted Water Closet	UOM: EA		\$117.80	\$120.14	\$0.00	\$237.94
		Qty: 1		\$118	\$120	\$0	\$238
Assm: 08010201	Descr: Floor Mounted Urinal	UOM: EA		\$446.88	\$254.69	\$0.00	\$701.56
		Qty: 1		\$447	\$255	\$0	\$702
Assm: 08010303	Descr: Wall Hung 20" By 18" White Single Bowl Lavatory	UOM: EA		\$346.08	\$304.54	\$0.00	\$650.62
		Qty: 1		\$346	\$305	\$0	\$651
Assm: 08010407	Descr: Janitor Sink - Floor Type	UOM: EA		\$468.25	\$144.70	\$0.00	\$612.95
		Qty: 1		\$468	\$145	\$0	\$613
Assm: 08010502	Descr: Shower Valve, Drain For Ceramic Tile Shower	UOM: EA		\$563.55	\$937.27	\$0.00	\$1,500.82
		Qty: 2		\$1,127	\$1,875	\$0	\$3,002

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 08010508	Descr: Fiberglass Shower Unit	UOM:	EA	\$338.53	\$265.30	\$0.00	\$603.82
		Qty:	2	\$677	\$531	\$0	\$1,208
Assm: 08010601	Descr: 8 GPH Electric Water Cooler - Wall Mounted	UOM:	EA	\$531.74	\$159.18	\$0.00	\$690.92
		Qty:	1	\$532	\$159	\$0	\$691
Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
		Qty:	2	\$62	\$341	\$0	\$403
Assm: 11020105	Descr: 120V Clock Receptacle	UOM:	EA	\$38.58	\$166.65	\$0.00	\$205.22
		Qty:	1	\$39	\$167	\$0	\$205
Assm: 11020108	Descr: Duplex GFI Receptacle Long Run	UOM:	EA	\$68.91	\$281.83	\$0.00	\$350.73
		Qty:	1	\$69	\$282	\$0	\$351
Assm: 11020109	Descr: 120V, 20 Amp Duplex Ground Fault Receptacle	UOM:	EA	\$32.43	\$173.15	\$0.00	\$205.59
		Qty:	1	\$32	\$173	\$0	\$206
Assm: 11020158	Descr: Thermal Motor Switch	UOM:	EA	\$24.57	\$160.34	\$0.00	\$184.91
		Qty:	1	\$25	\$160	\$0	\$185
Assm: 11020209	Descr: Surface Mount 2' X 4' Fluorescent Fixture	UOM:	EA	\$90.67	\$205.07	\$0.00	\$295.75
		Qty:	2	\$181	\$410	\$0	\$591
Assm: 11020210	Descr: 4' Vapor Tight Fluorescent Fixture	UOM:	EA	\$105.85	\$197.68	\$0.00	\$303.53
		Qty:	8	\$847	\$1,581	\$0	\$2,428
Assm: 11020272	Descr: Exit Light With Battery Backup	UOM:	EA	\$117.22	\$212.56	\$0.00	\$329.78
		Qty:	1	\$117	\$213	\$0	\$330
Assm: 11020274	Descr: 6V Emergency Battery Pack	UOM:	EA	\$75.96	\$241.46	\$0.00	\$317.42
		Qty:	1	\$76	\$241	\$0	\$317

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	13011509	Descr:	Oak Bench - 42"	UOM:	EA	\$373.19	\$15.59	\$0.00	\$388.78
				Qty:	2	\$746	\$31	\$0	\$778
Assm:	15900111	Descr:	SAUNA	UOM:	SF	\$66.86	\$8.68	\$0.00	\$75.54
				Qty:	13	\$869	\$113	\$0	\$982
FSA:	ID: KSM	Name:	KITCHEN (SMALL)						
Facility Type:	Supporting	ID: 13	Name:	MWL Storage Facility Office					
Assm:	05010102	Descr:	Mtl Stud Partition, 3-5/8", Sound Rated	UOM:	SF	\$0.59	\$0.94	\$0.00	\$1.54
				Qty:	291	\$173	\$274	\$0	\$447
Assm:	05050101	Descr:	Plastic Laminate Countertop With Backsplash	UOM:	LF	\$4.61	\$10.00	\$0.00	\$14.61
				Qty:	9	\$41	\$90	\$0	\$132
Assm:	05050220	Descr:	Plastic Laminated Wall Cabinet - 30" High, 12" Deep	UOM:	LF	\$55.77	\$7.50	\$0.00	\$63.27
				Qty:	4	\$204	\$27	\$0	\$232
Assm:	05050222	Descr:	Plastic Laminated Base Cabinet - 24" Deep	UOM:	LF	\$76.05	\$15.00	\$0.00	\$91.04
				Qty:	9	\$710	\$140	\$0	\$850
Assm:	06010304	Descr:	5/8" Gypsum Board/Installed/Taped & Finished	UOM:	SF	\$0.31	\$0.59	\$0.00	\$0.90
				Qty:	262	\$80	\$156	\$0	\$236
Assm:	06010501	Descr:	Paint To Gypsum Board Walls Using Roller	UOM:	SF	\$0.10	\$0.28	\$0.00	\$0.38
				Qty:	262	\$27	\$73	\$0	\$99
Assm:	06020404	Descr:	Sheet Vinyl Resilient Flooring	UOM:	SF	\$2.58	\$1.16	\$0.00	\$3.73
				Qty:	89	\$229	\$103	\$0	\$332
Assm:	06030301	Descr:	5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	UOM:	SF	\$0.32	\$0.59	\$0.00	\$0.92
				Qty:	120	\$39	\$71	\$0	\$110

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06030601	Descr: Painting To Drywall Or Plaster Using Rollers, 2 Coats	UOM:	SF	\$0.10	\$0.28	\$0.00	\$0.38
		Qty:	120	\$12	\$33	\$0	\$45
Assm: 06030704	Descr: Suspension System For Gypsum Board Ceiling	UOM:	SF	\$0.75	\$4.08	\$0.00	\$4.83
		Qty:	120	\$90	\$490	\$0	\$580
Assm: 08010402	Descr: S.S. Sink, Double Bowl 32 X 21 X 7	UOM:	EA	\$438.37	\$132.65	\$0.00	\$571.02
		Qty:	1	\$438	\$133	\$0	\$571
Assm: 11020101	Descr: 120 Volt, 20 Amp Duplex Receptacle - Stud Partition	UOM:	EA	\$26.43	\$164.10	\$0.00	\$190.53
		Qty:	2	\$53	\$328	\$0	\$381
Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
		Qty:	1	\$31	\$171	\$0	\$202
Assm: 11020109	Descr: 120V, 20 Amp Duplex Ground Fault Receptacle	UOM:	EA	\$32.43	\$173.15	\$0.00	\$205.59
		Qty:	1	\$32	\$173	\$0	\$206
Assm: 11020214	Descr: Surface Mounted 1' X 4' Fluorescent Fixture	UOM:	EA	\$101.83	\$186.65	\$0.00	\$288.48
		Qty:	1	\$102	\$187	\$0	\$288

FSA: ID: MHF Name: HAZARDOUS MATERIAL STORAGE - FLAMMABLE

Facility Type: Supporting ID: 13 Name: MWL Storage Facility Office

Assm: 05010119	Descr: 8 X 12 X 16 Load Bearing Concrete Masonry Unit Wall	UOM:	SF	\$6.59	\$8.57	\$0.09	\$15.26
		Qty:	19	\$125	\$163	\$2	\$290
Assm: 05030101	Descr: Coiling Overhead Door	UOM:	EA	\$1,101.78	\$1,107.72	\$0.00	\$2,209.50
		Qty:	1	\$1,102	\$1,108	\$0	\$2,210
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
		Qty:	62	\$18	\$44	\$0	\$62

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06020801	Descr: Epoxy Floor Coating	UOM:	SF	\$2.87	\$2.58	\$0.10	\$5.56
		Qty:	100	\$287	\$258	\$10	\$556
Assm: 11020146	Descr: Explosion Proof Equipment Connection 5 - 25 HP	UOM:	EA	\$1,336.04	\$537.38	\$0.00	\$1,873.42
		Qty:	1	\$1,336	\$537	\$0	\$1,873
Assm: 11020228	Descr: 250W Hps Wall Pack	UOM:	EA	\$291.34	\$229.01	\$0.00	\$520.35
		Qty:	1	\$291	\$229	\$0	\$520
Assm: 11020229	Descr: 100W Hps Wall Mount	UOM:	EA	\$175.34	\$236.30	\$0.00	\$411.64
		Qty:	1	\$175	\$236	\$0	\$412
Assm: 11020264	Descr: Explosion Proof Hps Low Bay	UOM:	EA	\$629.98	\$351.27	\$0.00	\$981.25
		Qty:	1	\$630	\$351	\$0	\$981
Assm: 11020265	Descr: Explosion Proof Exit W/Batt. Back Up	UOM:	EA	\$744.78	\$336.13	\$0.00	\$1,080.91
		Qty:	1	\$745	\$336	\$0	\$1,081
Assm: 11020274	Descr: 6V Emergency Battery Pack	UOM:	EA	\$75.96	\$241.46	\$0.00	\$317.42
		Qty:	1	\$76	\$241	\$0	\$317

FSA: **ID:** OFC **Name:** OFFICE - CLOSED OFFICE SPACE

Facility Type: Supporting **ID:** 13 **Name:** MWL Storage Facility Office

Assm: 05010101	Descr: Mtl Stud Partition, 3-5/8"	UOM:	SF	\$0.18	\$0.62	\$0.00	\$0.79
		Qty:	563	\$99	\$346	\$0	\$445
Assm: 05010102	Descr: Mtl Stud Partition, 3-5/8", Sound Rated	UOM:	SF	\$0.59	\$0.94	\$0.00	\$1.54
		Qty:	63	\$37	\$59	\$0	\$97
Assm: 05010504	Descr: Fixed Type Window With Aluminum Frm - 3/4" Clear Glass	UOM:	SF	\$16.81	\$6.30	\$0.00	\$23.11
		Qty:	1	\$17	\$6	\$0	\$23

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 05020117	Descr: 3'0" X 7'0" Wood Door, H.M. Frm	UOM:	EA	\$367.74	\$177.69	\$0.00	\$545.43
		Qty:	2	\$735	\$355	\$0	\$1,091
Assm: 05020303	Descr: 3'0" X 7'0" Fire Rated Wood Door	UOM:	EA	\$512.62	\$187.37	\$0.00	\$699.99
		Qty:	1	\$513	\$187	\$0	\$700
Assm: 05020304	Descr: 6'0" X 7'0" Pair Fire Rated Wood Doors	UOM:	EA	\$961.62	\$345.72	\$0.00	\$1,307.34
		Qty:	1	\$962	\$346	\$0	\$1,307
Assm: 05040301	Descr: Porcelain Enamel Chalkboard	UOM:	SF	\$16.66	\$22.28	\$0.00	\$38.94
		Qty:	5	\$83	\$111	\$0	\$195
Assm: 05040601	Descr: 10" Wide Stock Prefinished Shelves With Supports	UOM:	LF	\$3.84	\$4.29	\$0.00	\$8.13
		Qty:	600	\$2,302	\$2,574	\$0	\$4,876
Assm: 05050101	Descr: Plastic Laminate Countertop With Backsplash	UOM:	LF	\$4.61	\$10.00	\$0.00	\$14.61
		Qty:	12	\$55	\$120	\$0	\$175
Assm: 05050201	Descr: Plastic Laminate Cabinets With Countertop And Drawers	UOM:	LF	\$135.86	\$32.22	\$0.00	\$168.08
		Qty:	9	\$1,223	\$290	\$0	\$1,513
Assm: 06010301	Descr: 5/8" Gypsum Board On 7/8" Furring Channel	UOM:	SF	\$0.73	\$3.09	\$0.00	\$3.83
		Qty:	68	\$50	\$210	\$0	\$260
Assm: 06010303	Descr: Two Layers Of 5/8" Fire Resistant Gypsum Board	UOM:	SF	\$1.04	\$1.29	\$0.00	\$2.33
		Qty:	13	\$13	\$17	\$0	\$30
Assm: 06010304	Descr: 5/8" Gypsum Board/Installed/Taped & Finished	UOM:	SF	\$0.31	\$0.59	\$0.00	\$0.90
		Qty:	717	\$219	\$426	\$0	\$646
Assm: 06010501	Descr: Paint To Gypsum Board Walls Using Roller	UOM:	SF	\$0.10	\$0.28	\$0.00	\$0.38
		Qty:	771	\$79	\$213	\$0	\$292

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06010601	Descr: Light Weight Vinyl Wallcovering With Fabric Backing	UOM:	SF	\$0.51	\$0.41	\$0.00	\$0.92
		Qty:	75	\$38	\$31	\$0	\$69
Assm: 06010701	Descr: 4' X 8' X 1" Fiberglass Sound Absorbing Panels	UOM:	SF	\$1.56	\$0.58	\$0.00	\$2.14
		Qty:	14	\$22	\$8	\$0	\$30
Assm: 06020401	Descr: Vinyl Tile 1/8" X 12" X 12"	UOM:	SF	\$2.96	\$0.82	\$0.00	\$3.78
		Qty:	56	\$166	\$46	\$0	\$212
Assm: 06020501	Descr: Commercial Grade 26 Oz. Nylon Carpet	UOM:	SY	\$14.84	\$6.16	\$0.00	\$21.00
		Qty:	58	\$861	\$357	\$0	\$1,218
Assm: 06030402	Descr: 2' X 2' Or 2' X 4' Fiberglass Acoustical Ceiling Tiles	UOM:	SF	\$0.43	\$0.42	\$0.00	\$0.85
		Qty:	576	\$246	\$241	\$0	\$488
Assm: 06030703	Descr: T-Bar Ceiling Suspension System 2' X 4' Grid	UOM:	SF	\$0.31	\$0.37	\$0.00	\$0.67
		Qty:	576	\$176	\$213	\$0	\$389
Assm: 11020101	Descr: 120 Volt, 20 Amp Duplex Receptacle - Stud Partition	UOM:	EA	\$26.43	\$164.10	\$0.00	\$190.53
		Qty:	9	\$238	\$1,477	\$0	\$1,715
Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
		Qty:	2	\$62	\$341	\$0	\$403
Assm: 11020121	Descr: 230 Volt, 30 Amp Receptacle - Stud Partition	UOM:	EA	\$93.48	\$381.13	\$0.00	\$474.61
		Qty:	1	\$93	\$381	\$0	\$475
Assm: 11020202	Descr: 2' X 4' Lay-In Fluorescent Fixture	UOM:	EA	\$69.29	\$182.23	\$0.00	\$251.52
		Qty:	10	\$693	\$1,822	\$0	\$2,515
Assm: 11020220	Descr: Ceiling Recessed Incandescent 100 Watt Fixture	UOM:	EA	\$72.89	\$144.66	\$0.00	\$217.55
		Qty:	1	\$73	\$145	\$0	\$218

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>		
Assm:	11029011	Descr:	Fire Alarm Pull Station	UOM:	EA	\$41.30	\$155.77	\$0.00	\$197.07
				Qty:	1	\$41	\$156	\$0	\$197
FSA:	ID:	Name:	OFFICE - OPEN OFFICE SPACE						
Facility Type:	Supporting	ID:	13	Name:	MWL Storage Facility Office				
Assm:	05010101	Descr:	Mtl Stud Partition, 3-5/8"	UOM:	SF	\$0.18	\$0.62	\$0.00	\$0.79
				Qty:	223	\$39	\$137	\$0	\$176
Assm:	05010102	Descr:	Mtl Stud Partition, 3-5/8", Sound Rated	UOM:	SF	\$0.59	\$0.94	\$0.00	\$1.54
				Qty:	64	\$38	\$60	\$0	\$98
Assm:	05010113	Descr:	Non-Load Brg Partition Of 8 X 8 X 16 Concrete	UOM:	SF	\$2.08	\$3.86	\$0.00	\$5.94
				Qty:	32	\$67	\$123	\$0	\$190
Assm:	06010301	Descr:	5/8" Gypsum Board On 7/8" Furring Channel	UOM:	SF	\$0.73	\$3.09	\$0.00	\$3.83
				Qty:	52	\$38	\$161	\$0	\$199
Assm:	06010303	Descr:	Two Layers Of 5/8" Fire Resistant Gypsum Board	UOM:	SF	\$1.04	\$1.29	\$0.00	\$2.33
				Qty:	10	\$10	\$13	\$0	\$23
Assm:	06010304	Descr:	5/8" Gypsum Board/Installed/Taped & Finished	UOM:	SF	\$0.31	\$0.59	\$0.00	\$0.90
				Qty:	469	\$143	\$279	\$0	\$422
Assm:	06010501	Descr:	Paint To Gypsum Board Walls Using Roller	UOM:	SF	\$0.10	\$0.28	\$0.00	\$0.38
				Qty:	521	\$53	\$144	\$0	\$197
Assm:	06010502	Descr:	Paint To Concrete Block Using Brushes, Two Coats	UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
				Qty:	87	\$25	\$62	\$0	\$87
Assm:	06020401	Descr:	Vinyl Tile 1/8" X 12" X 12"	UOM:	SF	\$2.96	\$0.82	\$0.00	\$3.78
				Qty:	163	\$483	\$133	\$0	\$616

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06020501	Descr: Commercial Grade 26 Oz. Nylon Carpet	UOM:	SY	\$14.84	\$6.16	\$0.00	\$21.00
		Qty:	107	\$1,588	\$659	\$0	\$2,247
Assm: 06030302	Descr: 5/8" Gypsum Wallboard Ceiling, 3 Layers, Over 8 Ft.	UOM:	SF	\$0.78	\$1.47	\$0.00	\$2.25
		Qty:	49	\$38	\$72	\$0	\$110
Assm: 06030402	Descr: 2' X 2' Or 2' X 4' Fiberglass Acoustical Ceiling Tiles	UOM:	SF	\$0.43	\$0.42	\$0.00	\$0.85
		Qty:	1079	\$461	\$452	\$0	\$913
Assm: 06030601	Descr: Painting To Drywall Or Plaster Using Rollers, 2 Coats	UOM:	SF	\$0.10	\$0.28	\$0.00	\$0.38
		Qty:	49	\$5	\$14	\$0	\$19
Assm: 06030703	Descr: T-Bar Ceiling Suspension System 2' X 4' Grid	UOM:	SF	\$0.31	\$0.37	\$0.00	\$0.67
		Qty:	1079	\$330	\$398	\$0	\$728
Assm: 06030704	Descr: Suspension System For Gypsum Board Ceiling	UOM:	SF	\$0.75	\$4.08	\$0.00	\$4.83
		Qty:	49	\$37	\$200	\$0	\$237
Assm: 11020101	Descr: 120 Volt, 20 Amp Duplex Receptacle - Stud Partition	UOM:	EA	\$26.43	\$164.10	\$0.00	\$190.53
		Qty:	6	\$159	\$985	\$0	\$1,143
Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
		Qty:	2	\$62	\$341	\$0	\$403
Assm: 11020111	Descr: 120 Volt, 20 Amp Duplex Floor Mounted Receptacle	UOM:	EA	\$145.66	\$215.25	\$0.00	\$360.91
		Qty:	1	\$146	\$215	\$0	\$361
Assm: 11020202	Descr: 2' X 4' Lay-In Fluorescent Fixture	UOM:	EA	\$69.29	\$182.23	\$0.00	\$251.52
		Qty:	17	\$1,178	\$3,098	\$0	\$4,276
Assm: 11020220	Descr: Ceiling Recessed Incandescent 100 Watt Fixture	UOM:	EA	\$72.89	\$144.66	\$0.00	\$217.55
		Qty:	1	\$73	\$145	\$0	\$218

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 11029011	Descr: Fire Alarm Pull Station	UOM:	EA	\$41.30	\$155.77	\$0.00	\$197.07
		Qty:	1	\$41	\$156	\$0	\$197

FSA: **ID:** SEC **Name:** SECURITY

Facility Type: Supporting **ID:** 13 **Name:** MWL Storage Facility Office

Assm: 05010113	Descr: Non-Load Brg Partition Of 8 X 8 X 16 Concrete	UOM:	SF	\$2.08	\$3.86	\$0.00	\$5.94
		Qty:	84	\$175	\$324	\$0	\$499

Assm: 06010301	Descr: 5/8" Gypsum Board On 7/8" Furring Channel	UOM:	SF	\$0.73	\$3.09	\$0.00	\$3.83
		Qty:	145	\$106	\$449	\$0	\$555

Assm: 06010303	Descr: Two Layers Of 5/8" Fire Resistant Gypsum Board	UOM:	SF	\$1.04	\$1.29	\$0.00	\$2.33
		Qty:	29	\$30	\$37	\$0	\$67

Assm: 06010701	Descr: 4' X 8' X 1" Fiberglass Sound Absorbing Panels	UOM:	SF	\$1.56	\$0.58	\$0.00	\$2.14
		Qty:	50	\$78	\$29	\$0	\$107

Assm: 06020501	Descr: Commercial Grade 26 Oz. Nylon Carpet	UOM:	SY	\$14.84	\$6.16	\$0.00	\$21.00
		Qty:	6	\$89	\$37	\$0	\$126

Assm: 06030703	Descr: T-Bar Ceiling Suspension System 2' X 4' Grid	UOM:	SF	\$0.31	\$0.37	\$0.00	\$0.67
		Qty:	50	\$15	\$18	\$0	\$34

Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
		Qty:	1	\$31	\$171	\$0	\$202

Assm: 11020202	Descr: 2' X 4' Lay-In Fluorescent Fixture	UOM:	EA	\$69.29	\$182.23	\$0.00	\$251.52
		Qty:	1	\$69	\$182	\$0	\$252

FSA: **ID:** WOR **Name:** WORK AREA

Facility Type: Supporting **ID:** 13 **Name:** MWL Storage Facility Office

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06010504	Descr: Special Coating	UOM: SF	\$0.35	\$0.72	\$0.00	\$1.07
		Qty: 59	\$21	\$42	\$0	\$63
Assm: 06029003	Descr: Floor Hardener, Non-Metallic Light Service	UOM: SF	\$0.18	\$0.32	\$0.00	\$0.49
		Qty: 384	\$68	\$121	\$0	\$190
Assm: 07030201	Descr: Overhead Monorail - 2000 Lb Capacity	UOM: EA	\$2,092.46	\$269.53	\$0.00	\$2,361.99
		Qty: 1	\$2,092	\$270	\$0	\$2,362
Assm: 07030203	Descr: Overhead Monorail - 6000 Lb Capacity	UOM: EA	\$3,976.38	\$328.25	\$0.00	\$4,304.63
		Qty: 1	\$3,976	\$328	\$0	\$4,305
Assm: 09089010	Descr: Compressed Air System For Material Cutting Area (8 Out)	UOM: EA	\$7,553.80	\$6,586.32	\$0.00	\$14,140.12
		Qty: 1	\$7,554	\$6,586	\$0	\$14,140
Assm: 11020132	Descr: Explosion Proof 30A Rec	UOM: EA	\$1,590.17	\$766.06	\$0.00	\$2,356.23
		Qty: 1	\$1,590	\$766	\$0	\$2,356
Assm: 11020146	Descr: Explosion Proof Equipment Connection 5 - 25 HP	UOM: EA	\$1,336.04	\$537.38	\$0.00	\$1,873.42
		Qty: 1	\$1,336	\$537	\$0	\$1,873
Assm: 11020147	Descr: Explosion Proof Equipment Connection 30 - 60 HP	UOM: EA	\$1,981.83	\$667.92	\$0.00	\$2,649.75
		Qty: 1	\$1,982	\$668	\$0	\$2,650
Assm: 11020242	Descr: 150W Hps Hazardous Flood	UOM: EA	\$688.89	\$285.48	\$0.00	\$974.37
		Qty: 1	\$689	\$285	\$0	\$974
Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM: EA	\$200.94	\$375.90	\$0.00	\$576.85
		Qty: 1	\$201	\$376	\$0	\$577
Assm: 11020256	Descr: Twin Mounted High Bay 400W Hps Fixture W/Quartz Standby	UOM: EA	\$464.53	\$574.55	\$0.00	\$1,039.08
		Qty: 1	\$465	\$575	\$0	\$1,039

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	11020272	Descr:	Exit Light With Battery Backup	UOM:	EA	\$117.22	\$212.56	\$0.00	\$329.78
				Qty:	1	\$117	\$213	\$0	\$330
Assm:	11020274	Descr:	6V Emergency Battery Pack	UOM:	EA	\$75.96	\$241.46	\$0.00	\$317.42
				Qty:	1	\$76	\$241	\$0	\$317
Assm:	11020278	Descr:	Accent Wall Fixture, 100W	UOM:	EA	\$34.93	\$200.29	\$0.00	\$235.22
				Qty:	1	\$35	\$200	\$0	\$235
FSA:	ID:	Name:	DINING AREA						
Facility Type:	Supporting	ID:	13	Name:	MWL Storage Facility Office				
Assm:	05010113	Descr:	Non-Load Brg Partition Of 8 X 8 X 16 Concrete	UOM:	SF	\$2.08	\$3.86	\$0.00	\$5.94
				Qty:	36	\$75	\$139	\$0	\$214
Assm:	05040401	Descr:	Door Sign, 3" X 8"	UOM:	EA	\$8.77	\$7.35	\$0.00	\$16.12
				Qty:	1	\$9	\$7	\$0	\$16
Assm:	05040702	Descr:	Fire Extinguisher Cabinet, 8" X 16" X 38"	UOM:	EA	\$124.88	\$111.47	\$0.00	\$236.35
				Qty:	1	\$125	\$111	\$0	\$236
Assm:	06010504	Descr:	Special Coating	UOM:	SF	\$0.35	\$0.72	\$0.00	\$1.07
				Qty:	67	\$24	\$48	\$0	\$72
Assm:	06020401	Descr:	Vinyl Tile 1/8" X 12" X 12"	UOM:	SF	\$2.96	\$0.82	\$0.00	\$3.78
				Qty:	120	\$356	\$98	\$0	\$454
Assm:	06030402	Descr:	2' X 2' Or 2' X 4' Fiberglass Acoustical Ceiling Tiles	UOM:	SF	\$0.43	\$0.42	\$0.00	\$0.85
				Qty:	120	\$51	\$50	\$0	\$102
Assm:	06030702	Descr:	T-Bar Ceiling Suspension System 2' X 2' Grid	UOM:	SF	\$0.37	\$0.45	\$0.00	\$0.82
				Qty:	120	\$44	\$54	\$0	\$99

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
		Qty:	1	\$31	\$171	\$0	\$202
Assm: 11020111	Descr: 120 Volt, 20 Amp Duplex Floor Mounted Receptacle	UOM:	EA	\$145.66	\$215.25	\$0.00	\$360.91
		Qty:	1	\$146	\$215	\$0	\$361
Assm: 11020137	Descr: Equipment Connections For Up To 10 HP	UOM:	EA	\$301.38	\$572.98	\$0.00	\$874.36
		Qty:	1	\$301	\$573	\$0	\$874
Assm: 11020202	Descr: 2' X 4' Lay-In Fluorescent Fixture	UOM:	EA	\$69.29	\$182.23	\$0.00	\$251.52
		Qty:	2	\$139	\$364	\$0	\$503
Assm: 11020207	Descr: 2' X 4' Lay-In Fluorescent Fixture With Emergency Unit	UOM:	EA	\$146.08	\$182.23	\$0.00	\$328.32
		Qty:	1	\$146	\$182	\$0	\$328
Assm: 11020272	Descr: Exit Light With Battery Backup	UOM:	EA	\$117.22	\$212.56	\$0.00	\$329.78
		Qty:	1	\$117	\$213	\$0	\$330

FSA: **ID:** **Name:** Building Shell

Facility Type: Primary **ID:** 45 **Name:** UnClass Soil Storage Warehouse 2

Assm: 01010103	Descr: 1'0" X 3'0" Strip Footing 3000 PSI	UOM:	LF	\$11.15	\$10.90	\$0.17	\$22.22
		Qty:	4622	\$51,550	\$50,376	\$784	\$102,709
Assm: 01010105	Descr: 1'6" X 4'0" Strip Footing 3000 PSI	UOM:	LF	\$21.62	\$17.86	\$0.29	\$39.77
		Qty:	2558	\$55,296	\$45,684	\$748	\$101,728
Assm: 01010112	Descr: 1'3" X 2'6" Grade Beam 4000 PSI	UOM:	LF	\$20.15	\$26.26	\$0.21	\$46.63
		Qty:	4622	\$93,158	\$121,396	\$959	\$215,512
Assm: 01010117	Descr: 16" Masonry Wall Foundation - 24" Deep Wall	UOM:	LF	\$14.13	\$21.63	\$0.07	\$35.83
		Qty:	5116	\$72,275	\$110,653	\$377	\$183,305

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 01010201	Descr: Spread Footing	UOM: CY	\$73.57	\$45.75	\$2.16	\$121.48
		Qty: 1360	\$100,050	\$62,224	\$2,937	\$165,211
Assm: 01010212	Descr: Column Piers 2'0" X 2'0" X 3'0" High	UOM: EA	\$87.34	\$173.72	\$1.69	\$262.75
		Qty: 245	\$21,399	\$42,561	\$414	\$64,374
Assm: 01010241	Descr: Spread Footing, Reinforcing Steel	UOM: TON	\$551.26	\$645.22	\$0.00	\$1,196.47
		Qty: 15	\$8,164	\$9,556	\$0	\$17,720
Assm: 01029050	Descr: Tie Beams (Seismic Modification)	UOM: LF	\$14.64	\$18.55	\$0.16	\$33.35
		Qty: 13991	\$204,791	\$259,584	\$2,262	\$466,637
Assm: 01030104	Descr: 7" Standard Slab On Grade	UOM: SF	\$2.01	\$2.62	\$0.16	\$4.79
		Qty: 570581	\$1,146,868	\$1,495,550	\$91,464	\$2,733,882
Assm: 01030115	Descr: Loading Dock Apron	UOM: SF	\$3.89	\$2.31	\$0.08	\$6.28
		Qty: 36155	\$140,715	\$83,641	\$2,863	\$227,220
Assm: 02020204	Descr: 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	UOM: SF	\$5.99	\$8.06	\$0.09	\$14.14
		Qty: 235108	\$1,408,438	\$1,894,030	\$22,194	\$3,324,662
Assm: 02020313	Descr: Precast/Prestressed Roof Members	UOM: SF	\$4.96	\$1.19	\$0.34	\$6.49
		Qty: 634056	\$3,145,171	\$754,463	\$215,325	\$4,114,960
Assm: 02020314	Descr: 3" Topping Slab	UOM: SF	\$0.77	\$0.57	\$0.04	\$1.38
		Qty: 634056	\$489,238	\$358,812	\$25,362	\$873,412
Assm: 03010103	Descr: Tilt-Up Wall Panel 5-1/2" Thick	UOM: SF	\$11.02	\$1.21	\$0.17	\$12.40
		Qty: 42194	\$465,134	\$51,004	\$7,215	\$523,353
Assm: 03010147	Descr: Additional Vertical Reinforcement And Grouting; Seismic	UOM: SF	\$0.23	\$0.36	\$0.03	\$0.62
		Qty: 42194	\$9,679	\$15,270	\$1,063	\$26,013

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 03010205	Descr: Loose Fill 8" Block Insulation	UOM: SF	\$0.51	\$0.46	\$0.00	\$0.98
		Qty: 42194	\$21,548	\$19,612	\$0	\$41,160
Assm: 03010312	Descr: Paint CMU/Concrete	UOM: SF	\$0.19	\$0.53	\$0.00	\$0.72
		Qty: 42194	\$7,819	\$22,494	\$0	\$30,312
Assm: 03010501	Descr: Fixed Blade Exterior Louver With Baked Enamel Finish	UOM: SF	\$29.84	\$12.28	\$0.00	\$42.12
		Qty: 956	\$28,526	\$11,738	\$0	\$40,264
Assm: 03030101	Descr: 3'0" X 7'0" Aluminum And Glass Door	UOM: EA	\$608.95	\$579.12	\$0.00	\$1,188.07
		Qty: 3	\$1,827	\$1,737	\$0	\$3,564
Assm: 03030202	Descr: 3'0" X 7'0" Hollow Metal Door W/Frame	UOM: EA	\$1,287.09	\$468.13	\$0.00	\$1,755.22
		Qty: 20	\$25,742	\$9,363	\$0	\$35,104
Assm: 03030204	Descr: 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	UOM: EA	\$2,328.71	\$734.80	\$0.00	\$3,063.51
		Qty: 3	\$6,986	\$2,204	\$0	\$9,191
Assm: 03040103	Descr: 20'0" X 14'0" Metal Overhead Door	UOM: EA	\$3,536.29	\$1,914.35	\$99.90	\$5,550.54
		Qty: 38	\$134,379	\$72,745	\$3,796	\$210,921
Assm: 04010108	Descr: Standing Seam Metal Roof	UOM: SF	\$2.03	\$1.26	\$0.00	\$3.29
		Qty: 634056	\$1,287,768	\$797,706	\$0	\$2,085,474
Assm: 04010302	Descr: Rigid Insulation 1-1/2" Thick	UOM: SF	\$0.35	\$0.24	\$0.00	\$0.59
		Qty: 634056	\$223,378	\$152,871	\$0	\$376,249
Assm: 04010503	Descr: Skylights, Plastic Insulated Domes	UOM: SF	\$23.64	\$4.31	\$0.00	\$27.94
		Qty: 6071	\$143,492	\$26,159	\$0	\$169,652
Assm: 04010601	Descr: 5" Box Gutters With Downspouts	UOM: LF	\$1.59	\$3.61	\$0.00	\$5.20
		Qty: 180	\$287	\$650	\$0	\$937

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 08020101	Descr: Copper Pipe & Fittings	UOM:	EA	\$203.76	\$720.72	\$0.00	\$924.48
		Qty:	24	\$4,890	\$17,297	\$0	\$22,188
Assm: 08020201	Descr: Valves & Hydrants	UOM:	EA	\$90.94	\$25.08	\$0.00	\$116.03
		Qty:	13	\$1,182	\$326	\$0	\$1,508
Assm: 08020401	Descr: Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	UOM:	EA	\$78.67	\$82.34	\$0.00	\$161.01
		Qty:	24	\$1,888	\$1,976	\$0	\$3,864
Assm: 08030101	Descr: Waste Pipe & Fittings	UOM:	EA	\$180.14	\$361.88	\$0.00	\$542.02
		Qty:	30	\$5,404	\$10,856	\$0	\$16,261
Assm: 08030202	Descr: PVC Vent Pipng	UOM:	EA	\$13.95	\$47.57	\$0.00	\$61.51
		Qty:	30	\$418	\$1,427	\$0	\$1,845
Assm: 08030305	Descr: Heavy Duty Cast Iron Floor Drains	UOM:	EA	\$409.55	\$63.67	\$0.00	\$473.21
		Qty:	6	\$2,457	\$382	\$0	\$2,839
Assm: 08050102	Descr: Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	UOM:	EA	\$299.10	\$172.74	\$0.00	\$471.84
		Qty:	2	\$598	\$345	\$0	\$944
Assm: 08050108	Descr: Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	UOM:	EA	\$400.59	\$43.19	\$0.00	\$443.77
		Qty:	3	\$1,202	\$130	\$0	\$1,331
Assm: 08060201	Descr: Acid Waste System For Battery & Acid Rooms	UOM:	EA	\$2,609.25	\$939.01	\$0.00	\$3,548.25
		Qty:	2	\$5,218	\$1,878	\$0	\$7,097
Assm: 08060204	Descr: Special Plumbing For Battery And Acid Rooms	UOM:	EA	\$362.85	\$935.23	\$0.00	\$1,298.08
		Qty:	2	\$726	\$1,870	\$0	\$2,596
Assm: 08060304	Descr: Interceptors For Battery & Acid Rooms	UOM:	EA	\$1,401.67	\$222.85	\$0.00	\$1,624.52
		Qty:	2	\$2,803	\$446	\$0	\$3,249

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	09010211	Descr: 18000 MBH Gas Supply	UOM: EA	\$10,823.28	\$10,577.38	\$148.33	\$21,548.98
			Qty: 1	\$10,823	\$10,577	\$148	\$21,549
Assm:	09020403	Descr: Gas Fired Unit Heater, 300 MBH, Spark Ignition	UOM: EA	\$3,016.12	\$839.47	\$1.70	\$3,857.29
			Qty: 112	\$337,806	\$94,021	\$190	\$432,017
Assm:	09030209	Descr: 15 Ton Condensing Unit With Refrigerant Piping	UOM: EA	\$8,123.97	\$3,365.04	\$0.00	\$11,489.01
			Qty: 2	\$16,248	\$6,730	\$0	\$22,978
Assm:	09040703	Descr: Toilet Exhaust .2 MCFM	UOM: MCFM	\$1,116.15	\$1,667.16	\$0.00	\$2,783.31
			Qty: 1	\$659	\$984	\$0	\$1,642
Assm:	09040727	Descr: Ventilation System, 64.8 MCFM	UOM: MCFM	\$418.17	\$71.07	\$0.00	\$489.24
			Qty: 359	\$150,205	\$25,530	\$0	\$175,735
Assm:	09040765	Descr: 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	UOM: MCFM	\$3,520.33	\$790.73	\$0.00	\$4,311.06
			Qty: 10	\$34,781	\$7,812	\$0	\$42,593
Assm:	09049907	Descr: Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	UOM: MCFM	\$1,370.16	\$1,955.73	\$0.00	\$3,325.89
			Qty: 0	\$356	\$508	\$0	\$865
Assm:	09049921	Descr: 2.0 MCFM Air Dist Sys With Heat Pump	UOM: MCFM	\$3,706.36	\$4,390.65	\$0.00	\$8,097.01
			Qty: 2	\$8,636	\$10,230	\$0	\$18,866
Assm:	09049923	Descr: 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	UOM: MCFM	\$1,645.75	\$4,920.50	\$0.00	\$6,566.24
			Qty: 2	\$2,847	\$8,512	\$0	\$11,360
Assm:	09060107	Descr: Control System For Cooling Unit	UOM: EA	\$122.32	\$58.85	\$0.00	\$181.17
			Qty: 2	\$245	\$118	\$0	\$362
Assm:	09060182	Descr: Controls For Ventilating System	UOM: EA	\$19,211.52	\$29,488.79	\$0.00	\$48,700.31
			Qty: 1	\$19,212	\$29,489	\$0	\$48,700

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 09070201	Descr: Test & Balance, Cent Fan/Utility Set	UOM: EA	\$0.00	\$206.44	\$0.00	\$206.44
		Qty: 35	\$0	\$7,225	\$0	\$7,225
Assm: 09070202	Descr: Test & Balance H&V Unit/In Line Fan	UOM: EA	\$0.00	\$309.73	\$0.00	\$309.73
		Qty: 58	\$0	\$17,964	\$0	\$17,964
Assm: 09070206	Descr: Test & Balance Air Handler, Low Pressure	UOM: EA	\$0.00	\$413.28	\$0.00	\$413.28
		Qty: 3	\$0	\$1,240	\$0	\$1,240
Assm: 09070211	Descr: Test & Balance Vav Box	UOM: EA	\$39.90	\$68.74	\$0.00	\$108.64
		Qty: 1	\$40	\$69	\$0	\$109
Assm: 10010104	Descr: Fire Prot Water Supply, (40'H) Ord Haz Fac	UOM: EA	\$48.03	\$21.35	\$0.22	\$69.60
		Qty: 4962	\$238,327	\$105,928	\$1,089	\$345,344
Assm: 10020101	Descr: Exposed Sprinkler System For A Lg Facility - Ord. Haz.	UOM: EA	\$28.44	\$81.42	\$0.00	\$109.86
		Qty: 4962	\$141,102	\$404,000	\$0	\$545,102
Assm: 11010108	Descr: Electrical 2500A Main Transformer	UOM: EA	\$29,512.44	\$4,886.87	\$96.72	\$34,496.03
		Qty: 1	\$29,512	\$4,887	\$97	\$34,496
Assm: 11010211	Descr: Electrical 2500A Secondary	UOM: EA	\$37,780.63	\$23,682.69	\$47.01	\$61,510.33
		Qty: 1	\$37,781	\$23,683	\$47	\$61,510
Assm: 11010311	Descr: Electrical 2500A Main Switchboard	UOM: EA	\$91,215.75	\$9,632.58	\$0.00	\$100,848.33
		Qty: 1	\$91,216	\$9,633	\$0	\$100,848
Assm: 11010403	Descr: (45-90 Amps 480V) 75 KVA Dry Type Transformer	UOM: EA	\$2,149.90	\$1,038.62	\$0.00	\$3,188.52
		Qty: 9	\$19,349	\$9,348	\$0	\$28,697
Assm: 11010502	Descr: Panelbd 208V 100A 30 Cir Mlo W/Bkr	UOM: EA	\$1,153.60	\$899.36	\$0.00	\$2,052.95
		Qty: 8	\$9,229	\$7,195	\$0	\$16,424

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 11010507	Descr: Panelbd 208V 225A 42 Cir Mlo W/Bkr	UOM:	EA	\$1,772.16	\$2,235.15	\$0.00	\$4,007.30
		Qty:	8	\$14,177	\$17,881	\$0	\$32,058
Assm: 11010516	Descr: Panelbd 208V 225A MCB 42 Cir W/Bkr	UOM:	EA	\$2,088.56	\$2,391.53	\$0.00	\$4,480.09
		Qty:	1	\$2,089	\$2,392	\$0	\$4,480
Assm: 11010561	Descr: Panelbd 480V 600A MCB 42 Cir W/Bkr	UOM:	EA	\$7,082.74	\$3,958.17	\$0.00	\$11,040.92
		Qty:	2	\$14,165	\$7,916	\$0	\$22,082
Assm: 11010604	Descr: Enclosed Cir Bkr 600V 225A	UOM:	EA	\$1,805.61	\$1,767.07	\$0.00	\$3,572.68
		Qty:	1	\$1,806	\$1,767	\$0	\$3,573
Assm: 12010102	Descr: Fire Alarm System - Rate Of Rise Heat Detectors	UOM:	OUT	\$102.32	\$374.83	\$0.00	\$477.15
		Qty:	192	\$19,646	\$71,968	\$0	\$91,614
Assm: 12010119	Descr: 16 Zone FACP, Annun And Transmitter	UOM:	EA	\$6,181.75	\$3,465.03	\$0.00	\$9,646.78
		Qty:	2	\$12,363	\$6,930	\$0	\$19,294
Assm: 12010301	Descr: Telephone System, 2 Pair	UOM:	EA	\$42.39	\$176.98	\$0.00	\$219.38
		Qty:	55	\$2,332	\$9,734	\$0	\$12,066
Assm: 12010402	Descr: Public Address For Large Warehouse	UOM:	SF	\$0.03	\$0.07	\$0.00	\$0.10
		Qty:	570584	\$16,889	\$40,968	\$0	\$57,857
Assm: 12010601	Descr: Clock System	UOM:	EA	\$222.34	\$177.74	\$0.00	\$400.08
		Qty:	25	\$5,559	\$4,444	\$0	\$10,002
Assm: 12010602	Descr: Time Clock System	UOM:	EA	\$334.18	\$866.03	\$0.00	\$1,200.22
		Qty:	9	\$3,008	\$7,794	\$0	\$10,802
Assm: 12020221	Descr: Battery Charger	UOM:	EA	\$1,043.18	\$619.45	\$0.00	\$1,662.63
		Qty:	34	\$35,468	\$21,061	\$0	\$56,529

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 12020401	Descr: Lightning Protection System	UOM:	EA	\$78.54	\$141.38	\$0.00	\$219.92
		Qty:	30	\$2,356	\$4,241	\$0	\$6,598
Assm: 12020601	Descr: Energy Management Control System	UOM:	PTS	\$932.47	\$401.74	\$0.00	\$1,334.21
		Qty:	97	\$90,449	\$38,969	\$0	\$129,418

FSA: ID: CVN **Name:** COVERED EXTERIOR ENTRYWAY

Facility Type: Primary **ID:** 45 **Name:** UnClass Soil Storage Warehouse 2

Assm: 06039002	Descr: Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
		Qty:	108	\$623	\$705	\$0	\$1,327
Assm: 11020229	Descr: 100W Hps Wall Mount	UOM:	EA	\$175.34	\$236.30	\$0.00	\$411.64
		Qty:	1	\$175	\$236	\$0	\$412
Assm: 11020235	Descr: 150 Watt Hps Recessed Fixture	UOM:	EA	\$215.09	\$246.25	\$0.00	\$461.34
		Qty:	1	\$215	\$246	\$0	\$461

FSA: ID: CVT **Name:** COVERED EXTERIOR LOADING DOCK W/LEVELER

Facility Type: Primary **ID:** 45 **Name:** UnClass Soil Storage Warehouse 2

Assm: 06039002	Descr: Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
		Qty:	1061	\$6,117	\$6,923	\$0	\$13,039
Assm: 11020136	Descr: Equipment Connections For Up To 5 HP	UOM:	EA	\$267.15	\$527.09	\$0.00	\$794.24
		Qty:	1	\$267	\$527	\$0	\$794
Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM:	EA	\$200.94	\$375.90	\$0.00	\$576.85
		Qty:	4	\$804	\$1,504	\$0	\$2,307
Assm: 11020280	Descr: Dock Lights	UOM:	EA	\$123.71	\$227.24	\$0.00	\$350.95
		Qty:	2	\$247	\$454	\$0	\$702

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 13010602	Descr: 6'0" X 8'0" Long 10 Ton Capacity With Stairs	UOM:	DOCK	\$4,942.83	\$1,428.71	\$40.13	\$6,411.67
		Qty:	1	\$4,943	\$1,429	\$40	\$6,412
Assm: 13010606	Descr: 24" Deep Dock Leveler Pit Wall W/Stl Angle	UOM:	EA	\$483.17	\$1,116.94	\$1.04	\$1,601.14
		Qty:	1	\$483	\$1,117	\$1	\$1,601

FSA: ID: MEL Name: MECHANICAL, ELECTRICAL, & BUILDING SUPPORT

Facility Type: Primary ID: 45 Name: UnClass Soil Storage Warehouse 2

Assm: 05010114	Descr: Non-Load Bearing 8 X 8 X 16 Concrete Block	UOM:	SF	\$2.34	\$5.03	\$0.00	\$7.37
		Qty:	337	\$788	\$1,695	\$0	\$2,483
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
		Qty:	668	\$192	\$479	\$0	\$671
Assm: 06030301	Descr: 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	UOM:	SF	\$0.32	\$0.59	\$0.00	\$0.92
		Qty:	56	\$18	\$33	\$0	\$51
Assm: 06030704	Descr: Suspension System For Gypsum Board Ceiling	UOM:	SF	\$0.75	\$4.08	\$0.00	\$4.83
		Qty:	56	\$42	\$228	\$0	\$270
Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
		Qty:	2	\$62	\$341	\$0	\$403
Assm: 11020156	Descr: 120V 20A Single Pole Switch	UOM:	EA	\$25.89	\$148.76	\$0.00	\$174.65
		Qty:	1	\$26	\$149	\$0	\$175
Assm: 11020276	Descr: Porcelain Lamp Holder	UOM:	EA	\$21.47	\$177.99	\$0.00	\$199.46
		Qty:	1	\$21	\$178	\$0	\$199

FSA: ID: SRM Name: STOCKROOM

Facility Type: Primary ID: 45 Name: UnClass Soil Storage Warehouse 2

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 05010112	Descr: Non-Load Brg Partition Of 8 X 6 X 16 Concrete	UOM: SF	\$1.97	\$3.68	\$0.00	\$5.65
		Qty: 18778	\$36,906	\$69,184	\$0	\$106,090
Assm: 05010126	Descr: Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	UOM: SF	\$1.68	\$1.66	\$0.00	\$3.34
		Qty: 139792	\$234,655	\$231,565	\$0	\$466,220
Assm: 05010127	Descr: Wire Mesh Partitions, 4' Wide X 20' High	UOM: SF	\$3.37	\$1.04	\$0.00	\$4.41
		Qty: 3901	\$13,144	\$4,039	\$0	\$17,184
Assm: 05039014	Descr: Sliding Metal Clad Door (With Motor)	UOM: SF	\$35.54	\$9.59	\$0.00	\$45.13
		Qty: 7231	\$257,009	\$69,340	\$0	\$326,349
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM: SF	\$0.29	\$0.72	\$0.00	\$1.00
		Qty: 11265	\$3,235	\$8,084	\$0	\$11,319
Assm: 06029001	Descr: Concrete Floor Sealer	UOM: SF	\$0.04	\$0.05	\$0.00	\$0.08
		Qty: 568936	\$20,994	\$27,252	\$0	\$48,246
Assm: 06029003	Descr: Floor Hardener, Non-Metallic Light Service	UOM: SF	\$0.18	\$0.32	\$0.00	\$0.49
		Qty: 568936	\$101,441	\$179,727	\$0	\$281,168
Assm: 11020103	Descr: Duplex Receptacle Long Run	UOM: EA	\$48.69	\$297.44	\$0.00	\$346.13
		Qty: 240	\$11,687	\$71,386	\$0	\$83,072
Assm: 11020136	Descr: Equipment Connections For Up To 5 HP	UOM: EA	\$267.15	\$527.09	\$0.00	\$794.24
		Qty: 175	\$46,751	\$92,240	\$0	\$138,991
Assm: 11020229	Descr: 100W Hps Wall Mount	UOM: EA	\$175.34	\$236.30	\$0.00	\$411.64
		Qty: 72	\$12,625	\$17,013	\$0	\$29,638
Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM: EA	\$200.94	\$375.90	\$0.00	\$576.85
		Qty: 931	\$187,080	\$349,963	\$0	\$537,043

Paces

Project Summary Report

Date 07/26/2002

						<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm:	11020255	Descr:	High Bay 400W Hps Fixture With Quartz Standby	UOM:	EA	\$296.72	\$467.99	\$0.00	\$764.70
				Qty:	125	\$37,089	\$58,498	\$0	\$95,588
Assm:	11020272	Descr:	Exit Light With Battery Backup	UOM:	EA	\$117.22	\$212.56	\$0.00	\$329.78
				Qty:	21	\$2,462	\$4,464	\$0	\$6,925
FSA:	ID:	Name:	Building Shell						
Facility Type:	Primary	ID:	46	Name:	UnClass Soil Storage Warehouse 3				
Assm:	01010103	Descr:	1'0" X 3'0" Strip Footing 3000 PSI	UOM:	LF	\$11.15	\$10.90	\$0.17	\$22.22
				Qty:	4622	\$51,550	\$50,376	\$784	\$102,709
Assm:	01010105	Descr:	1'6" X 4'0" Strip Footing 3000 PSI	UOM:	LF	\$21.62	\$17.86	\$0.29	\$39.77
				Qty:	2558	\$55,296	\$45,684	\$748	\$101,728
Assm:	01010112	Descr:	1'3" X 2'6" Grade Beam 4000 PSI	UOM:	LF	\$20.15	\$26.26	\$0.21	\$46.63
				Qty:	4622	\$93,158	\$121,396	\$959	\$215,512
Assm:	01010117	Descr:	16" Masonry Wall Foundation - 24" Deep Wall	UOM:	LF	\$14.13	\$21.63	\$0.07	\$35.83
				Qty:	5116	\$72,275	\$110,653	\$377	\$183,305
Assm:	01010201	Descr:	Spread Footing	UOM:	CY	\$73.57	\$45.75	\$2.16	\$121.48
				Qty:	1360	\$100,050	\$62,224	\$2,937	\$165,211
Assm:	01010212	Descr:	Column Piers 2'0" X 2'0" X 3'0" High	UOM:	EA	\$87.34	\$173.72	\$1.69	\$262.75
				Qty:	245	\$21,399	\$42,561	\$414	\$64,374
Assm:	01010241	Descr:	Spread Footing, Reinforcing Steel	UOM:	TON	\$551.26	\$645.22	\$0.00	\$1,196.47
				Qty:	15	\$8,164	\$9,556	\$0	\$17,720
Assm:	01029050	Descr:	Tie Beams (Seismic Modification)	UOM:	LF	\$14.64	\$18.55	\$0.16	\$33.35
				Qty:	13991	\$204,791	\$259,584	\$2,262	\$466,637

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 01030104	Descr: 7" Standard Slab On Grade	UOM: SF	\$2.01	\$2.62	\$0.16	\$4.79
		Qty: 570581	\$1,146,868	\$1,495,550	\$91,464	\$2,733,882
Assm: 01030115	Descr: Loading Dock Apron	UOM: SF	\$3.89	\$2.31	\$0.08	\$6.28
		Qty: 36155	\$140,715	\$83,641	\$2,863	\$227,220
Assm: 02020204	Descr: 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	UOM: SF	\$5.99	\$8.06	\$0.09	\$14.14
		Qty: 235108	\$1,408,438	\$1,894,030	\$22,194	\$3,324,662
Assm: 02020313	Descr: Precast/Prestressed Roof Members	UOM: SF	\$4.96	\$1.19	\$0.34	\$6.49
		Qty: 634056	\$3,145,171	\$754,463	\$215,325	\$4,114,960
Assm: 02020314	Descr: 3" Topping Slab	UOM: SF	\$0.77	\$0.57	\$0.04	\$1.38
		Qty: 634056	\$489,238	\$358,812	\$25,362	\$873,412
Assm: 03010103	Descr: Tilt-Up Wall Panel 5-1/2" Thick	UOM: SF	\$11.02	\$1.21	\$0.17	\$12.40
		Qty: 42194	\$465,134	\$51,004	\$7,215	\$523,353
Assm: 03010147	Descr: Additional Vertical Reinforcement And Grouting; Seismic	UOM: SF	\$0.23	\$0.36	\$0.03	\$0.62
		Qty: 42194	\$9,679	\$15,270	\$1,063	\$26,013
Assm: 03010205	Descr: Loose Fill 8" Block Insulation	UOM: SF	\$0.51	\$0.46	\$0.00	\$0.98
		Qty: 42194	\$21,548	\$19,612	\$0	\$41,160
Assm: 03010312	Descr: Paint CMU/Concrete	UOM: SF	\$0.19	\$0.53	\$0.00	\$0.72
		Qty: 42194	\$7,819	\$22,494	\$0	\$30,312
Assm: 03010501	Descr: Fixed Blade Exterior Louver With Baked Enamel Finish	UOM: SF	\$29.84	\$12.28	\$0.00	\$42.12
		Qty: 956	\$28,526	\$11,738	\$0	\$40,264
Assm: 03030101	Descr: 3'0" X 7'0" Aluminum And Glass Door	UOM: EA	\$608.95	\$579.12	\$0.00	\$1,188.07
		Qty: 3	\$1,827	\$1,737	\$0	\$3,564

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 03030202	Descr: 3'0" X 7'0" Hollow Metal Door W/Frame	UOM: EA	\$1,287.09	\$468.13	\$0.00	\$1,755.22
		Qty: 20	\$25,742	\$9,363	\$0	\$35,104
Assm: 03030204	Descr: 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	UOM: EA	\$2,328.71	\$734.80	\$0.00	\$3,063.51
		Qty: 3	\$6,986	\$2,204	\$0	\$9,191
Assm: 03040103	Descr: 20'0" X 14'0" Metal Overhead Door	UOM: EA	\$3,536.29	\$1,914.35	\$99.90	\$5,550.54
		Qty: 38	\$134,379	\$72,745	\$3,796	\$210,921
Assm: 04010108	Descr: Standing Seam Metal Roof	UOM: SF	\$2.03	\$1.26	\$0.00	\$3.29
		Qty: 634056	\$1,287,768	\$797,706	\$0	\$2,085,474
Assm: 04010302	Descr: Rigid Insulation 1-1/2" Thick	UOM: SF	\$0.35	\$0.24	\$0.00	\$0.59
		Qty: 634056	\$223,378	\$152,871	\$0	\$376,249
Assm: 04010503	Descr: Skylights, Plastic Insulated Domes	UOM: SF	\$23.64	\$4.31	\$0.00	\$27.94
		Qty: 6071	\$143,492	\$26,159	\$0	\$169,652
Assm: 04010601	Descr: 5" Box Gutters With Downspouts	UOM: LF	\$1.59	\$3.61	\$0.00	\$5.20
		Qty: 180	\$287	\$650	\$0	\$937
Assm: 08020101	Descr: Copper Pipe & Fittings	UOM: EA	\$203.76	\$720.72	\$0.00	\$924.48
		Qty: 24	\$4,890	\$17,297	\$0	\$22,188
Assm: 08020201	Descr: Valves & Hydrants	UOM: EA	\$90.94	\$25.08	\$0.00	\$116.03
		Qty: 13	\$1,182	\$326	\$0	\$1,508
Assm: 08020401	Descr: Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	UOM: EA	\$78.67	\$82.34	\$0.00	\$161.01
		Qty: 24	\$1,888	\$1,976	\$0	\$3,864
Assm: 08030101	Descr: Waste Pipe & Fittings	UOM: EA	\$180.14	\$361.88	\$0.00	\$542.02
		Qty: 30	\$5,404	\$10,856	\$0	\$16,261

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 08030202	Descr: PVC Vent Piping	UOM: EA	\$13.95	\$47.57	\$0.00	\$61.51
		Qty: 30	\$418	\$1,427	\$0	\$1,845
Assm: 08030305	Descr: Heavy Duty Cast Iron Floor Drains	UOM: EA	\$409.55	\$63.67	\$0.00	\$473.21
		Qty: 6	\$2,457	\$382	\$0	\$2,839
Assm: 08050102	Descr: Domestic Water Supply Equip - 50 Gal. Elec. Hot Water	UOM: EA	\$299.10	\$172.74	\$0.00	\$471.84
		Qty: 2	\$598	\$345	\$0	\$944
Assm: 08050108	Descr: Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	UOM: EA	\$400.59	\$43.19	\$0.00	\$443.77
		Qty: 3	\$1,202	\$130	\$0	\$1,331
Assm: 08060201	Descr: Acid Waste System For Battery & Acid Rooms	UOM: EA	\$2,609.25	\$939.01	\$0.00	\$3,548.25
		Qty: 2	\$5,218	\$1,878	\$0	\$7,097
Assm: 08060204	Descr: Special Plumbing For Battery And Acid Rooms	UOM: EA	\$362.85	\$935.23	\$0.00	\$1,298.08
		Qty: 2	\$726	\$1,870	\$0	\$2,596
Assm: 08060304	Descr: Interceptors For Battery & Acid Rooms	UOM: EA	\$1,401.67	\$222.85	\$0.00	\$1,624.52
		Qty: 2	\$2,803	\$446	\$0	\$3,249
Assm: 09010211	Descr: 18000 MBH Gas Supply	UOM: EA	\$10,823.28	\$10,577.38	\$148.33	\$21,548.98
		Qty: 1	\$10,823	\$10,577	\$148	\$21,549
Assm: 09020403	Descr: Gas Fired Unit Heater, 300 MBH, Spark Ignition	UOM: EA	\$3,016.12	\$839.47	\$1.70	\$3,857.29
		Qty: 112	\$337,806	\$94,021	\$190	\$432,017
Assm: 09030209	Descr: 15 Ton Condensing Unit With Refrigerant Piping	UOM: EA	\$8,123.97	\$3,365.04	\$0.00	\$11,489.01
		Qty: 2	\$16,248	\$6,730	\$0	\$22,978
Assm: 09040703	Descr: Toilet Exhaust .2 MCFM	UOM: MCFM	\$1,116.15	\$1,667.16	\$0.00	\$2,783.31
		Qty: 1	\$659	\$984	\$0	\$1,642

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 09040727	Descr: Ventilation System, 64.8 MCFM	UOM: MCFM	\$418.17	\$71.07	\$0.00	\$489.24
		Qty: 359	\$150,205	\$25,530	\$0	\$175,735
Assm: 09040765	Descr: 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	UOM: MCFM	\$3,520.33	\$790.73	\$0.00	\$4,311.06
		Qty: 10	\$34,781	\$7,812	\$0	\$42,593
Assm: 09049907	Descr: Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	UOM: MCFM	\$1,370.16	\$1,955.73	\$0.00	\$3,325.89
		Qty: 0	\$356	\$508	\$0	\$865
Assm: 09049921	Descr: 2.0 MCFM Air Dist Sys With Heat Pump	UOM: MCFM	\$3,706.36	\$4,390.65	\$0.00	\$8,097.01
		Qty: 2	\$8,636	\$10,230	\$0	\$18,866
Assm: 09049923	Descr: 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	UOM: MCFM	\$1,645.75	\$4,920.50	\$0.00	\$6,566.24
		Qty: 2	\$2,847	\$8,512	\$0	\$11,360
Assm: 09060107	Descr: Control System For Cooling Unit	UOM: EA	\$122.32	\$58.85	\$0.00	\$181.17
		Qty: 2	\$245	\$118	\$0	\$362
Assm: 09060182	Descr: Controls For Ventilating System	UOM: EA	\$19,211.52	\$29,488.79	\$0.00	\$48,700.31
		Qty: 1	\$19,212	\$29,489	\$0	\$48,700
Assm: 09070201	Descr: Test & Balance, Cent Fan/Utility Set	UOM: EA	\$0.00	\$206.44	\$0.00	\$206.44
		Qty: 35	\$0	\$7,225	\$0	\$7,225
Assm: 09070202	Descr: Test & Balance H&V Unit/In Line Fan	UOM: EA	\$0.00	\$309.73	\$0.00	\$309.73
		Qty: 58	\$0	\$17,964	\$0	\$17,964
Assm: 09070206	Descr: Test & Balance Air Handler, Low Pressure	UOM: EA	\$0.00	\$413.28	\$0.00	\$413.28
		Qty: 3	\$0	\$1,240	\$0	\$1,240
Assm: 09070211	Descr: Test & Balance Vav Box	UOM: EA	\$39.90	\$68.74	\$0.00	\$108.64
		Qty: 1	\$40	\$69	\$0	\$109

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 10010104	Descr: Fire Prot Water Supply, (40'H) Ord Haz Fac	UOM: EA	\$48.03	\$21.35	\$0.22	\$69.60
		Qty: 4962	\$238,327	\$105,928	\$1,089	\$345,344
Assm: 10020101	Descr: Exposed Sprinkler System For A Lg Facility - Ord. Haz.	UOM: EA	\$28.44	\$81.42	\$0.00	\$109.86
		Qty: 4962	\$141,102	\$404,000	\$0	\$545,102
Assm: 11010108	Descr: Electrical 2500A Main Transformer	UOM: EA	\$29,512.44	\$4,886.87	\$96.72	\$34,496.03
		Qty: 1	\$29,512	\$4,887	\$97	\$34,496
Assm: 11010211	Descr: Electrical 2500A Secondary	UOM: EA	\$37,780.63	\$23,682.69	\$47.01	\$61,510.33
		Qty: 1	\$37,781	\$23,683	\$47	\$61,510
Assm: 11010311	Descr: Electrical 2500A Main Switchboard	UOM: EA	\$91,215.75	\$9,632.58	\$0.00	\$100,848.33
		Qty: 1	\$91,216	\$9,633	\$0	\$100,848
Assm: 11010403	Descr: (45-90 Amps 480V) 75 KVA Dry Type Transformer	UOM: EA	\$2,149.90	\$1,038.62	\$0.00	\$3,188.52
		Qty: 9	\$19,349	\$9,348	\$0	\$28,697
Assm: 11010502	Descr: Panelbd 208V 100A 30 Cir Mlo W/Bkr	UOM: EA	\$1,153.60	\$899.36	\$0.00	\$2,052.95
		Qty: 8	\$9,229	\$7,195	\$0	\$16,424
Assm: 11010507	Descr: Panelbd 208V 225A 42 Cir Mlo W/Bkr	UOM: EA	\$1,772.16	\$2,235.15	\$0.00	\$4,007.30
		Qty: 8	\$14,177	\$17,881	\$0	\$32,058
Assm: 11010516	Descr: Panelbd 208V 225A MCB 42 Cir W/Bkr	UOM: EA	\$2,088.56	\$2,391.53	\$0.00	\$4,480.09
		Qty: 1	\$2,089	\$2,392	\$0	\$4,480
Assm: 11010561	Descr: Panelbd 480V 600A MCB 42 Cir W/Bkr	UOM: EA	\$7,082.74	\$3,958.17	\$0.00	\$11,040.92
		Qty: 2	\$14,165	\$7,916	\$0	\$22,082
Assm: 11010604	Descr: Enclosed Cir Bkr 600V 225A	UOM: EA	\$1,805.61	\$1,767.07	\$0.00	\$3,572.68
		Qty: 1	\$1,806	\$1,767	\$0	\$3,573

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>		
Assm:	12010102	Descr:	Fire Alarm System - Rate Of Rise Heat Detectors	UOM:	OUT	\$102.32	\$374.83	\$0.00	\$477.15
				Qty:	192	\$19,646	\$71,968	\$0	\$91,614
Assm:	12010119	Descr:	16 Zone FACP, Annun And Transmitter	UOM:	EA	\$6,181.75	\$3,465.03	\$0.00	\$9,646.78
				Qty:	2	\$12,363	\$6,930	\$0	\$19,294
Assm:	12010301	Descr:	Telephone System, 2 Pair	UOM:	EA	\$42.39	\$176.98	\$0.00	\$219.38
				Qty:	55	\$2,332	\$9,734	\$0	\$12,066
Assm:	12010402	Descr:	Public Address For Large Warehouse	UOM:	SF	\$0.03	\$0.07	\$0.00	\$0.10
				Qty:	570584	\$16,889	\$40,968	\$0	\$57,857
Assm:	12010601	Descr:	Clock System	UOM:	EA	\$222.34	\$177.74	\$0.00	\$400.08
				Qty:	25	\$5,559	\$4,444	\$0	\$10,002
Assm:	12010602	Descr:	Time Clock System	UOM:	EA	\$334.18	\$866.03	\$0.00	\$1,200.22
				Qty:	9	\$3,008	\$7,794	\$0	\$10,802
Assm:	12020221	Descr:	Battery Charger	UOM:	EA	\$1,043.18	\$619.45	\$0.00	\$1,662.63
				Qty:	34	\$35,468	\$21,061	\$0	\$56,529
Assm:	12020401	Descr:	Lightning Protection System	UOM:	EA	\$78.54	\$141.38	\$0.00	\$219.92
				Qty:	30	\$2,356	\$4,241	\$0	\$6,598
Assm:	12020601	Descr:	Energy Management Control System	UOM:	PTS	\$932.47	\$401.74	\$0.00	\$1,334.21
				Qty:	97	\$90,449	\$38,969	\$0	\$129,418
FSA:	ID: CVN	Name:	COVERED EXTERIOR ENTRYWAY						
Facility Type:	Primary	ID: 46	Name:	UnClass Soil Storage Warehouse 3					
Assm:	06039002	Descr:	Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
				Qty:	108	\$623	\$705	\$0	\$1,327

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>		
Assm:	11020229	Descr:	100W Hps Wall Mount	UOM:	EA	\$175.34	\$236.30	\$0.00	\$411.64
				Qty:	1	\$175	\$236	\$0	\$412
<hr/>									
Assm:	11020235	Descr:	150 Watt Hps Recessed Fixture	UOM:	EA	\$215.09	\$246.25	\$0.00	\$461.34
				Qty:	1	\$215	\$246	\$0	\$461

FSA: ID: CVT **Name:** COVERED EXTERIOR LOADING DOCK W/LEVELER

Facility Type: Primary **ID:** 46 **Name:** UnClass Soil Storage Warehouse 3

Assm:	06039002	Descr:	Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
				Qty:	1061	\$6,117	\$6,923	\$0	\$13,039
Assm:	11020136	Descr:	Equipment Connections For Up To 5 HP	UOM:	EA	\$267.15	\$527.09	\$0.00	\$794.24
				Qty:	1	\$267	\$527	\$0	\$794
Assm:	11020254	Descr:	High Bay 400W Hps Fixture	UOM:	EA	\$200.94	\$375.90	\$0.00	\$576.85
				Qty:	4	\$804	\$1,504	\$0	\$2,307
Assm:	11020280	Descr:	Dock Lights	UOM:	EA	\$123.71	\$227.24	\$0.00	\$350.95
				Qty:	2	\$247	\$454	\$0	\$702
Assm:	13010602	Descr:	6'0" X 8'0" Long 10 Ton Capacity With Stairs	UOM:	DOCK	\$4,942.83	\$1,428.71	\$40.13	\$6,411.67
				Qty:	1	\$4,943	\$1,429	\$40	\$6,412
Assm:	13010606	Descr:	24" Deep Dock Leveler Pit Wall W/Stl Angle	UOM:	EA	\$483.17	\$1,116.94	\$1.04	\$1,601.14
				Qty:	1	\$483	\$1,117	\$1	\$1,601

FSA: ID: MEL **Name:** MECHANICAL, ELECTRICAL, & BUILDING SUPPORT

Facility Type: Primary **ID:** 46 **Name:** UnClass Soil Storage Warehouse 3

Assm:	05010114	Descr:	Non-Load Bearing 8 X 8 X 16 Concrete Block	UOM:	SF	\$2.34	\$5.03	\$0.00	\$7.37
				Qty:	337	\$788	\$1,695	\$0	\$2,483

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM: SF		\$0.29	\$0.72	\$0.00	\$1.00
		Qty: 668		\$192	\$479	\$0	\$671
Assm: 06030301	Descr: 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	UOM: SF		\$0.32	\$0.59	\$0.00	\$0.92
		Qty: 56		\$18	\$33	\$0	\$51
Assm: 06030704	Descr: Suspension System For Gypsum Board Ceiling	UOM: SF		\$0.75	\$4.08	\$0.00	\$4.83
		Qty: 56		\$42	\$228	\$0	\$270
Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM: EA		\$31.01	\$170.59	\$0.00	\$201.60
		Qty: 2		\$62	\$341	\$0	\$403
Assm: 11020156	Descr: 120V 20A Single Pole Switch	UOM: EA		\$25.89	\$148.76	\$0.00	\$174.65
		Qty: 1		\$26	\$149	\$0	\$175
Assm: 11020276	Descr: Porcelain Lamp Holder	UOM: EA		\$21.47	\$177.99	\$0.00	\$199.46
		Qty: 1		\$21	\$178	\$0	\$199

FSA: **ID:** SRM **Name:** STOCKROOM

Facility Type: Primary **ID:** 46 **Name:** UnClass Soil Storage Warehouse 3

Assm: 05010112	Descr: Non-Load Brg Partition Of 8 X 6 X 16 Concrete	UOM: SF		\$1.97	\$3.68	\$0.00	\$5.65
		Qty: 18778		\$36,906	\$69,184	\$0	\$106,090
Assm: 05010126	Descr: Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	UOM: SF		\$1.68	\$1.66	\$0.00	\$3.34
		Qty: 139792		\$234,655	\$231,565	\$0	\$466,220
Assm: 05010127	Descr: Wire Mesh Partitions, 4' Wide X 20' High	UOM: SF		\$3.37	\$1.04	\$0.00	\$4.41
		Qty: 3901		\$13,144	\$4,039	\$0	\$17,184
Assm: 05039014	Descr: Sliding Metal Clad Door (With Motor)	UOM: SF		\$35.54	\$9.59	\$0.00	\$45.13
		Qty: 7231		\$257,009	\$69,340	\$0	\$326,349

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM: SF		\$0.29	\$0.72	\$0.00	\$1.00
		Qty: 11265		\$3,235	\$8,084	\$0	\$11,319
Assm: 06029001	Descr: Concrete Floor Sealer	UOM: SF		\$0.04	\$0.05	\$0.00	\$0.08
		Qty: 568936		\$20,994	\$27,252	\$0	\$48,246
Assm: 06029003	Descr: Floor Hardener, Non-Metallic Light Service	UOM: SF		\$0.18	\$0.32	\$0.00	\$0.49
		Qty: 568936		\$101,441	\$179,727	\$0	\$281,168
Assm: 11020103	Descr: Duplex Receptacle Long Run	UOM: EA		\$48.69	\$297.44	\$0.00	\$346.13
		Qty: 240		\$11,687	\$71,386	\$0	\$83,072
Assm: 11020136	Descr: Equipment Connections For Up To 5 HP	UOM: EA		\$267.15	\$527.09	\$0.00	\$794.24
		Qty: 175		\$46,751	\$92,240	\$0	\$138,991
Assm: 11020229	Descr: 100W Hps Wall Mount	UOM: EA		\$175.34	\$236.30	\$0.00	\$411.64
		Qty: 72		\$12,625	\$17,013	\$0	\$29,638
Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM: EA		\$200.94	\$375.90	\$0.00	\$576.85
		Qty: 931		\$187,080	\$349,963	\$0	\$537,043
Assm: 11020255	Descr: High Bay 400W Hps Fixture With Quartz Standby	UOM: EA		\$296.72	\$467.99	\$0.00	\$764.70
		Qty: 125		\$37,089	\$58,498	\$0	\$95,588
Assm: 11020272	Descr: Exit Light With Battery Backup	UOM: EA		\$117.22	\$212.56	\$0.00	\$329.78
		Qty: 21		\$2,462	\$4,464	\$0	\$6,925
FSA:	ID:	Name:	Building Shell				
Facility Type:	Primary	ID: 47	Name:	Class Soil Storage Warehouse 1			
Assm: 01010103	Descr: 1'0" X 3'0" Strip Footing 3000 PSI	UOM: LF		\$11.15	\$10.90	\$0.17	\$22.22
		Qty: 3875		\$43,219	\$42,235	\$657	\$86,111

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 01010105	Descr: 1'6" X 4'0" Strip Footing 3000 PSI	UOM: LF	\$21.62	\$17.86	\$0.29	\$39.77
		Qty: 2144	\$46,360	\$38,301	\$627	\$85,288
Assm: 01010112	Descr: 1'3" X 2'6" Grade Beam 4000 PSI	UOM: LF	\$20.15	\$26.26	\$0.21	\$46.63
		Qty: 3875	\$78,103	\$101,778	\$804	\$180,685
Assm: 01010117	Descr: 16" Masonry Wall Foundation - 24" Deep Wall	UOM: LF	\$14.13	\$21.63	\$0.07	\$35.83
		Qty: 4289	\$60,596	\$92,771	\$316	\$153,683
Assm: 01010201	Descr: Spread Footing	UOM: CY	\$73.57	\$45.75	\$2.16	\$121.48
		Qty: 1144	\$84,160	\$52,341	\$2,471	\$138,972
Assm: 01010212	Descr: Column Piers 2'0" X 2'0" X 3'0" High	UOM: EA	\$87.34	\$173.72	\$1.69	\$262.75
		Qty: 206	\$17,993	\$35,786	\$349	\$54,127
Assm: 01010241	Descr: Spread Footing, Reinforcing Steel	UOM: TON	\$551.26	\$645.22	\$0.00	\$1,196.47
		Qty: 12	\$6,869	\$8,039	\$0	\$14,908
Assm: 01029050	Descr: Tie Beams (Seismic Modification)	UOM: LF	\$14.64	\$18.55	\$0.16	\$33.35
		Qty: 11730	\$171,700	\$217,640	\$1,897	\$391,237
Assm: 01030104	Descr: 7" Standard Slab On Grade	UOM: SF	\$2.01	\$2.62	\$0.16	\$4.79
		Qty: 478386	\$961,556	\$1,253,898	\$76,685	\$2,292,139
Assm: 01030115	Descr: Loading Dock Apron	UOM: SF	\$3.89	\$2.31	\$0.08	\$6.28
		Qty: 30313	\$117,978	\$70,126	\$2,401	\$190,505
Assm: 02020204	Descr: 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	UOM: SF	\$5.99	\$8.06	\$0.09	\$14.14
		Qty: 197119	\$1,180,861	\$1,587,991	\$18,608	\$2,787,460
Assm: 02020313	Descr: Precast/Prestressed Roof Members	UOM: SF	\$4.96	\$1.19	\$0.34	\$6.49
		Qty: 531604	\$2,636,968	\$632,556	\$180,533	\$3,450,057

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 02020314	Descr: 3" Topping Slab	UOM: SF	\$0.77	\$0.57	\$0.04	\$1.38
		Qty: 531604	\$410,186	\$300,835	\$21,264	\$732,285
Assm: 03010103	Descr: Tilt-Up Wall Panel 5-1/2" Thick	UOM: SF	\$11.02	\$1.21	\$0.17	\$12.40
		Qty: 38635	\$425,901	\$46,702	\$6,607	\$479,209
Assm: 03010147	Descr: Additional Vertical Reinforcement And Grouting; Seismic	UOM: SF	\$0.23	\$0.36	\$0.03	\$0.62
		Qty: 38635	\$8,863	\$13,982	\$974	\$23,818
Assm: 03010205	Descr: Loose Fill 8" Block Insulation	UOM: SF	\$0.51	\$0.46	\$0.00	\$0.98
		Qty: 38635	\$19,731	\$17,958	\$0	\$37,688
Assm: 03010312	Descr: Paint CMU/Concrete	UOM: SF	\$0.19	\$0.53	\$0.00	\$0.72
		Qty: 38635	\$7,159	\$20,596	\$0	\$27,755
Assm: 03010501	Descr: Fixed Blade Exterior Louver With Baked Enamel Finish	UOM: SF	\$29.84	\$12.28	\$0.00	\$42.12
		Qty: 875	\$26,109	\$10,744	\$0	\$36,853
Assm: 03030101	Descr: 3'0" X 7'0" Aluminum And Glass Door	UOM: EA	\$608.95	\$579.12	\$0.00	\$1,188.07
		Qty: 3	\$1,827	\$1,737	\$0	\$3,564
Assm: 03030202	Descr: 3'0" X 7'0" Hollow Metal Door W/Frame	UOM: EA	\$1,287.09	\$468.13	\$0.00	\$1,755.22
		Qty: 16	\$20,593	\$7,490	\$0	\$28,084
Assm: 03030204	Descr: 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	UOM: EA	\$2,328.71	\$734.80	\$0.00	\$3,063.51
		Qty: 3	\$6,986	\$2,204	\$0	\$9,191
Assm: 03040103	Descr: 20'0" X 14'0" Metal Overhead Door	UOM: EA	\$3,536.29	\$1,914.35	\$99.90	\$5,550.54
		Qty: 32	\$113,161	\$61,259	\$3,197	\$177,617
Assm: 04010108	Descr: Standing Seam Metal Roof	UOM: SF	\$2.03	\$1.26	\$0.00	\$3.29
		Qty: 531604	\$1,079,688	\$668,811	\$0	\$1,748,499

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	04010302	Descr: Rigid Insulation 1-1/2" Thick	UOM:	SF	\$0.35	\$0.24	\$0.00	\$0.59
			Qty:	531604	\$187,284	\$128,170	\$0	\$315,454
Assm:	04010503	Descr: Skylights, Plastic Insulated Domes	UOM:	SF	\$23.64	\$4.31	\$0.00	\$27.94
			Qty:	5090	\$120,306	\$21,932	\$0	\$142,238
Assm:	04010601	Descr: 5" Box Gutters With Downspouts	UOM:	LF	\$1.59	\$3.61	\$0.00	\$5.20
			Qty:	170	\$271	\$615	\$0	\$886
Assm:	08020101	Descr: Copper Pipe & Fittings	UOM:	EA	\$203.76	\$720.72	\$0.00	\$924.48
			Qty:	20	\$4,075	\$14,414	\$0	\$18,490
Assm:	08020201	Descr: Valves & Hydrants	UOM:	EA	\$90.94	\$25.08	\$0.00	\$116.03
			Qty:	11	\$1,000	\$276	\$0	\$1,276
Assm:	08020401	Descr: Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	UOM:	EA	\$78.67	\$82.34	\$0.00	\$161.01
			Qty:	20	\$1,573	\$1,647	\$0	\$3,220
Assm:	08030101	Descr: Waste Pipe & Fittings	UOM:	EA	\$180.14	\$361.88	\$0.00	\$542.02
			Qty:	26	\$4,684	\$9,409	\$0	\$14,093
Assm:	08030202	Descr: PVC Vent Piping	UOM:	EA	\$13.95	\$47.57	\$0.00	\$61.51
			Qty:	26	\$363	\$1,237	\$0	\$1,599
Assm:	08030305	Descr: Heavy Duty Cast Iron Floor Drains	UOM:	EA	\$409.55	\$63.67	\$0.00	\$473.21
			Qty:	5	\$2,048	\$318	\$0	\$2,366
Assm:	08050102	Descr: Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	UOM:	EA	\$299.10	\$172.74	\$0.00	\$471.84
			Qty:	2	\$598	\$345	\$0	\$944
Assm:	08050108	Descr: Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	UOM:	EA	\$400.59	\$43.19	\$0.00	\$443.77
			Qty:	3	\$1,202	\$130	\$0	\$1,331

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 08060201	Descr: Acid Waste System For Battery & Acid Rooms	UOM:	EA	\$2,609.25	\$939.01	\$0.00	\$3,548.25
		Qty:	2	\$5,218	\$1,878	\$0	\$7,097
Assm: 08060204	Descr: Special Plumbing For Battery And Acid Rooms	UOM:	EA	\$362.85	\$935.23	\$0.00	\$1,298.08
		Qty:	2	\$726	\$1,870	\$0	\$2,596
Assm: 08060304	Descr: Interceptors For Battery & Acid Rooms	UOM:	EA	\$1,401.67	\$222.85	\$0.00	\$1,624.52
		Qty:	1	\$1,402	\$223	\$0	\$1,625
Assm: 09010211	Descr: 18000 MBH Gas Supply	UOM:	EA	\$10,823.28	\$10,577.38	\$148.33	\$21,548.98
		Qty:	1	\$10,823	\$10,577	\$148	\$21,549
Assm: 09020403	Descr: Gas Fired Unit Heater, 300 MBH, Spark Ignition	UOM:	EA	\$3,016.12	\$839.47	\$1.70	\$3,857.29
		Qty:	90	\$271,451	\$75,553	\$153	\$347,156
Assm: 09030210	Descr: 20 Ton Condensing Unit With Refrigerant Piping	UOM:	EA	\$16,247.49	\$7,178.80	\$0.00	\$23,426.29
		Qty:	1	\$16,247	\$7,179	\$0	\$23,426
Assm: 09040703	Descr: Toilet Exhaust .2 MCFM	UOM:	MCFM	\$1,116.15	\$1,667.16	\$0.00	\$2,783.31
		Qty:	0	\$525	\$784	\$0	\$1,308
Assm: 09040727	Descr: Ventilation System, 64.8 MCFM	UOM:	MCFM	\$418.17	\$71.07	\$0.00	\$489.24
		Qty:	289	\$120,850	\$20,540	\$0	\$141,390
Assm: 09040765	Descr: 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	UOM:	MCFM	\$3,520.33	\$790.73	\$0.00	\$4,311.06
		Qty:	8	\$27,987	\$6,286	\$0	\$34,273
Assm: 09049907	Descr: Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	UOM:	MCFM	\$1,370.16	\$1,955.73	\$0.00	\$3,325.89
		Qty:	0	\$288	\$411	\$0	\$698
Assm: 09049921	Descr: 2.0 MCFM Air Dist Sys With Heat Pump	UOM:	MCFM	\$3,706.36	\$4,390.65	\$0.00	\$8,097.01
		Qty:	2	\$6,968	\$8,254	\$0	\$15,222

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 09049923	Descr: 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	UOM: MCFM		\$1,645.75	\$4,920.50	\$0.00	\$6,566.24
		Qty: 1		\$2,288	\$6,839	\$0	\$9,127
Assm: 09060107	Descr: Control System For Cooling Unit	UOM: EA		\$122.32	\$58.85	\$0.00	\$181.17
		Qty: 1		\$122	\$59	\$0	\$181
Assm: 09060182	Descr: Controls For Ventilating System	UOM: EA		\$19,211.52	\$29,488.79	\$0.00	\$48,700.31
		Qty: 1		\$19,212	\$29,489	\$0	\$48,700
Assm: 09070201	Descr: Test & Balance, Cent Fan/Utility Set	UOM: EA		\$0.00	\$206.44	\$0.00	\$206.44
		Qty: 28		\$0	\$5,780	\$0	\$5,780
Assm: 09070202	Descr: Test & Balance H&V Unit/In Line Fan	UOM: EA		\$0.00	\$309.73	\$0.00	\$309.73
		Qty: 46		\$0	\$14,248	\$0	\$14,248
Assm: 09070206	Descr: Test & Balance Air Handler, Low Pressure	UOM: EA		\$0.00	\$413.28	\$0.00	\$413.28
		Qty: 2		\$0	\$827	\$0	\$827
Assm: 09070211	Descr: Test & Balance Vav Box	UOM: EA		\$39.90	\$68.74	\$0.00	\$108.64
		Qty: 1		\$40	\$69	\$0	\$109
Assm: 10010104	Descr: Fire Prot Water Supply, (40'H) Ord Haz Fac	UOM: EA		\$48.03	\$21.35	\$0.22	\$69.60
		Qty: 4160		\$199,807	\$88,807	\$913	\$289,527
Assm: 10020101	Descr: Exposed Sprinkler System For A Lg Facility - Ord. Haz.	UOM: EA		\$28.44	\$81.42	\$0.00	\$109.86
		Qty: 4160		\$118,296	\$338,702	\$0	\$456,998
Assm: 11010107	Descr: Ungrd 2000 Amp Main Transformer	UOM: EA		\$25,284.04	\$4,296.94	\$84.17	\$29,665.15
		Qty: 1		\$25,284	\$4,297	\$84	\$29,665
Assm: 11010210	Descr: Ungrd 2000 Amp Secondary	UOM: EA		\$24,757.16	\$15,830.50	\$33.58	\$40,621.24
		Qty: 1		\$24,757	\$15,831	\$34	\$40,621

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm:	11010310	Descr: Ungrd 2000 Amp Main Switchboard	UOM:	EA	\$102,879.41	\$11,704.28	\$0.00	\$114,583.70
			Qty:	1	\$102,879	\$11,704	\$0	\$114,584
Assm:	11010402	Descr: (30-45 Amps 480V) 37.5 KVA Dry Type Transformer	UOM:	EA	\$1,367.54	\$843.36	\$0.00	\$2,210.90
			Qty:	6	\$8,205	\$5,060	\$0	\$13,265
Assm:	11010403	Descr: (45-90 Amps 480V) 75 KVA Dry Type Transformer	UOM:	EA	\$2,149.90	\$1,038.62	\$0.00	\$3,188.52
			Qty:	3	\$6,450	\$3,116	\$0	\$9,566
Assm:	11010404	Descr: (90-135 Amps 480V) 112.5 KVA Dry Type Transformer	UOM:	EA	\$2,559.47	\$933.62	\$106.03	\$3,599.13
			Qty:	2	\$5,119	\$1,867	\$212	\$7,198
Assm:	11010501	Descr: Panelbd 208V 100A 24 Cir Mlo W/Bkr	UOM:	EA	\$882.61	\$1,140.56	\$0.00	\$2,023.17
			Qty:	7	\$6,178	\$7,984	\$0	\$14,162
Assm:	11010506	Descr: Panelbd 208V 225A 36 Cir Mlo W/Bkr	UOM:	EA	\$1,554.41	\$2,086.31	\$0.00	\$3,640.72
			Qty:	5	\$7,772	\$10,432	\$0	\$18,204
Assm:	11010507	Descr: Panelbd 208V 225A 42 Cir Mlo W/Bkr	UOM:	EA	\$1,772.16	\$2,235.15	\$0.00	\$4,007.30
			Qty:	4	\$7,089	\$8,941	\$0	\$16,029
Assm:	11010536	Descr: Panelbd 480V 225A 36 Cir Mlo W/Bkr	UOM:	EA	\$2,296.82	\$2,123.79	\$0.00	\$4,420.61
			Qty:	4	\$9,187	\$8,495	\$0	\$17,682
Assm:	11010537	Descr: Panelbd 480V 225A 42 Cir Mlo W/Bkr	UOM:	EA	\$2,950.05	\$2,311.21	\$0.00	\$5,261.26
			Qty:	3	\$8,850	\$6,934	\$0	\$15,784
Assm:	11010541	Descr: Panelbd 480V 400A 42 Cir Mlo W/Bkr	UOM:	EA	\$3,383.52	\$2,561.48	\$0.00	\$5,944.99
			Qty:	2	\$6,767	\$5,123	\$0	\$11,890
Assm:	11010602	Descr: Enclosed Cir Bkr 600V 60A	UOM:	EA	\$691.57	\$1,188.21	\$0.00	\$1,879.78
			Qty:	5	\$3,458	\$5,941	\$0	\$9,399

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 11010603	Descr: Enclosed Cir Bkr 600V 100A	UOM: EA	\$1,967.78	\$2,379.44	\$0.00	\$4,347.21
		Qty: 3	\$5,903	\$7,138	\$0	\$13,042
Assm: 11010604	Descr: Enclosed Cir Bkr 600V 225A	UOM: EA	\$1,805.61	\$1,767.07	\$0.00	\$3,572.68
		Qty: 5	\$9,028	\$8,835	\$0	\$17,863
Assm: 11010609	Descr: Enclosed Cir Bkr 600V 30A	UOM: EA	\$260.10	\$281.26	\$0.00	\$541.36
		Qty: 8	\$2,081	\$2,250	\$0	\$4,331
Assm: 12010102	Descr: Fire Alarm System - Rate Of Rise Heat Detectors	UOM: OUT	\$102.32	\$374.83	\$0.00	\$477.15
		Qty: 162	\$16,576	\$60,723	\$0	\$77,299
Assm: 12010119	Descr: 16 Zone FACP, Annun And Transmitter	UOM: EA	\$6,181.75	\$3,465.03	\$0.00	\$9,646.78
		Qty: 1	\$6,182	\$3,465	\$0	\$9,647
Assm: 12010301	Descr: Telephone System, 2 Pair	UOM: EA	\$42.39	\$176.98	\$0.00	\$219.38
		Qty: 46	\$1,950	\$8,141	\$0	\$10,091
Assm: 12010402	Descr: Public Address For Large Warehouse	UOM: SF	\$0.03	\$0.07	\$0.00	\$0.10
		Qty: 478388	\$14,160	\$34,348	\$0	\$48,509
Assm: 12010601	Descr: Clock System	UOM: EA	\$222.34	\$177.74	\$0.00	\$400.08
		Qty: 21	\$4,669	\$3,733	\$0	\$8,402
Assm: 12010602	Descr: Time Clock System	UOM: EA	\$334.18	\$866.03	\$0.00	\$1,200.22
		Qty: 8	\$2,673	\$6,928	\$0	\$9,602
Assm: 12020221	Descr: Battery Charger	UOM: EA	\$1,043.18	\$619.45	\$0.00	\$1,662.63
		Qty: 29	\$30,252	\$17,964	\$0	\$48,216
Assm: 12020401	Descr: Lightning Protection System	UOM: EA	\$78.54	\$141.38	\$0.00	\$219.92
		Qty: 25	\$1,964	\$3,534	\$0	\$5,498

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	12020601	Descr:	Energy Management Control System	UOM:	PTS	\$932.47	\$401.74	\$0.00	\$1,334.21
				Qty:	81	\$75,530	\$32,541	\$0	\$108,071

FSA: **ID:** CVN **Name:** COVERED EXTERIOR ENTRYWAY

Facility Type: Primary **ID:** 47 **Name:** Class Soil Storage Warehouse 1

Assm:	06039002	Descr:	Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
				Qty:	108	\$623	\$705	\$0	\$1,327

Assm:	11020229	Descr:	100W Hps Wall Mount	UOM:	EA	\$175.34	\$236.30	\$0.00	\$411.64
				Qty:	1	\$175	\$236	\$0	\$412

Assm:	11020235	Descr:	150 Watt Hps Recessed Fixture	UOM:	EA	\$215.09	\$246.25	\$0.00	\$461.34
				Qty:	1	\$215	\$246	\$0	\$461

FSA: **ID:** CVT **Name:** COVERED EXTERIOR LOADING DOCK W/LEVELER

Facility Type: Primary **ID:** 47 **Name:** Class Soil Storage Warehouse 1

Assm:	06039002	Descr:	Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
				Qty:	1061	\$6,117	\$6,923	\$0	\$13,039

Assm:	11020136	Descr:	Equipment Connections For Up To 5 HP	UOM:	EA	\$267.15	\$527.09	\$0.00	\$794.24
				Qty:	1	\$267	\$527	\$0	\$794

Assm:	11020254	Descr:	High Bay 400W Hps Fixture	UOM:	EA	\$200.94	\$375.90	\$0.00	\$576.85
				Qty:	4	\$804	\$1,504	\$0	\$2,307

Assm:	11020280	Descr:	Dock Lights	UOM:	EA	\$123.71	\$227.24	\$0.00	\$350.95
				Qty:	2	\$247	\$454	\$0	\$702

Assm:	13010602	Descr:	6'0" X 8'0" Long 10 Ton Capacity With Stairs	UOM:	DOCK	\$4,942.83	\$1,428.71	\$40.13	\$6,411.67
				Qty:	1	\$4,943	\$1,429	\$40	\$6,412

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	13010606	Descr: 24" Deep Dock Leveler Pit Wall W/Stl Angle	UOM:	EA	\$483.17	\$1,116.94	\$1.04	\$1,601.14
			Qty:	1	\$483	\$1,117	\$1	\$1,601

FSA: ID: MEL Name: MECHANICAL, ELECTRICAL, & BUILDING SUPPORT

Facility Type: Primary ID: 47 Name: Class Soil Storage Warehouse 1

Assm:	05010114	Descr: Non-Load Bearing 8 X 8 X 16 Concrete Block	UOM:	SF	\$2.34	\$5.03	\$0.00	\$7.37
			Qty:	337	\$788	\$1,695	\$0	\$2,483

Assm:	06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
			Qty:	668	\$192	\$479	\$0	\$671

Assm:	06030301	Descr: 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	UOM:	SF	\$0.32	\$0.59	\$0.00	\$0.92
			Qty:	56	\$18	\$33	\$0	\$51

Assm:	06030704	Descr: Suspension System For Gypsum Board Ceiling	UOM:	SF	\$0.75	\$4.08	\$0.00	\$4.83
			Qty:	56	\$42	\$228	\$0	\$270

Assm:	11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
			Qty:	2	\$62	\$341	\$0	\$403

Assm:	11020156	Descr: 120V 20A Single Pole Switch	UOM:	EA	\$25.89	\$148.76	\$0.00	\$174.65
			Qty:	1	\$26	\$149	\$0	\$175

Assm:	11020276	Descr: Porcelain Lamp Holder	UOM:	EA	\$21.47	\$177.99	\$0.00	\$199.46
			Qty:	1	\$21	\$178	\$0	\$199

FSA: ID: SRM Name: STOCKROOM

Facility Type: Primary ID: 47 Name: Class Soil Storage Warehouse 1

Assm:	05010112	Descr: Non-Load Brg Partition Of 8 X 6 X 16 Concrete	UOM:	SF	\$1.97	\$3.68	\$0.00	\$5.65
			Qty:	15735	\$30,926	\$57,972	\$0	\$88,898

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 05010126	Descr: Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	UOM: SF	\$1.68	\$1.66	\$0.00	\$3.34
		Qty: 117139	\$196,630	\$194,041	\$0	\$390,670
Assm: 05010127	Descr: Wire Mesh Partitions, 4' Wide X 20' High	UOM: SF	\$3.37	\$1.04	\$0.00	\$4.41
		Qty: 3269	\$11,015	\$3,385	\$0	\$14,400
Assm: 05039014	Descr: Sliding Metal Clad Door (With Motor)	UOM: SF	\$35.54	\$9.59	\$0.00	\$45.13
		Qty: 6059	\$215,353	\$58,102	\$0	\$273,454
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM: SF	\$0.29	\$0.72	\$0.00	\$1.00
		Qty: 9439	\$2,711	\$6,773	\$0	\$9,484
Assm: 06029001	Descr: Concrete Floor Sealer	UOM: SF	\$0.04	\$0.05	\$0.00	\$0.08
		Qty: 476740	\$17,592	\$22,836	\$0	\$40,428
Assm: 06029003	Descr: Floor Hardener, Non-Metallic Light Service	UOM: SF	\$0.18	\$0.32	\$0.00	\$0.49
		Qty: 476740	\$85,003	\$150,602	\$0	\$235,605
Assm: 11020103	Descr: Duplex Receptacle Long Run	UOM: EA	\$48.69	\$297.44	\$0.00	\$346.13
		Qty: 201	\$9,788	\$59,785	\$0	\$69,573
Assm: 11020136	Descr: Equipment Connections For Up To 5 HP	UOM: EA	\$267.15	\$527.09	\$0.00	\$794.24
		Qty: 147	\$39,271	\$77,482	\$0	\$116,753
Assm: 11020229	Descr: 100W Hps Wall Mount	UOM: EA	\$175.34	\$236.30	\$0.00	\$411.64
		Qty: 60	\$10,521	\$14,178	\$0	\$24,698
Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM: EA	\$200.94	\$375.90	\$0.00	\$576.85
		Qty: 780	\$156,737	\$293,202	\$0	\$449,939
Assm: 11020255	Descr: High Bay 400W Hps Fixture With Quartz Standby	UOM: EA	\$296.72	\$467.99	\$0.00	\$764.70
		Qty: 105	\$31,155	\$49,138	\$0	\$80,294

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>		
Assm:	11020272	Descr:	Exit Light With Battery Backup	UOM:	EA	\$117.22	\$212.56	\$0.00	\$329.78
				Qty:	17	\$1,993	\$3,613	\$0	\$5,606
FSA:	ID:	Name:	Building Shell						
Facility Type:	Primary	ID:	48	Name:	Class Soil Storage Warehouse 2				
Assm:	01010103	Descr:	1'0" X 3'0" Strip Footing 3000 PSI	UOM:	LF	\$11.15	\$10.90	\$0.17	\$22.22
				Qty:	3875	\$43,219	\$42,235	\$657	\$86,111
Assm:	01010105	Descr:	1'6" X 4'0" Strip Footing 3000 PSI	UOM:	LF	\$21.62	\$17.86	\$0.29	\$39.77
				Qty:	2144	\$46,360	\$38,301	\$627	\$85,288
Assm:	01010112	Descr:	1'3" X 2'6" Grade Beam 4000 PSI	UOM:	LF	\$20.15	\$26.26	\$0.21	\$46.63
				Qty:	3875	\$78,103	\$101,778	\$804	\$180,685
Assm:	01010117	Descr:	16" Masonry Wall Foundation - 24" Deep Wall	UOM:	LF	\$14.13	\$21.63	\$0.07	\$35.83
				Qty:	4289	\$60,596	\$92,771	\$316	\$153,683
Assm:	01010201	Descr:	Spread Footing	UOM:	CY	\$73.57	\$45.75	\$2.16	\$121.48
				Qty:	1144	\$84,160	\$52,341	\$2,471	\$138,972
Assm:	01010212	Descr:	Column Piers 2'0" X 2'0" X 3'0" High	UOM:	EA	\$87.34	\$173.72	\$1.69	\$262.75
				Qty:	206	\$17,993	\$35,786	\$349	\$54,127
Assm:	01010241	Descr:	Spread Footing, Reinforcing Steel	UOM:	TON	\$551.26	\$645.22	\$0.00	\$1,196.47
				Qty:	12	\$6,869	\$8,039	\$0	\$14,908
Assm:	01029050	Descr:	Tie Beams (Seismic Modification)	UOM:	LF	\$14.64	\$18.55	\$0.16	\$33.35
				Qty:	11730	\$171,700	\$217,640	\$1,897	\$391,237
Assm:	01030104	Descr:	7" Standard Slab On Grade	UOM:	SF	\$2.01	\$2.62	\$0.16	\$4.79
				Qty:	478386	\$961,556	\$1,253,898	\$76,685	\$2,292,139

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 01030115	Descr: Loading Dock Apron	UOM: SF	\$3.89	\$2.31	\$0.08	\$6.28
		Qty: 30313	\$117,978	\$70,126	\$2,401	\$190,505
Assm: 02020204	Descr: 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	UOM: SF	\$5.99	\$8.06	\$0.09	\$14.14
		Qty: 197119	\$1,180,861	\$1,587,991	\$18,608	\$2,787,460
Assm: 02020313	Descr: Precast/Prestressed Roof Members	UOM: SF	\$4.96	\$1.19	\$0.34	\$6.49
		Qty: 531604	\$2,636,968	\$632,556	\$180,533	\$3,450,057
Assm: 02020314	Descr: 3" Topping Slab	UOM: SF	\$0.77	\$0.57	\$0.04	\$1.38
		Qty: 531604	\$410,186	\$300,835	\$21,264	\$732,285
Assm: 03010103	Descr: Tilt-Up Wall Panel 5-1/2" Thick	UOM: SF	\$11.02	\$1.21	\$0.17	\$12.40
		Qty: 38635	\$425,901	\$46,702	\$6,607	\$479,209
Assm: 03010147	Descr: Additional Vertical Reinforcement And Grouting; Seismic	UOM: SF	\$0.23	\$0.36	\$0.03	\$0.62
		Qty: 38635	\$8,863	\$13,982	\$974	\$23,818
Assm: 03010205	Descr: Loose Fill 8" Block Insulation	UOM: SF	\$0.51	\$0.46	\$0.00	\$0.98
		Qty: 38635	\$19,731	\$17,958	\$0	\$37,688
Assm: 03010312	Descr: Paint CMU/Concrete	UOM: SF	\$0.19	\$0.53	\$0.00	\$0.72
		Qty: 38635	\$7,159	\$20,596	\$0	\$27,755
Assm: 03010501	Descr: Fixed Blade Exterior Louver With Baked Enamel Finish	UOM: SF	\$29.84	\$12.28	\$0.00	\$42.12
		Qty: 875	\$26,109	\$10,744	\$0	\$36,853
Assm: 03030101	Descr: 3'0" X 7'0" Aluminum And Glass Door	UOM: EA	\$608.95	\$579.12	\$0.00	\$1,188.07
		Qty: 3	\$1,827	\$1,737	\$0	\$3,564
Assm: 03030202	Descr: 3'0" X 7'0" Hollow Metal Door W/Frame	UOM: EA	\$1,287.09	\$468.13	\$0.00	\$1,755.22
		Qty: 16	\$20,593	\$7,490	\$0	\$28,084

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 03030204	Descr: 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	UOM: EA	\$2,328.71	\$734.80	\$0.00	\$3,063.51
		Qty: 3	\$6,986	\$2,204	\$0	\$9,191
Assm: 03040103	Descr: 20'0" X 14'0" Metal Overhead Door	UOM: EA	\$3,536.29	\$1,914.35	\$99.90	\$5,550.54
		Qty: 32	\$113,161	\$61,259	\$3,197	\$177,617
Assm: 04010108	Descr: Standing Seam Metal Roof	UOM: SF	\$2.03	\$1.26	\$0.00	\$3.29
		Qty: 531604	\$1,079,688	\$668,811	\$0	\$1,748,499
Assm: 04010302	Descr: Rigid Insulation 1-1/2" Thick	UOM: SF	\$0.35	\$0.24	\$0.00	\$0.59
		Qty: 531604	\$187,284	\$128,170	\$0	\$315,454
Assm: 04010503	Descr: Skylights, Plastic Insulated Domes	UOM: SF	\$23.64	\$4.31	\$0.00	\$27.94
		Qty: 5090	\$120,306	\$21,932	\$0	\$142,238
Assm: 04010601	Descr: 5" Box Gutters With Downspouts	UOM: LF	\$1.59	\$3.61	\$0.00	\$5.20
		Qty: 170	\$271	\$615	\$0	\$886
Assm: 08020101	Descr: Copper Pipe & Fittings	UOM: EA	\$203.76	\$720.72	\$0.00	\$924.48
		Qty: 20	\$4,075	\$14,414	\$0	\$18,490
Assm: 08020201	Descr: Valves & Hydrants	UOM: EA	\$90.94	\$25.08	\$0.00	\$116.03
		Qty: 11	\$1,000	\$276	\$0	\$1,276
Assm: 08020401	Descr: Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	UOM: EA	\$78.67	\$82.34	\$0.00	\$161.01
		Qty: 20	\$1,573	\$1,647	\$0	\$3,220
Assm: 08030101	Descr: Waste Pipe & Fittings	UOM: EA	\$180.14	\$361.88	\$0.00	\$542.02
		Qty: 26	\$4,684	\$9,409	\$0	\$14,093
Assm: 08030202	Descr: PVC Vent Piping	UOM: EA	\$13.95	\$47.57	\$0.00	\$61.51
		Qty: 26	\$363	\$1,237	\$0	\$1,599

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	08030305	Descr:	Heavy Duty Cast Iron Floor Drains	UOM:	EA	\$409.55	\$63.67	\$0.00	\$473.21
				Qty:	5	\$2,048	\$318	\$0	\$2,366
Assm:	08050102	Descr:	Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	UOM:	EA	\$299.10	\$172.74	\$0.00	\$471.84
				Qty:	2	\$598	\$345	\$0	\$944
Assm:	08050108	Descr:	Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	UOM:	EA	\$400.59	\$43.19	\$0.00	\$443.77
				Qty:	3	\$1,202	\$130	\$0	\$1,331
Assm:	08060201	Descr:	Acid Waste System For Battery & Acid Rooms	UOM:	EA	\$2,609.25	\$939.01	\$0.00	\$3,548.25
				Qty:	2	\$5,218	\$1,878	\$0	\$7,097
Assm:	08060204	Descr:	Special Plumbing For Battery And Acid Rooms	UOM:	EA	\$362.85	\$935.23	\$0.00	\$1,298.08
				Qty:	2	\$726	\$1,870	\$0	\$2,596
Assm:	08060304	Descr:	Interceptors For Battery & Acid Rooms	UOM:	EA	\$1,401.67	\$222.85	\$0.00	\$1,624.52
				Qty:	1	\$1,402	\$223	\$0	\$1,625
Assm:	09010211	Descr:	18000 MBH Gas Supply	UOM:	EA	\$10,823.28	\$10,577.38	\$148.33	\$21,548.98
				Qty:	1	\$10,823	\$10,577	\$148	\$21,549
Assm:	09020403	Descr:	Gas Fired Unit Heater, 300 MBH, Spark Ignition	UOM:	EA	\$3,016.12	\$839.47	\$1.70	\$3,857.29
				Qty:	90	\$271,451	\$75,553	\$153	\$347,156
Assm:	09030210	Descr:	20 Ton Condensing Unit With Refrigerant Piping	UOM:	EA	\$16,247.49	\$7,178.80	\$0.00	\$23,426.29
				Qty:	1	\$16,247	\$7,179	\$0	\$23,426
Assm:	09040703	Descr:	Toilet Exhaust .2 MCFM	UOM:	MCFM	\$1,116.15	\$1,667.16	\$0.00	\$2,783.31
				Qty:	0	\$525	\$784	\$0	\$1,308
Assm:	09040727	Descr:	Ventilation System, 64.8 MCFM	UOM:	MCFM	\$418.17	\$71.07	\$0.00	\$489.24
				Qty:	289	\$120,850	\$20,540	\$0	\$141,390

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 09040765	Descr: 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	UOM: MCFM	\$3,520.33	\$790.73	\$0.00	\$4,311.06
		Qty: 8	\$27,987	\$6,286	\$0	\$34,273
Assm: 09049907	Descr: Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	UOM: MCFM	\$1,370.16	\$1,955.73	\$0.00	\$3,325.89
		Qty: 0	\$288	\$411	\$0	\$698
Assm: 09049921	Descr: 2.0 MCFM Air Dist Sys With Heat Pump	UOM: MCFM	\$3,706.36	\$4,390.65	\$0.00	\$8,097.01
		Qty: 2	\$6,968	\$8,254	\$0	\$15,222
Assm: 09049923	Descr: 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	UOM: MCFM	\$1,645.75	\$4,920.50	\$0.00	\$6,566.24
		Qty: 1	\$2,288	\$6,839	\$0	\$9,127
Assm: 09060107	Descr: Control System For Cooling Unit	UOM: EA	\$122.32	\$58.85	\$0.00	\$181.17
		Qty: 1	\$122	\$59	\$0	\$181
Assm: 09060182	Descr: Controls For Ventilating System	UOM: EA	\$19,211.52	\$29,488.79	\$0.00	\$48,700.31
		Qty: 1	\$19,212	\$29,489	\$0	\$48,700
Assm: 09070201	Descr: Test & Balance, Cent Fan/Utility Set	UOM: EA	\$0.00	\$206.44	\$0.00	\$206.44
		Qty: 28	\$0	\$5,780	\$0	\$5,780
Assm: 09070202	Descr: Test & Balance H&V Unit/In Line Fan	UOM: EA	\$0.00	\$309.73	\$0.00	\$309.73
		Qty: 46	\$0	\$14,248	\$0	\$14,248
Assm: 09070206	Descr: Test & Balance Air Handler, Low Pressure	UOM: EA	\$0.00	\$413.28	\$0.00	\$413.28
		Qty: 2	\$0	\$827	\$0	\$827
Assm: 09070211	Descr: Test & Balance Vav Box	UOM: EA	\$39.90	\$68.74	\$0.00	\$108.64
		Qty: 1	\$40	\$69	\$0	\$109
Assm: 10010104	Descr: Fire Prot Water Supply, (40'H) Ord Haz Fac	UOM: EA	\$48.03	\$21.35	\$0.22	\$69.60
		Qty: 4160	\$199,807	\$88,807	\$913	\$289,527

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 10020101	Descr: Exposed Sprinkler System For A Lg Facility - Ord. Haz.	UOM: EA	\$28.44	\$81.42	\$0.00	\$109.86
		Qty: 4160	\$118,296	\$338,702	\$0	\$456,998
Assm: 11010107	Descr: Ungrd 2000 Amp Main Transformer	UOM: EA	\$25,284.04	\$4,296.94	\$84.17	\$29,665.15
		Qty: 1	\$25,284	\$4,297	\$84	\$29,665
Assm: 11010210	Descr: Ungrd 2000 Amp Secondary	UOM: EA	\$24,757.16	\$15,830.50	\$33.58	\$40,621.24
		Qty: 1	\$24,757	\$15,831	\$34	\$40,621
Assm: 11010310	Descr: Ungrd 2000 Amp Main Switchboard	UOM: EA	\$102,879.41	\$11,704.28	\$0.00	\$114,583.70
		Qty: 1	\$102,879	\$11,704	\$0	\$114,584
Assm: 11010402	Descr: (30-45 Amps 480V) 37.5 KVA Dry Type Transformer	UOM: EA	\$1,367.54	\$843.36	\$0.00	\$2,210.90
		Qty: 6	\$8,205	\$5,060	\$0	\$13,265
Assm: 11010403	Descr: (45-90 Amps 480V) 75 KVA Dry Type Transformer	UOM: EA	\$2,149.90	\$1,038.62	\$0.00	\$3,188.52
		Qty: 3	\$6,450	\$3,116	\$0	\$9,566
Assm: 11010404	Descr: (90-135 Amps 480V) 112.5 KVA Dry Type Transformer	UOM: EA	\$2,559.47	\$933.62	\$106.03	\$3,599.13
		Qty: 2	\$5,119	\$1,867	\$212	\$7,198
Assm: 11010501	Descr: Panelbd 208V 100A 24 Cir Mlo W/Bkr	UOM: EA	\$882.61	\$1,140.56	\$0.00	\$2,023.17
		Qty: 7	\$6,178	\$7,984	\$0	\$14,162
Assm: 11010506	Descr: Panelbd 208V 225A 36 Cir Mlo W/Bkr	UOM: EA	\$1,554.41	\$2,086.31	\$0.00	\$3,640.72
		Qty: 5	\$7,772	\$10,432	\$0	\$18,204
Assm: 11010507	Descr: Panelbd 208V 225A 42 Cir Mlo W/Bkr	UOM: EA	\$1,772.16	\$2,235.15	\$0.00	\$4,007.30
		Qty: 4	\$7,089	\$8,941	\$0	\$16,029
Assm: 11010536	Descr: Panelbd 480V 225A 36 Cir Mlo W/Bkr	UOM: EA	\$2,296.82	\$2,123.79	\$0.00	\$4,420.61
		Qty: 4	\$9,187	\$8,495	\$0	\$17,682

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 11010537	Descr: Panelbd 480V 225A 42 Cir Mlo W/Bkr	UOM:	EA	\$2,950.05	\$2,311.21	\$0.00	\$5,261.26
		Qty:	3	\$8,850	\$6,934	\$0	\$15,784
Assm: 11010541	Descr: Panelbd 480V 400A 42 Cir Mlo W/Bkr	UOM:	EA	\$3,383.52	\$2,561.48	\$0.00	\$5,944.99
		Qty:	2	\$6,767	\$5,123	\$0	\$11,890
Assm: 11010602	Descr: Enclosed Cir Bkr 600V 60A	UOM:	EA	\$691.57	\$1,188.21	\$0.00	\$1,879.78
		Qty:	5	\$3,458	\$5,941	\$0	\$9,399
Assm: 11010603	Descr: Enclosed Cir Bkr 600V 100A	UOM:	EA	\$1,967.78	\$2,379.44	\$0.00	\$4,347.21
		Qty:	3	\$5,903	\$7,138	\$0	\$13,042
Assm: 11010604	Descr: Enclosed Cir Bkr 600V 225A	UOM:	EA	\$1,805.61	\$1,767.07	\$0.00	\$3,572.68
		Qty:	5	\$9,028	\$8,835	\$0	\$17,863
Assm: 11010609	Descr: Enclosed Cir Bkr 600V 30A	UOM:	EA	\$260.10	\$281.26	\$0.00	\$541.36
		Qty:	8	\$2,081	\$2,250	\$0	\$4,331
Assm: 12010102	Descr: Fire Alarm System - Rate Of Rise Heat Detectors	UOM:	OUT	\$102.32	\$374.83	\$0.00	\$477.15
		Qty:	162	\$16,576	\$60,723	\$0	\$77,299
Assm: 12010119	Descr: 16 Zone FACP, Annun And Transmitter	UOM:	EA	\$6,181.75	\$3,465.03	\$0.00	\$9,646.78
		Qty:	1	\$6,182	\$3,465	\$0	\$9,647
Assm: 12010301	Descr: Telephone System, 2 Pair	UOM:	EA	\$42.39	\$176.98	\$0.00	\$219.38
		Qty:	46	\$1,950	\$8,141	\$0	\$10,091
Assm: 12010402	Descr: Public Address For Large Warehouse	UOM:	SF	\$0.03	\$0.07	\$0.00	\$0.10
		Qty:	478388	\$14,160	\$34,348	\$0	\$48,509
Assm: 12010601	Descr: Clock System	UOM:	EA	\$222.34	\$177.74	\$0.00	\$400.08
		Qty:	21	\$4,669	\$3,733	\$0	\$8,402

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	12010602	Descr:	Time Clock System	UOM:	EA	\$334.18	\$866.03	\$0.00	\$1,200.22
				Qty:	8	\$2,673	\$6,928	\$0	\$9,602
Assm:	12020221	Descr:	Battery Charger	UOM:	EA	\$1,043.18	\$619.45	\$0.00	\$1,662.63
				Qty:	29	\$30,252	\$17,964	\$0	\$48,216
Assm:	12020401	Descr:	Lightning Protection System	UOM:	EA	\$78.54	\$141.38	\$0.00	\$219.92
				Qty:	25	\$1,964	\$3,534	\$0	\$5,498
Assm:	12020601	Descr:	Energy Management Control System	UOM:	PTS	\$932.47	\$401.74	\$0.00	\$1,334.21
				Qty:	81	\$75,530	\$32,541	\$0	\$108,071

FSA: ID: CVN Name: COVERED EXTERIOR ENTRYWAY

Facility Type: Primary ID: 48 Name: Class Soil Storage Warehouse 2

Assm:	06039002	Descr:	Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
				Qty:	108	\$623	\$705	\$0	\$1,327
Assm:	11020229	Descr:	100W Hps Wall Mount	UOM:	EA	\$175.34	\$236.30	\$0.00	\$411.64
				Qty:	1	\$175	\$236	\$0	\$412
Assm:	11020235	Descr:	150 Watt Hps Recessed Fixture	UOM:	EA	\$215.09	\$246.25	\$0.00	\$461.34
				Qty:	1	\$215	\$246	\$0	\$461

FSA: ID: CVT Name: COVERED EXTERIOR LOADING DOCK W/LEVELER

Facility Type: Primary ID: 48 Name: Class Soil Storage Warehouse 2

Assm:	06039002	Descr:	Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
				Qty:	1061	\$6,117	\$6,923	\$0	\$13,039
Assm:	11020136	Descr:	Equipment Connections For Up To 5 HP	UOM:	EA	\$267.15	\$527.09	\$0.00	\$794.24
				Qty:	1	\$267	\$527	\$0	\$794

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM:	EA	\$200.94	\$375.90	\$0.00	\$576.85
		Qty:	4	\$804	\$1,504	\$0	\$2,307
Assm: 11020280	Descr: Dock Lights	UOM:	EA	\$123.71	\$227.24	\$0.00	\$350.95
		Qty:	2	\$247	\$454	\$0	\$702
Assm: 13010602	Descr: 6'0" X 8'0" Long 10 Ton Capacity With Stairs	UOM:	DOCK	\$4,942.83	\$1,428.71	\$40.13	\$6,411.67
		Qty:	1	\$4,943	\$1,429	\$40	\$6,412
Assm: 13010606	Descr: 24" Deep Dock Leveler Pit Wall W/Stl Angle	UOM:	EA	\$483.17	\$1,116.94	\$1.04	\$1,601.14
		Qty:	1	\$483	\$1,117	\$1	\$1,601

FSA: ID: MEL Name: MECHANICAL, ELECTRICAL, & BUILDING SUPPORT

Facility Type: Primary ID: 48 Name: Class Soil Storage Warehouse 2

Assm: 05010114	Descr: Non-Load Bearing 8 X 8 X 16 Concrete Block	UOM:	SF	\$2.34	\$5.03	\$0.00	\$7.37
		Qty:	337	\$788	\$1,695	\$0	\$2,483
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
		Qty:	668	\$192	\$479	\$0	\$671
Assm: 06030301	Descr: 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	UOM:	SF	\$0.32	\$0.59	\$0.00	\$0.92
		Qty:	56	\$18	\$33	\$0	\$51
Assm: 06030704	Descr: Suspension System For Gypsum Board Ceiling	UOM:	SF	\$0.75	\$4.08	\$0.00	\$4.83
		Qty:	56	\$42	\$228	\$0	\$270
Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
		Qty:	2	\$62	\$341	\$0	\$403
Assm: 11020156	Descr: 120V 20A Single Pole Switch	UOM:	EA	\$25.89	\$148.76	\$0.00	\$174.65
		Qty:	1	\$26	\$149	\$0	\$175

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>			
Assm:	11020276	Descr:	Porcelain Lamp Holder	UOM:	EA	\$21.47	\$177.99	\$0.00	\$199.46	
				Qty:	1	\$21	\$178	\$0	\$199	
FSA:	ID:	SRM	Name:	STOCKROOM						
Facility Type:	Primary	ID:	48	Name:	Class Soil Storage Warehouse 2					
Assm:	05010112	Descr:	Non-Load Brg Partition Of 8 X 6 X 16 Concrete		UOM:	SF	\$1.97	\$3.68	\$0.00	\$5.65
					Qty:	15735	\$30,926	\$57,972	\$0	\$88,898
Assm:	05010126	Descr:	Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation		UOM:	SF	\$1.68	\$1.66	\$0.00	\$3.34
					Qty:	117139	\$196,630	\$194,041	\$0	\$390,670
Assm:	05010127	Descr:	Wire Mesh Partitions, 4' Wide X 20' High		UOM:	SF	\$3.37	\$1.04	\$0.00	\$4.41
					Qty:	3269	\$11,015	\$3,385	\$0	\$14,400
Assm:	05039014	Descr:	Sliding Metal Clad Door (With Motor)		UOM:	SF	\$35.54	\$9.59	\$0.00	\$45.13
					Qty:	6059	\$215,353	\$58,102	\$0	\$273,454
Assm:	06010502	Descr:	Paint To Concrete Block Using Brushes, Two Coats		UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
					Qty:	9439	\$2,711	\$6,773	\$0	\$9,484
Assm:	06029001	Descr:	Concrete Floor Sealer		UOM:	SF	\$0.04	\$0.05	\$0.00	\$0.08
					Qty:	476740	\$17,592	\$22,836	\$0	\$40,428
Assm:	06029003	Descr:	Floor Hardener, Non-Metallic Light Service		UOM:	SF	\$0.18	\$0.32	\$0.00	\$0.49
					Qty:	476740	\$85,003	\$150,602	\$0	\$235,605
Assm:	11020103	Descr:	Duplex Receptacle Long Run		UOM:	EA	\$48.69	\$297.44	\$0.00	\$346.13
					Qty:	201	\$9,788	\$59,785	\$0	\$69,573
Assm:	11020136	Descr:	Equipment Connections For Up To 5 HP		UOM:	EA	\$267.15	\$527.09	\$0.00	\$794.24
					Qty:	147	\$39,271	\$77,482	\$0	\$116,753

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	11020229	Descr:	100W Hps Wall Mount	UOM:	EA	\$175.34	\$236.30	\$0.00	\$411.64
				Qty:	60	\$10,521	\$14,178	\$0	\$24,698
Assm:	11020254	Descr:	High Bay 400W Hps Fixture	UOM:	EA	\$200.94	\$375.90	\$0.00	\$576.85
				Qty:	780	\$156,737	\$293,202	\$0	\$449,939
Assm:	11020255	Descr:	High Bay 400W Hps Fixture With Quartz Standby	UOM:	EA	\$296.72	\$467.99	\$0.00	\$764.70
				Qty:	105	\$31,155	\$49,138	\$0	\$80,294
Assm:	11020272	Descr:	Exit Light With Battery Backup	UOM:	EA	\$117.22	\$212.56	\$0.00	\$329.78
				Qty:	17	\$1,993	\$3,613	\$0	\$5,606

FSA: **ID:** **Name:** Building Shell

Facility Type: Primary **ID:** 49 **Name:** UnClass Waste Storage Warehouse

Assm:	01010103	Descr:	1'0" X 3'0" Strip Footing 3000 PSI	UOM:	LF	\$11.15	\$10.90	\$0.17	\$22.22
				Qty:	4622	\$51,550	\$50,376	\$784	\$102,709
Assm:	01010105	Descr:	1'6" X 4'0" Strip Footing 3000 PSI	UOM:	LF	\$21.62	\$17.86	\$0.29	\$39.77
				Qty:	2558	\$55,296	\$45,684	\$748	\$101,728
Assm:	01010112	Descr:	1'3" X 2'6" Grade Beam 4000 PSI	UOM:	LF	\$20.15	\$26.26	\$0.21	\$46.63
				Qty:	4622	\$93,158	\$121,396	\$959	\$215,512
Assm:	01010117	Descr:	16" Masonry Wall Foundation - 24" Deep Wall	UOM:	LF	\$14.13	\$21.63	\$0.07	\$35.83
				Qty:	5116	\$72,275	\$110,653	\$377	\$183,305
Assm:	01010201	Descr:	Spread Footing	UOM:	CY	\$73.57	\$45.75	\$2.16	\$121.48
				Qty:	1360	\$100,050	\$62,224	\$2,937	\$165,211
Assm:	01010212	Descr:	Column Piers 2'0" X 2'0" X 3'0" High	UOM:	EA	\$87.34	\$173.72	\$1.69	\$262.75
				Qty:	245	\$21,399	\$42,561	\$414	\$64,374

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 01010241	Descr: Spread Footing, Reinforcing Steel	UOM: TON	\$551.26	\$645.22	\$0.00	\$1,196.47
		Qty: 15	\$8,164	\$9,556	\$0	\$17,720
Assm: 01029050	Descr: Tie Beams (Seismic Modification)	UOM: LF	\$14.64	\$18.55	\$0.16	\$33.35
		Qty: 13991	\$204,791	\$259,584	\$2,262	\$466,637
Assm: 01030104	Descr: 7" Standard Slab On Grade	UOM: SF	\$2.01	\$2.62	\$0.16	\$4.79
		Qty: 570581	\$1,146,868	\$1,495,550	\$91,464	\$2,733,882
Assm: 01030115	Descr: Loading Dock Apron	UOM: SF	\$3.89	\$2.31	\$0.08	\$6.28
		Qty: 36155	\$140,715	\$83,641	\$2,863	\$227,220
Assm: 02020204	Descr: 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	UOM: SF	\$5.99	\$8.06	\$0.09	\$14.14
		Qty: 235108	\$1,408,438	\$1,894,030	\$22,194	\$3,324,662
Assm: 02020313	Descr: Precast/Prestressed Roof Members	UOM: SF	\$4.96	\$1.19	\$0.34	\$6.49
		Qty: 634056	\$3,145,171	\$754,463	\$215,325	\$4,114,960
Assm: 02020314	Descr: 3" Topping Slab	UOM: SF	\$0.77	\$0.57	\$0.04	\$1.38
		Qty: 634056	\$489,238	\$358,812	\$25,362	\$873,412
Assm: 03010103	Descr: Tilt-Up Wall Panel 5-1/2" Thick	UOM: SF	\$11.02	\$1.21	\$0.17	\$12.40
		Qty: 42194	\$465,134	\$51,004	\$7,215	\$523,353
Assm: 03010147	Descr: Additional Vertical Reinforcement And Grouting; Seismic	UOM: SF	\$0.23	\$0.36	\$0.03	\$0.62
		Qty: 42194	\$9,679	\$15,270	\$1,063	\$26,013
Assm: 03010205	Descr: Loose Fill 8" Block Insulation	UOM: SF	\$0.51	\$0.46	\$0.00	\$0.98
		Qty: 42194	\$21,548	\$19,612	\$0	\$41,160
Assm: 03010312	Descr: Paint CMU/Concrete	UOM: SF	\$0.19	\$0.53	\$0.00	\$0.72
		Qty: 42194	\$7,819	\$22,494	\$0	\$30,312

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 03010501	Descr: Fixed Blade Exterior Louver With Baked Enamel Finish	UOM: SF	\$29.84	\$12.28	\$0.00	\$42.12
		Qty: 956	\$28,526	\$11,738	\$0	\$40,264
Assm: 03030101	Descr: 3'0" X 7'0" Aluminum And Glass Door	UOM: EA	\$608.95	\$579.12	\$0.00	\$1,188.07
		Qty: 3	\$1,827	\$1,737	\$0	\$3,564
Assm: 03030202	Descr: 3'0" X 7'0" Hollow Metal Door W/Frame	UOM: EA	\$1,287.09	\$468.13	\$0.00	\$1,755.22
		Qty: 20	\$25,742	\$9,363	\$0	\$35,104
Assm: 03030204	Descr: 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	UOM: EA	\$2,328.71	\$734.80	\$0.00	\$3,063.51
		Qty: 3	\$6,986	\$2,204	\$0	\$9,191
Assm: 03040103	Descr: 20'0" X 14'0" Metal Overhead Door	UOM: EA	\$3,536.29	\$1,914.35	\$99.90	\$5,550.54
		Qty: 38	\$134,379	\$72,745	\$3,796	\$210,921
Assm: 04010108	Descr: Standing Seam Metal Roof	UOM: SF	\$2.03	\$1.26	\$0.00	\$3.29
		Qty: 634056	\$1,287,768	\$797,706	\$0	\$2,085,474
Assm: 04010302	Descr: Rigid Insulation 1-1/2" Thick	UOM: SF	\$0.35	\$0.24	\$0.00	\$0.59
		Qty: 634056	\$223,378	\$152,871	\$0	\$376,249
Assm: 04010503	Descr: Skylights, Plastic Insulated Domes	UOM: SF	\$23.64	\$4.31	\$0.00	\$27.94
		Qty: 6071	\$143,492	\$26,159	\$0	\$169,652
Assm: 04010601	Descr: 5" Box Gutters With Downspouts	UOM: LF	\$1.59	\$3.61	\$0.00	\$5.20
		Qty: 180	\$287	\$650	\$0	\$937
Assm: 08020101	Descr: Copper Pipe & Fittings	UOM: EA	\$203.76	\$720.72	\$0.00	\$924.48
		Qty: 24	\$4,890	\$17,297	\$0	\$22,188
Assm: 08020201	Descr: Valves & Hydrants	UOM: EA	\$90.94	\$25.08	\$0.00	\$116.03
		Qty: 13	\$1,182	\$326	\$0	\$1,508

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm:	08020401	Descr: Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	UOM:	EA	\$78.67	\$82.34	\$0.00	\$161.01
			Qty:	24	\$1,888	\$1,976	\$0	\$3,864
Assm:	08030101	Descr: Waste Pipe & Fittings	UOM:	EA	\$180.14	\$361.88	\$0.00	\$542.02
			Qty:	30	\$5,404	\$10,856	\$0	\$16,261
Assm:	08030202	Descr: PVC Vent Piping	UOM:	EA	\$13.95	\$47.57	\$0.00	\$61.51
			Qty:	30	\$418	\$1,427	\$0	\$1,845
Assm:	08030305	Descr: Heavy Duty Cast Iron Floor Drains	UOM:	EA	\$409.55	\$63.67	\$0.00	\$473.21
			Qty:	6	\$2,457	\$382	\$0	\$2,839
Assm:	08050102	Descr: Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	UOM:	EA	\$299.10	\$172.74	\$0.00	\$471.84
			Qty:	2	\$598	\$345	\$0	\$944
Assm:	08050108	Descr: Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	UOM:	EA	\$400.59	\$43.19	\$0.00	\$443.77
			Qty:	3	\$1,202	\$130	\$0	\$1,331
Assm:	08060201	Descr: Acid Waste System For Battery & Acid Rooms	UOM:	EA	\$2,609.25	\$939.01	\$0.00	\$3,548.25
			Qty:	2	\$5,218	\$1,878	\$0	\$7,097
Assm:	08060204	Descr: Special Plumbing For Battery And Acid Rooms	UOM:	EA	\$362.85	\$935.23	\$0.00	\$1,298.08
			Qty:	2	\$726	\$1,870	\$0	\$2,596
Assm:	08060304	Descr: Interceptors For Battery & Acid Rooms	UOM:	EA	\$1,401.67	\$222.85	\$0.00	\$1,624.52
			Qty:	2	\$2,803	\$446	\$0	\$3,249
Assm:	09010211	Descr: 18000 MBH Gas Supply	UOM:	EA	\$10,823.28	\$10,577.38	\$148.33	\$21,548.98
			Qty:	1	\$10,823	\$10,577	\$148	\$21,549
Assm:	09020403	Descr: Gas Fired Unit Heater, 300 MBH, Spark Ignition	UOM:	EA	\$3,016.12	\$839.47	\$1.70	\$3,857.29
			Qty:	112	\$337,806	\$94,021	\$190	\$432,017

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	09030209	Descr:	15 Ton Condensing Unit With Refrigerant Piping	UOM:	EA	\$8,123.97	\$3,365.04	\$0.00	\$11,489.01
				Qty:	2	\$16,248	\$6,730	\$0	\$22,978
Assm:	09040703	Descr:	Toilet Exhaust .2 MCFM	UOM:	MCFM	\$1,116.15	\$1,667.16	\$0.00	\$2,783.31
				Qty:	1	\$659	\$984	\$0	\$1,642
Assm:	09040727	Descr:	Ventilation System, 64.8 MCFM	UOM:	MCFM	\$418.17	\$71.07	\$0.00	\$489.24
				Qty:	359	\$150,205	\$25,530	\$0	\$175,735
Assm:	09040765	Descr:	14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	UOM:	MCFM	\$3,520.33	\$790.73	\$0.00	\$4,311.06
				Qty:	10	\$34,781	\$7,812	\$0	\$42,593
Assm:	09049907	Descr:	Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	UOM:	MCFM	\$1,370.16	\$1,955.73	\$0.00	\$3,325.89
				Qty:	0	\$356	\$508	\$0	\$865
Assm:	09049921	Descr:	2.0 MCFM Air Dist Sys With Heat Pump	UOM:	MCFM	\$3,706.36	\$4,390.65	\$0.00	\$8,097.01
				Qty:	2	\$8,636	\$10,230	\$0	\$18,866
Assm:	09049923	Descr:	2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	UOM:	MCFM	\$1,645.75	\$4,920.50	\$0.00	\$6,566.24
				Qty:	2	\$2,847	\$8,512	\$0	\$11,360
Assm:	09060107	Descr:	Control System For Cooling Unit	UOM:	EA	\$122.32	\$58.85	\$0.00	\$181.17
				Qty:	2	\$245	\$118	\$0	\$362
Assm:	09060182	Descr:	Controls For Ventilating System	UOM:	EA	\$19,211.52	\$29,488.79	\$0.00	\$48,700.31
				Qty:	1	\$19,212	\$29,489	\$0	\$48,700
Assm:	09070201	Descr:	Test & Balance, Cent Fan/Utility Set	UOM:	EA	\$0.00	\$206.44	\$0.00	\$206.44
				Qty:	35	\$0	\$7,225	\$0	\$7,225
Assm:	09070202	Descr:	Test & Balance H&V Unit/In Line Fan	UOM:	EA	\$0.00	\$309.73	\$0.00	\$309.73
				Qty:	58	\$0	\$17,964	\$0	\$17,964

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 09070206	Descr: Test & Balance Air Handler, Low Pressure	UOM: EA	\$0.00	\$413.28	\$0.00	\$413.28
		Qty: 3	\$0	\$1,240	\$0	\$1,240
Assm: 09070211	Descr: Test & Balance Vav Box	UOM: EA	\$39.90	\$68.74	\$0.00	\$108.64
		Qty: 1	\$40	\$69	\$0	\$109
Assm: 10010104	Descr: Fire Prot Water Supply, (40'H) Ord Haz Fac	UOM: EA	\$48.03	\$21.35	\$0.22	\$69.60
		Qty: 4962	\$238,327	\$105,928	\$1,089	\$345,344
Assm: 10020101	Descr: Exposed Sprinkler System For A Lg Facility - Ord. Haz.	UOM: EA	\$28.44	\$81.42	\$0.00	\$109.86
		Qty: 4962	\$141,102	\$404,000	\$0	\$545,102
Assm: 11010108	Descr: Electrical 2500A Main Transformer	UOM: EA	\$29,512.44	\$4,886.87	\$96.72	\$34,496.03
		Qty: 1	\$29,512	\$4,887	\$97	\$34,496
Assm: 11010211	Descr: Electrical 2500A Secondary	UOM: EA	\$37,780.63	\$23,682.69	\$47.01	\$61,510.33
		Qty: 1	\$37,781	\$23,683	\$47	\$61,510
Assm: 11010311	Descr: Electrical 2500A Main Switchboard	UOM: EA	\$91,215.75	\$9,632.58	\$0.00	\$100,848.33
		Qty: 1	\$91,216	\$9,633	\$0	\$100,848
Assm: 11010403	Descr: (45-90 Amps 480V) 75 KVA Dry Type Transformer	UOM: EA	\$2,149.90	\$1,038.62	\$0.00	\$3,188.52
		Qty: 9	\$19,349	\$9,348	\$0	\$28,697
Assm: 11010502	Descr: Panelbd 208V 100A 30 Cir Mlo W/Bkr	UOM: EA	\$1,153.60	\$899.36	\$0.00	\$2,052.95
		Qty: 8	\$9,229	\$7,195	\$0	\$16,424
Assm: 11010507	Descr: Panelbd 208V 225A 42 Cir Mlo W/Bkr	UOM: EA	\$1,772.16	\$2,235.15	\$0.00	\$4,007.30
		Qty: 8	\$14,177	\$17,881	\$0	\$32,058
Assm: 11010516	Descr: Panelbd 208V 225A MCB 42 Cir W/Bkr	UOM: EA	\$2,088.56	\$2,391.53	\$0.00	\$4,480.09
		Qty: 1	\$2,089	\$2,392	\$0	\$4,480

Paces

Project Summary Report

Date 07/26/2002

						<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm:	11010561	Descr:	Panelbd 480V 600A MCB 42 Cir W/Bkr	UOM:	EA	\$7,082.74	\$3,958.17	\$0.00	\$11,040.92
				Qty:	2	\$14,165	\$7,916	\$0	\$22,082
Assm:	11010604	Descr:	Enclosed Cir Bkr 600V 225A	UOM:	EA	\$1,805.61	\$1,767.07	\$0.00	\$3,572.68
				Qty:	1	\$1,806	\$1,767	\$0	\$3,573
Assm:	12010102	Descr:	Fire Alarm System - Rate Of Rise Heat Detectors	UOM:	OUT	\$102.32	\$374.83	\$0.00	\$477.15
				Qty:	192	\$19,646	\$71,968	\$0	\$91,614
Assm:	12010119	Descr:	16 Zone FACP, Annun And Transmitter	UOM:	EA	\$6,181.75	\$3,465.03	\$0.00	\$9,646.78
				Qty:	2	\$12,363	\$6,930	\$0	\$19,294
Assm:	12010301	Descr:	Telephone System, 2 Pair	UOM:	EA	\$42.39	\$176.98	\$0.00	\$219.38
				Qty:	55	\$2,332	\$9,734	\$0	\$12,066
Assm:	12010402	Descr:	Public Address For Large Warehouse	UOM:	SF	\$0.03	\$0.07	\$0.00	\$0.10
				Qty:	570584	\$16,889	\$40,968	\$0	\$57,857
Assm:	12010601	Descr:	Clock System	UOM:	EA	\$222.34	\$177.74	\$0.00	\$400.08
				Qty:	25	\$5,559	\$4,444	\$0	\$10,002
Assm:	12010602	Descr:	Time Clock System	UOM:	EA	\$334.18	\$866.03	\$0.00	\$1,200.22
				Qty:	9	\$3,008	\$7,794	\$0	\$10,802
Assm:	12020221	Descr:	Battery Charger	UOM:	EA	\$1,043.18	\$619.45	\$0.00	\$1,662.63
				Qty:	34	\$35,468	\$21,061	\$0	\$56,529
Assm:	12020401	Descr:	Lightning Protection System	UOM:	EA	\$78.54	\$141.38	\$0.00	\$219.92
				Qty:	30	\$2,356	\$4,241	\$0	\$6,598
Assm:	12020601	Descr:	Energy Management Control System	UOM:	PTS	\$932.47	\$401.74	\$0.00	\$1,334.21
				Qty:	97	\$90,449	\$38,969	\$0	\$129,418

FSA: **ID:** CVN **Name:** COVERED EXTERIOR ENTRYWAY

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Facility Type:	Primary	ID: 49	Name: UnClass Waste Storage Warehouse				
Assm: 06039002	Descr: Exterior Canopy W/Framing	UOM: SF		\$5.76	\$6.52	\$0.00	\$12.29
		Qty: 108		\$623	\$705	\$0	\$1,327
Assm: 11020229	Descr: 100W Hps Wall Mount	UOM: EA		\$175.34	\$236.30	\$0.00	\$411.64
		Qty: 1		\$175	\$236	\$0	\$412
Assm: 11020235	Descr: 150 Watt Hps Recessed Fixture	UOM: EA		\$215.09	\$246.25	\$0.00	\$461.34
		Qty: 1		\$215	\$246	\$0	\$461
FSA:	ID: CVT	Name: COVERED EXTERIOR LOADING DOCK W/LEVELER					
Facility Type:	Primary	ID: 49	Name: UnClass Waste Storage Warehouse				
Assm: 06039002	Descr: Exterior Canopy W/Framing	UOM: SF		\$5.76	\$6.52	\$0.00	\$12.29
		Qty: 1061		\$6,117	\$6,923	\$0	\$13,039
Assm: 11020136	Descr: Equipment Connections For Up To 5 HP	UOM: EA		\$267.15	\$527.09	\$0.00	\$794.24
		Qty: 1		\$267	\$527	\$0	\$794
Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM: EA		\$200.94	\$375.90	\$0.00	\$576.85
		Qty: 4		\$804	\$1,504	\$0	\$2,307
Assm: 11020280	Descr: Dock Lights	UOM: EA		\$123.71	\$227.24	\$0.00	\$350.95
		Qty: 2		\$247	\$454	\$0	\$702
Assm: 13010602	Descr: 6'0" X 8'0" Long 10 Ton Capacity With Stairs	UOM: DOCK		\$4,942.83	\$1,428.71	\$40.13	\$6,411.67
		Qty: 1		\$4,943	\$1,429	\$40	\$6,412
Assm: 13010606	Descr: 24" Deep Dock Leveler Pit Wall W/Stl Angle	UOM: EA		\$483.17	\$1,116.94	\$1.04	\$1,601.14
		Qty: 1		\$483	\$1,117	\$1	\$1,601
FSA:	ID: MEL	Name: MECHANICAL, ELECTRICAL, & BUILDING SUPPORT					

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Facility Type:	Primary	ID: 49	Name: UnClass Waste Storage Warehouse				
Assm: 05010114	Descr: Non-Load Bearing 8 X 8 X 16 Concrete Block	UOM:	SF	\$2.34	\$5.03	\$0.00	\$7.37
		Qty:	337	\$788	\$1,695	\$0	\$2,483
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
		Qty:	668	\$192	\$479	\$0	\$671
Assm: 06030301	Descr: 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	UOM:	SF	\$0.32	\$0.59	\$0.00	\$0.92
		Qty:	56	\$18	\$33	\$0	\$51
Assm: 06030704	Descr: Suspension System For Gypsum Board Ceiling	UOM:	SF	\$0.75	\$4.08	\$0.00	\$4.83
		Qty:	56	\$42	\$228	\$0	\$270
Assm: 11020102	Descr: 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
		Qty:	2	\$62	\$341	\$0	\$403
Assm: 11020156	Descr: 120V 20A Single Pole Switch	UOM:	EA	\$25.89	\$148.76	\$0.00	\$174.65
		Qty:	1	\$26	\$149	\$0	\$175
Assm: 11020276	Descr: Porcelain Lamp Holder	UOM:	EA	\$21.47	\$177.99	\$0.00	\$199.46
		Qty:	1	\$21	\$178	\$0	\$199

FSA: ID: SRM Name: STOCKROOM

Facility Type:	Primary	ID: 49	Name: UnClass Waste Storage Warehouse				
Assm: 03010310	Descr: 5/8" Gypsum Board/Installed/Taped & Finished	UOM:	SF	\$5.93	\$0.59	\$0.00	\$6.52
		Qty:	51495	\$305,365	\$30,619	\$0	\$335,984
Assm: 05010112	Descr: Non-Load Brg Partition Of 8 X 6 X 16 Concrete	UOM:	SF	\$1.97	\$3.68	\$0.00	\$5.65
		Qty:	18778	\$36,906	\$69,184	\$0	\$106,090
Assm: 05010126	Descr: Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	UOM:	SF	\$1.68	\$1.66	\$0.00	\$3.34
		Qty:	139792	\$234,655	\$231,565	\$0	\$466,220

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 05010127	Descr: Wire Mesh Partitions, 4' Wide X 20' High	UOM: SF	\$3.37	\$1.04	\$0.00	\$4.41
		Qty: 3901	\$13,144	\$4,039	\$0	\$17,184
Assm: 05039014	Descr: Sliding Metal Clad Door (With Motor)	UOM: SF	\$35.54	\$9.59	\$0.00	\$45.13
		Qty: 7231	\$257,009	\$69,340	\$0	\$326,349
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM: SF	\$0.29	\$0.72	\$0.00	\$1.00
		Qty: 11265	\$3,235	\$8,084	\$0	\$11,319
Assm: 06029001	Descr: Concrete Floor Sealer	UOM: SF	\$0.04	\$0.05	\$0.00	\$0.08
		Qty: 568936	\$20,994	\$27,252	\$0	\$48,246
Assm: 06029003	Descr: Floor Hardener, Non-Metallic Light Service	UOM: SF	\$0.18	\$0.32	\$0.00	\$0.49
		Qty: 568936	\$101,441	\$179,727	\$0	\$281,168
Assm: 11020103	Descr: Duplex Receptacle Long Run	UOM: EA	\$48.69	\$297.44	\$0.00	\$346.13
		Qty: 240	\$11,687	\$71,386	\$0	\$83,072
Assm: 11020136	Descr: Equipment Connections For Up To 5 HP	UOM: EA	\$267.15	\$527.09	\$0.00	\$794.24
		Qty: 175	\$46,751	\$92,240	\$0	\$138,991
Assm: 11020229	Descr: 100W Hps Wall Mount	UOM: EA	\$175.34	\$236.30	\$0.00	\$411.64
		Qty: 72	\$12,625	\$17,013	\$0	\$29,638
Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM: EA	\$200.94	\$375.90	\$0.00	\$576.85
		Qty: 931	\$187,080	\$349,963	\$0	\$537,043
Assm: 11020255	Descr: High Bay 400W Hps Fixture With Quartz Standby	UOM: EA	\$296.72	\$467.99	\$0.00	\$764.70
		Qty: 125	\$37,089	\$58,498	\$0	\$95,588
Assm: 11020272	Descr: Exit Light With Battery Backup	UOM: EA	\$117.22	\$212.56	\$0.00	\$329.78
		Qty: 21	\$2,462	\$4,464	\$0	\$6,925

FSA: **ID:** **Name:** Building Shell

Project Summary Report

Date 07/26/2002

					Mat \$	Lab \$	Eqp \$	Ttl \$		
Facility Type:		Primary	ID: 50	Name:	Classified Waste Storage Warehouse					
Assm:	01010103	Descr: 1'0" X 3'0" Strip Footing 3000 PSI			UOM:	LF	\$11.15	\$10.90	\$0.17	\$22.22
					Qty:	843	\$9,400	\$9,186	\$143	\$18,729
Assm:	01010105	Descr: 1'6" X 4'0" Strip Footing 3000 PSI			UOM:	LF	\$21.62	\$17.86	\$0.29	\$39.77
					Qty:	466	\$10,083	\$8,330	\$136	\$18,550
Assm:	01010112	Descr: 1'3" X 2'6" Grade Beam 4000 PSI			UOM:	LF	\$20.15	\$26.26	\$0.21	\$46.63
					Qty:	843	\$16,987	\$22,137	\$175	\$39,299
Assm:	01010117	Descr: 16" Masonry Wall Foundation - 24" Deep Wall			UOM:	LF	\$14.13	\$21.63	\$0.07	\$35.83
					Qty:	933	\$13,179	\$20,178	\$69	\$33,426
Assm:	01010201	Descr: Spread Footing			UOM:	CY	\$73.57	\$45.75	\$2.16	\$121.48
					Qty:	100	\$7,357	\$4,575	\$216	\$12,148
Assm:	01010212	Descr: Column Piers 2'0" X 2'0" X 3'0" High			UOM:	EA	\$87.34	\$173.72	\$1.69	\$262.75
					Qty:	74	\$6,463	\$12,855	\$125	\$19,444
Assm:	01010241	Descr: Spread Footing, Reinforcing Steel			UOM:	TON	\$551.26	\$645.22	\$0.00	\$1,196.47
					Qty:	3	\$1,378	\$1,613	\$0	\$2,991
Assm:	01010277	Descr: Spread Footing Column Bolts			UOM:	EA	\$1.22	\$4.37	\$0.00	\$5.59
					Qty:	408	\$497	\$1,782	\$0	\$2,279
Assm:	01029050	Descr: Tie Beams (Seismic Modification)			UOM:	LF	\$14.64	\$18.55	\$0.16	\$33.35
					Qty:	2551	\$37,343	\$47,334	\$413	\$85,090
Assm:	01030104	Descr: 7" Standard Slab On Grade			UOM:	SF	\$2.01	\$2.62	\$0.16	\$4.79
					Qty:	104043	\$209,126	\$272,707	\$16,678	\$498,512
Assm:	01030115	Descr: Loading Dock Apron			UOM:	SF	\$3.89	\$2.31	\$0.08	\$6.28
					Qty:	6593	\$25,660	\$15,252	\$522	\$41,434

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 02020112	Descr: Lrg Span, Structural Stl, Hv Ld, Roof Frame	UOM: SF	\$4.48	\$1.48	\$0.34	\$6.30
		Qty: 115618	\$518,061	\$170,976	\$39,449	\$728,486
Assm: 02020137	Descr: Structural Steel, Hv Load, Columns	UOM: SF	\$0.74	\$0.24	\$0.06	\$1.04
		Qty: 83917	\$62,132	\$20,509	\$4,733	\$87,374
Assm: 02020204	Descr: 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	UOM: SF	\$5.99	\$8.06	\$0.09	\$14.14
		Qty: 42871	\$256,823	\$345,369	\$4,047	\$606,239
Assm: 02020315	Descr: Concrete Roof Deck	UOM: SF	\$2.56	\$2.79	\$0.05	\$5.40
		Qty: 115618	\$296,202	\$322,736	\$5,619	\$624,557
Assm: 02020320	Descr: Concrete Deck Reinforcing Steel	UOM: TON	\$551.26	\$645.22	\$0.00	\$1,196.47
		Qty: 335	\$184,832	\$216,334	\$0	\$401,166
Assm: 03010103	Descr: Tilt-Up Wall Panel 5-1/2" Thick	UOM: SF	\$11.02	\$1.21	\$0.17	\$12.40
		Qty: 18017	\$198,614	\$21,779	\$3,081	\$223,474
Assm: 03010147	Descr: Additional Vertical Reinforcement And Grouting; Seismic	UOM: SF	\$0.23	\$0.36	\$0.03	\$0.62
		Qty: 18017	\$4,133	\$6,520	\$454	\$11,107
Assm: 03010205	Descr: Loose Fill 8" Block Insulation	UOM: SF	\$0.51	\$0.46	\$0.00	\$0.98
		Qty: 18017	\$9,201	\$8,374	\$0	\$17,576
Assm: 03010312	Descr: Paint CMU/Concrete	UOM: SF	\$0.19	\$0.53	\$0.00	\$0.72
		Qty: 18017	\$3,339	\$9,605	\$0	\$12,943
Assm: 03010501	Descr: Fixed Blade Exterior Louver With Baked Enamel Finish	UOM: SF	\$29.84	\$12.28	\$0.00	\$42.12
		Qty: 408	\$12,174	\$5,010	\$0	\$17,184
Assm: 03030101	Descr: 3'0" X 7'0" Aluminum And Glass Door	UOM: EA	\$608.95	\$579.12	\$0.00	\$1,188.07
		Qty: 1	\$609	\$579	\$0	\$1,188

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 03030202	Descr: 3'0" X 7'0" Hollow Metal Door W/Frame	UOM: EA	\$1,287.09	\$468.13	\$0.00	\$1,755.22
		Qty: 3	\$3,861	\$1,404	\$0	\$5,266
Assm: 03030204	Descr: 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	UOM: EA	\$2,328.71	\$734.80	\$0.00	\$3,063.51
		Qty: 1	\$2,329	\$735	\$0	\$3,064
Assm: 03040103	Descr: 20'0" X 14'0" Metal Overhead Door	UOM: EA	\$3,536.29	\$1,914.35	\$99.90	\$5,550.54
		Qty: 7	\$24,754	\$13,400	\$699	\$38,854
Assm: 04010108	Descr: Standing Seam Metal Roof	UOM: SF	\$2.03	\$1.26	\$0.00	\$3.29
		Qty: 115618	\$234,820	\$145,459	\$0	\$380,279
Assm: 04010302	Descr: Rigid Insulation 1-1/2" Thick	UOM: SF	\$0.35	\$0.24	\$0.00	\$0.59
		Qty: 115618	\$40,732	\$27,875	\$0	\$68,608
Assm: 04010503	Descr: Skylights, Plastic Insulated Domes	UOM: SF	\$23.64	\$4.31	\$0.00	\$27.94
		Qty: 1107	\$26,165	\$4,770	\$0	\$30,935
Assm: 04010601	Descr: 5" Box Gutters With Downspouts	UOM: LF	\$1.59	\$3.61	\$0.00	\$5.20
		Qty: 114	\$181	\$410	\$0	\$591
Assm: 08020101	Descr: Copper Pipe & Fittings	UOM: EA	\$203.76	\$720.72	\$0.00	\$924.48
		Qty: 4	\$815	\$2,883	\$0	\$3,698
Assm: 08020201	Descr: Valves & Hydrants	UOM: EA	\$90.94	\$25.08	\$0.00	\$116.03
		Qty: 2	\$182	\$50	\$0	\$232
Assm: 08020401	Descr: Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	UOM: EA	\$78.67	\$82.34	\$0.00	\$161.01
		Qty: 4	\$315	\$329	\$0	\$644
Assm: 08030101	Descr: Waste Pipe & Fittings	UOM: EA	\$180.14	\$361.88	\$0.00	\$542.02
		Qty: 6	\$1,081	\$2,171	\$0	\$3,252

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 08030202	Descr: PVC Vent Piping	UOM: EA	\$13.95	\$47.57	\$0.00	\$61.51
		Qty: 6	\$84	\$285	\$0	\$369
Assm: 08030305	Descr: Heavy Duty Cast Iron Floor Drains	UOM: EA	\$409.55	\$63.67	\$0.00	\$473.21
		Qty: 1	\$410	\$64	\$0	\$473
Assm: 08050102	Descr: Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	UOM: EA	\$299.10	\$172.74	\$0.00	\$471.84
		Qty: 1	\$299	\$173	\$0	\$472
Assm: 08050108	Descr: Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	UOM: EA	\$400.59	\$43.19	\$0.00	\$443.77
		Qty: 1	\$401	\$43	\$0	\$444
Assm: 08060201	Descr: Acid Waste System For Battery & Acid Rooms	UOM: EA	\$2,609.25	\$939.01	\$0.00	\$3,548.25
		Qty: 1	\$2,609	\$939	\$0	\$3,548
Assm: 08060204	Descr: Special Plumbing For Battery And Acid Rooms	UOM: EA	\$362.85	\$935.23	\$0.00	\$1,298.08
		Qty: 1	\$363	\$935	\$0	\$1,298
Assm: 08060304	Descr: Interceptors For Battery & Acid Rooms	UOM: EA	\$1,401.67	\$222.85	\$0.00	\$1,624.52
		Qty: 1	\$1,402	\$223	\$0	\$1,625
Assm: 09010208	Descr: 1998 MBH Gas Supply	UOM: EA	\$3,367.39	\$2,292.17	\$148.33	\$5,807.88
		Qty: 1	\$3,367	\$2,292	\$148	\$5,808
Assm: 09020403	Descr: Gas Fired Unit Heater, 300 MBH, Spark Ignition	UOM: EA	\$3,016.12	\$839.47	\$1.70	\$3,857.29
		Qty: 15	\$45,242	\$12,592	\$25	\$57,859
Assm: 09030203	Descr: 4 Ton Condensing Unit With Refrigerant Piping	UOM: EA	\$2,738.13	\$2,106.03	\$0.00	\$4,844.16
		Qty: 1	\$2,738	\$2,106	\$0	\$4,844
Assm: 09040703	Descr: Toilet Exhaust .2 MCFM	UOM: MCFM	\$1,116.15	\$1,667.16	\$0.00	\$2,783.31
		Qty: 0	\$89	\$133	\$0	\$223

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 09040727	Descr: Ventilation System, 64.8 MCFM	UOM: MCFM	\$418.17	\$71.07	\$0.00	\$489.24
		Qty: 48	\$20,273	\$3,446	\$0	\$23,718
Assm: 09040765	Descr: 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	UOM: MCFM	\$3,520.33	\$790.73	\$0.00	\$4,311.06
		Qty: 1	\$4,682	\$1,052	\$0	\$5,734
Assm: 09049907	Descr: Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	UOM: MCFM	\$1,370.16	\$1,955.73	\$0.00	\$3,325.89
		Qty: 0	\$41	\$59	\$0	\$100
Assm: 09049921	Descr: 2.0 MCFM Air Dist Sys With Heat Pump	UOM: MCFM	\$3,706.36	\$4,390.65	\$0.00	\$8,097.01
		Qty: 0	\$1,149	\$1,361	\$0	\$2,510
Assm: 09049923	Descr: 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	UOM: MCFM	\$1,645.75	\$4,920.50	\$0.00	\$6,566.24
		Qty: 0	\$379	\$1,132	\$0	\$1,510
Assm: 09060107	Descr: Control System For Cooling Unit	UOM: EA	\$122.32	\$58.85	\$0.00	\$181.17
		Qty: 1	\$122	\$59	\$0	\$181
Assm: 09060182	Descr: Controls For Ventilating System	UOM: EA	\$19,211.52	\$29,488.79	\$0.00	\$48,700.31
		Qty: 1	\$19,212	\$29,489	\$0	\$48,700
Assm: 09070201	Descr: Test & Balance, Cent Fan/Utility Set	UOM: EA	\$0.00	\$206.44	\$0.00	\$206.44
		Qty: 5	\$0	\$1,032	\$0	\$1,032
Assm: 09070202	Descr: Test & Balance H&V Unit/In Line Fan	UOM: EA	\$0.00	\$309.73	\$0.00	\$309.73
		Qty: 8	\$0	\$2,478	\$0	\$2,478
Assm: 09070206	Descr: Test & Balance Air Handler, Low Pressure	UOM: EA	\$0.00	\$413.28	\$0.00	\$413.28
		Qty: 1	\$0	\$413	\$0	\$413
Assm: 09070211	Descr: Test & Balance Vav Box	UOM: EA	\$39.90	\$68.74	\$0.00	\$108.64
		Qty: 1	\$40	\$69	\$0	\$109

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm:	10010104	Descr: Fire Prot Water Supply, (40'H) Ord Haz Fac	UOM:	EA	\$48.03	\$21.35	\$0.22	\$69.60
			Qty:	905	\$43,468	\$19,320	\$199	\$62,986
Assm:	10020101	Descr: Exposed Sprinkler System For A Lg Facility - Ord. Haz.	UOM:	EA	\$28.44	\$81.42	\$0.00	\$109.86
			Qty:	905	\$25,735	\$73,684	\$0	\$99,419
Assm:	11010102	Descr: Ungrd 400 Amp Main Transformer	UOM:	EA	\$12,302.04	\$2,719.04	\$54.41	\$15,075.49
			Qty:	1	\$12,302	\$2,719	\$54	\$15,075
Assm:	11010205	Descr: Ungrd 400 Amp Secondary	UOM:	EA	\$3,411.78	\$2,187.03	\$10.07	\$5,608.88
			Qty:	1	\$3,412	\$2,187	\$10	\$5,609
Assm:	11010305	Descr: Ungrd 400 Amp Main Switchboard	UOM:	EA	\$22,577.91	\$3,342.16	\$0.00	\$25,920.07
			Qty:	1	\$22,578	\$3,342	\$0	\$25,920
Assm:	11010401	Descr: (10-30 Amps 480V) 25 KVA Dry Type Transformer	UOM:	EA	\$1,291.40	\$674.69	\$0.00	\$1,966.09
			Qty:	2	\$2,583	\$1,349	\$0	\$3,932
Assm:	11010402	Descr: (30-45 Amps 480V) 37.5 KVA Dry Type Transformer	UOM:	EA	\$1,367.54	\$843.36	\$0.00	\$2,210.90
			Qty:	2	\$2,735	\$1,687	\$0	\$4,422
Assm:	11010501	Descr: Panelbd 208V 100A 24 Cir Mlo W/Bkr	UOM:	EA	\$882.61	\$1,140.56	\$0.00	\$2,023.17
			Qty:	2	\$1,765	\$2,281	\$0	\$4,046
Assm:	11010506	Descr: Panelbd 208V 225A 36 Cir Mlo W/Bkr	UOM:	EA	\$1,554.41	\$2,086.31	\$0.00	\$3,640.72
			Qty:	1	\$1,554	\$2,086	\$0	\$3,641
Assm:	11010507	Descr: Panelbd 208V 225A 42 Cir Mlo W/Bkr	UOM:	EA	\$1,772.16	\$2,235.15	\$0.00	\$4,007.30
			Qty:	1	\$1,772	\$2,235	\$0	\$4,007
Assm:	11010536	Descr: Panelbd 480V 225A 36 Cir Mlo W/Bkr	UOM:	EA	\$2,296.82	\$2,123.79	\$0.00	\$4,420.61
			Qty:	1	\$2,297	\$2,124	\$0	\$4,421

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 11010602	Descr: Enclosed Cir Bkr 600V 60A	UOM:	EA	\$691.57	\$1,188.21	\$0.00	\$1,879.78
		Qty:	1	\$692	\$1,188	\$0	\$1,880
Assm: 11010609	Descr: Enclosed Cir Bkr 600V 30A	UOM:	EA	\$260.10	\$281.26	\$0.00	\$541.36
		Qty:	2	\$520	\$563	\$0	\$1,083
Assm: 11010611	Descr: Enclosed Cir Bkr 600V 100A	UOM:	EA	\$539.76	\$481.77	\$0.00	\$1,021.53
		Qty:	2	\$1,080	\$964	\$0	\$2,043
Assm: 12010102	Descr: Fire Alarm System - Rate Of Rise Heat Detectors	UOM:	OUT	\$102.32	\$374.83	\$0.00	\$477.15
		Qty:	35	\$3,581	\$13,119	\$0	\$16,700
Assm: 12010119	Descr: 16 Zone FACP, Annun And Transmitter	UOM:	EA	\$6,181.75	\$3,465.03	\$0.00	\$9,646.78
		Qty:	1	\$6,182	\$3,465	\$0	\$9,647
Assm: 12010301	Descr: Telephone System, 2 Pair	UOM:	EA	\$42.39	\$176.98	\$0.00	\$219.38
		Qty:	10	\$424	\$1,770	\$0	\$2,194
Assm: 12010402	Descr: Public Address For Large Warehouse	UOM:	SF	\$0.03	\$0.07	\$0.00	\$0.10
		Qty:	104044	\$3,080	\$7,470	\$0	\$10,550
Assm: 12010601	Descr: Clock System	UOM:	EA	\$222.34	\$177.74	\$0.00	\$400.08
		Qty:	4	\$889	\$711	\$0	\$1,600
Assm: 12010602	Descr: Time Clock System	UOM:	EA	\$334.18	\$866.03	\$0.00	\$1,200.22
		Qty:	2	\$668	\$1,732	\$0	\$2,400
Assm: 12020221	Descr: Battery Charger	UOM:	EA	\$1,043.18	\$619.45	\$0.00	\$1,662.63
		Qty:	6	\$6,259	\$3,717	\$0	\$9,976
Assm: 12020401	Descr: Lightning Protection System	UOM:	EA	\$78.54	\$141.38	\$0.00	\$219.92
		Qty:	5	\$393	\$707	\$0	\$1,100

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 12020601	Descr: Energy Management Control System	UOM:	PTS	\$932.47	\$401.74	\$0.00	\$1,334.21
		Qty:	18	\$16,784	\$7,231	\$0	\$24,016

FSA: **ID:** CVN **Name:** COVERED EXTERIOR ENTRYWAY

Facility Type: Primary **ID:** 50 **Name:** Classified Waste Storage Warehouse

Assm: 06039002	Descr: Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
		Qty:	108	\$623	\$705	\$0	\$1,327

Assm: 11020229	Descr: 100W Hps Wall Mount	UOM:	EA	\$175.34	\$236.30	\$0.00	\$411.64
		Qty:	1	\$175	\$236	\$0	\$412

Assm: 11020235	Descr: 150 Watt Hps Recessed Fixture	UOM:	EA	\$215.09	\$246.25	\$0.00	\$461.34
		Qty:	1	\$215	\$246	\$0	\$461

FSA: **ID:** CVT **Name:** COVERED EXTERIOR LOADING DOCK W/LEVELER

Facility Type: Primary **ID:** 50 **Name:** Classified Waste Storage Warehouse

Assm: 06039002	Descr: Exterior Canopy W/Framing	UOM:	SF	\$5.76	\$6.52	\$0.00	\$12.29
		Qty:	1061	\$6,117	\$6,923	\$0	\$13,039

Assm: 11020136	Descr: Equipment Connections For Up To 5 HP	UOM:	EA	\$267.15	\$527.09	\$0.00	\$794.24
		Qty:	1	\$267	\$527	\$0	\$794

Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM:	EA	\$200.94	\$375.90	\$0.00	\$576.85
		Qty:	4	\$804	\$1,504	\$0	\$2,307

Assm: 11020280	Descr: Dock Lights	UOM:	EA	\$123.71	\$227.24	\$0.00	\$350.95
		Qty:	2	\$247	\$454	\$0	\$702

Assm: 13010602	Descr: 6'0" X 8'0" Long 10 Ton Capacity With Stairs	UOM:	DOCK	\$4,942.83	\$1,428.71	\$40.13	\$6,411.67
		Qty:	1	\$4,943	\$1,429	\$40	\$6,412

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	13010606	Descr:	24" Deep Dock Leveler Pit Wall W/Stl Angle	UOM:	EA	\$483.17	\$1,116.94	\$1.04	\$1,601.14
				Qty:	1	\$483	\$1,117	\$1	\$1,601

FSA: ID: MEL Name: MECHANICAL, ELECTRICAL, & BUILDING SUPPORT

Facility Type: Primary ID: 50 Name: Classified Waste Storage Warehouse

Assm:	05010114	Descr:	Non-Load Bearing 8 X 8 X 16 Concrete Block	UOM:	SF	\$2.34	\$5.03	\$0.00	\$7.37
				Qty:	337	\$788	\$1,695	\$0	\$2,483

Assm:	06010502	Descr:	Paint To Concrete Block Using Brushes, Two Coats	UOM:	SF	\$0.29	\$0.72	\$0.00	\$1.00
				Qty:	668	\$192	\$479	\$0	\$671

Assm:	06030301	Descr:	5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	UOM:	SF	\$0.32	\$0.59	\$0.00	\$0.92
				Qty:	56	\$18	\$33	\$0	\$51

Assm:	06030704	Descr:	Suspension System For Gypsum Board Ceiling	UOM:	SF	\$0.75	\$4.08	\$0.00	\$4.83
				Qty:	56	\$42	\$228	\$0	\$270

Assm:	11020102	Descr:	120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	UOM:	EA	\$31.01	\$170.59	\$0.00	\$201.60
				Qty:	2	\$62	\$341	\$0	\$403

Assm:	11020156	Descr:	120V 20A Single Pole Switch	UOM:	EA	\$25.89	\$148.76	\$0.00	\$174.65
				Qty:	1	\$26	\$149	\$0	\$175

Assm:	11020276	Descr:	Porcelain Lamp Holder	UOM:	EA	\$21.47	\$177.99	\$0.00	\$199.46
				Qty:	1	\$21	\$178	\$0	\$199

FSA: ID: SRM Name: STOCKROOM

Facility Type: Primary ID: 50 Name: Classified Waste Storage Warehouse

Assm:	03010310	Descr:	5/8" Gypsum Board/Installed/Taped & Finished	UOM:	SF	\$5.93	\$0.59	\$0.00	\$6.52
				Qty:	21837	\$129,493	\$12,984	\$0	\$142,478

Paces

Project Summary Report

Date 07/26/2002

			<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 05010112	Descr: Non-Load Brg Partition Of 8 X 6 X 16 Concrete	UOM: SF	\$1.97	\$3.68	\$0.00	\$5.65
		Qty: 3380	\$6,643	\$12,453	\$0	\$19,096
Assm: 05010126	Descr: Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	UOM: SF	\$1.68	\$1.66	\$0.00	\$3.34
		Qty: 25159	\$42,232	\$41,676	\$0	\$83,908
Assm: 05010127	Descr: Wire Mesh Partitions, 4' Wide X 20' High	UOM: SF	\$3.37	\$1.04	\$0.00	\$4.41
		Qty: 702	\$2,365	\$727	\$0	\$3,092
Assm: 05039014	Descr: Sliding Metal Clad Door (With Motor)	UOM: SF	\$35.54	\$9.59	\$0.00	\$45.13
		Qty: 1301	\$46,241	\$12,476	\$0	\$58,717
Assm: 06010502	Descr: Paint To Concrete Block Using Brushes, Two Coats	UOM: SF	\$0.29	\$0.72	\$0.00	\$1.00
		Qty: 2027	\$582	\$1,455	\$0	\$2,037
Assm: 06029001	Descr: Concrete Floor Sealer	UOM: SF	\$0.04	\$0.05	\$0.00	\$0.08
		Qty: 102396	\$3,778	\$4,905	\$0	\$8,683
Assm: 06029003	Descr: Floor Hardener, Non-Metallic Light Service	UOM: SF	\$0.18	\$0.32	\$0.00	\$0.49
		Qty: 102396	\$18,257	\$32,347	\$0	\$50,604
Assm: 11020103	Descr: Duplex Receptacle Long Run	UOM: EA	\$48.69	\$297.44	\$0.00	\$346.13
		Qty: 43	\$2,094	\$12,790	\$0	\$14,884
Assm: 11020136	Descr: Equipment Connections For Up To 5 HP	UOM: EA	\$267.15	\$527.09	\$0.00	\$794.24
		Qty: 32	\$8,549	\$16,867	\$0	\$25,416
Assm: 11020229	Descr: 100W Hps Wall Mount	UOM: EA	\$175.34	\$236.30	\$0.00	\$411.64
		Qty: 13	\$2,279	\$3,072	\$0	\$5,351
Assm: 11020254	Descr: High Bay 400W Hps Fixture	UOM: EA	\$200.94	\$375.90	\$0.00	\$576.85
		Qty: 168	\$33,759	\$63,151	\$0	\$96,910

Paces

Project Summary Report

Date 07/26/2002

						<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm:	11020255	Descr:	High Bay 400W Hps Fixture With Quartz Standby	UOM:	EA	\$296.72	\$467.99	\$0.00	\$764.70
				Qty:	23	\$6,824	\$10,764	\$0	\$17,588
Assm:	11020272	Descr:	Exit Light With Battery Backup	UOM:	EA	\$117.22	\$212.56	\$0.00	\$329.78
				Qty:	4	\$469	\$850	\$0	\$1,319
FSA:	ID: PRK	Name:	Parking Lots						
Facility Type:	Supporting	ID: 12	Name: Parking Lots 1						
Assm:	17010106	Descr:	Heavy Brush, Light Trees, Clear, Grub, Haul	UOM:	ACRE	\$0.00	\$2,002.62	\$921.83	\$2,924.44
				Qty:	0	\$0	\$941	\$433	\$1,374
FSA:	ID: GAD	Name:	Gas Distribution						
Facility Type:	Supporting	ID: 12	Name: Gas Distribution 1						
Assm:	17020401	Descr:	Dump Charge	UOM:	CY	\$15.00	\$0.00	\$0.00	\$15.00
				Qty:	111	\$1,666	\$0	\$0	\$1,666
FSA:	ID: WTD	Name:	Water Distribution						
Facility Type:	Supporting	ID: 12	Name: Water Distribution 1						
Assm:	17020401	Descr:	Dump Charge	UOM:	CY	\$15.00	\$0.00	\$0.00	\$15.00
				Qty:	303	\$4,539	\$0	\$0	\$4,539
FSA:	ID: SAN	Name:	Sanitary Sewer						
Facility Type:	Supporting	ID: 12	Name: Sanitary Sewer 1						
Assm:	17020401	Descr:	Dump Charge	UOM:	CY	\$15.00	\$0.00	\$0.00	\$15.00
				Qty:	61	\$912	\$0	\$0	\$912
FSA:	ID: PRK	Name:	Parking Lots						

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Facility Type:	Supporting	ID: 12	Name: Parking Lots 1				
Assm: 17030102	Descr: Rough Grading, 12G, 1 Pass			UOM: SY	\$0.00	\$0.20	\$0.17
				Qty: 3433	\$0	\$681	\$583
FSA:	ID: ARD	Name: Access Roads					
Facility Type:	Supporting	ID: 12	Name: Access Roads 1				
Assm: 17030103	Descr: ROUGH GRADING, 14G, 1 PASS			UOM: SY	\$0.00	\$0.30	\$0.25
				Qty: 86720	\$0	\$25,799	\$21,264
FSA:	ID: PRK	Name: Parking Lots					
Facility Type:	Supporting	ID: 12	Name: Parking Lots 1				
Assm: 17030107	Descr: Fine Grading, 120G, 2 Passes			UOM: SY	\$0.00	\$0.09	\$0.07
				Qty: 3433	\$0	\$302	\$227
FSA:	ID: ARD	Name: Access Roads					
Facility Type:	Supporting	ID: 12	Name: Access Roads 1				
Assm: 17030108	Descr: Fine Grading, 130G, 2 Passes			UOM: SY	\$0.00	\$0.09	\$0.07
				Qty: 37940	\$0	\$3,343	\$2,504
Assm: 17030202	Descr: Ditch Excavation, Normal Soil, Hauloff Spoil 1 Mile			UOM: CY	\$0.00	\$1.98	\$2.08
				Qty: 12044	\$0	\$23,885	\$24,992
Assm: 17030203	Descr: Roadway Soil Excavation, W/Scraper, Load & Haul Spoil			UOM: CY	\$0.00	\$1.86	\$2.04
				Qty: 10539	\$0	\$19,622	\$21,471
FSA:	ID: PRK	Name: Parking Lots					
Facility Type:	Supporting	ID: 12	Name: Parking Lots 1				

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 17030203	Descr: Roadway Soil Excavation, W/Scraper, Load & Haul Spoil	UOM:	CY		\$0.00	\$1.86	\$2.04	\$3.90
		Qty:	381		\$0	\$710	\$777	\$1,487
FSA:	ID: GAD	Name:	Gas Distribution					
Facility Type:	Supporting	ID: 12	Name:	Gas Distribution 1				
Assm: 17030220	Descr: 910, 1.25 CY, Wheel Loader	UOM:	HR		\$0.00	\$35.90	\$19.54	\$55.45
		Qty:	3		\$0	\$108	\$59	\$166
FSA:	ID: SAN	Name:	Sanitary Sewer					
Facility Type:	Supporting	ID: 12	Name:	Sanitary Sewer 1				
Assm: 17030220	Descr: 910, 1.25 CY, Wheel Loader	UOM:	HR		\$0.00	\$35.90	\$19.54	\$55.45
		Qty:	2		\$0	\$72	\$39	\$111
FSA:	ID: WTD	Name:	Water Distribution					
Facility Type:	Supporting	ID: 12	Name:	Water Distribution 1				
Assm: 17030220	Descr: 910, 1.25 CY, Wheel Loader	UOM:	HR		\$0.00	\$35.90	\$19.54	\$55.45
		Qty:	7		\$0	\$251	\$137	\$388
FSA:	ID: LTG	Name:	Lighting-Interstate, Roadway, Parking					
Facility Type:	Supporting	ID: 12	Name:	Lighting-Interstate, Roadway, Parking 1				
Assm: 17030255	Descr: Trenching To 48" Dp, Inc Bkfl & Compaction	UOM:	CY		\$0.00	\$5.57	\$1.02	\$6.59
		Qty:	2820		\$0	\$15,720	\$2,873	\$18,593
FSA:	ID: PRK	Name:	Parking Lots					
Facility Type:	Supporting	ID: 12	Name:	Parking Lots 1				

Paces

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>		
Assm:	17030257	Descr:	Cat 215, 1 CY, Soil, Shallow, Trenching	UOM:	CY	\$0.00	\$0.32	\$0.31	\$0.63
				Qty:	50	\$0	\$16	\$15	\$31
FSA:	ID: COM	Name:	Communications						
Facility Type:	Supporting	ID: 12	Name:	Communications 1					
Assm:	17030259	Descr:	Cat 225, 1.5 CY, Soil/Sand, Trenching	UOM:	CY	\$0.00	\$0.24	\$0.28	\$0.53
				Qty:	195	\$0	\$47	\$55	\$102
FSA:	ID: SAN	Name:	Sanitary Sewer						
Facility Type:	Supporting	ID: 12	Name:	Sanitary Sewer 1					
Assm:	17030259	Descr:	Cat 225, 1.5 CY, Soil/Sand, Trenching	UOM:	CY	\$0.00	\$0.24	\$0.28	\$0.53
				Qty:	294	\$0	\$71	\$83	\$154
FSA:	ID: UND	Name:	Underground Electrical Distribution						
Facility Type:	Supporting	ID: 12	Name:	Underground Electrical Distribution 1					
Assm:	17030259	Descr:	Cat 225, 1.5 CY, Soil/Sand, Trenching	UOM:	CY	\$0.00	\$0.24	\$0.28	\$0.53
				Qty:	260	\$0	\$63	\$74	\$137
FSA:	ID: WTD	Name:	Water Distribution						
Facility Type:	Supporting	ID: 12	Name:	Water Distribution 1					
Assm:	17030259	Descr:	Cat 225, 1.5 CY, Soil/Sand, Trenching	UOM:	CY	\$0.00	\$0.24	\$0.28	\$0.53
				Qty:	1640	\$0	\$398	\$464	\$862
FSA:	ID: GAD	Name:	Gas Distribution						
Facility Type:	Supporting	ID: 12	Name:	Gas Distribution 1					

Paces

Project Summary Report

Date 07/26/2002

						<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm:	17030259	Descr:	Cat 225, 1.5 CY, Soil/Sand, Trenching	UOM:	CY	\$0.00	\$0.24	\$0.28	\$0.53
				Qty:	545	\$0	\$132	\$154	\$286
FSA:	ID: SAN	Name:	Sanitary Sewer						
Facility Type:	Supporting	ID: 12	Name:	Sanitary Sewer 1					
Assm:	17030284	Descr:	8 CY, Dump Truck	UOM:	HR	\$0.00	\$29.10	\$36.46	\$65.56
				Qty:	5	\$0	\$145	\$182	\$328
FSA:	ID: WTD	Name:	Water Distribution						
Facility Type:	Supporting	ID: 12	Name:	Water Distribution 1					
Assm:	17030284	Descr:	8 CY, Dump Truck	UOM:	HR	\$0.00	\$29.10	\$36.46	\$65.56
				Qty:	23	\$0	\$669	\$839	\$1,508
FSA:	ID: GAD	Name:	Gas Distribution						
Facility Type:	Supporting	ID: 12	Name:	Gas Distribution 1					
Assm:	17030284	Descr:	8 CY, Dump Truck	UOM:	HR	\$0.00	\$29.10	\$36.46	\$65.56
				Qty:	9	\$0	\$262	\$328	\$590
Assm:	17030401	Descr:	950, 3 CY, Backfill W/Excavated Material	UOM:	CY	\$0.00	\$0.51	\$0.59	\$1.10
				Qty:	391	\$0	\$198	\$232	\$430
FSA:	ID: COM	Name:	Communications						
Facility Type:	Supporting	ID: 12	Name:	Communications 1					
Assm:	17030401	Descr:	950, 3 CY, Backfill W/Excavated Material	UOM:	CY	\$0.00	\$0.51	\$0.59	\$1.10
				Qty:	112	\$0	\$57	\$67	\$123
FSA:	ID: SAN	Name:	Sanitary Sewer						

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Facility Type:	Supporting	ID: 12	Name:	Sanitary Sewer 1					
Assm:	17030401	Descr:	950, 3 CY, Backfill W/Excavated Material	UOM:	CY	\$0.00	\$0.51	\$0.59	\$1.10
					Qty:	245	\$0	\$124	\$146
FSA:	ID: UND	Name:	Underground Electrical Distribution						
Facility Type:	Supporting	ID: 12	Name:	Underground Electrical Distribution 1					
Assm:	17030401	Descr:	950, 3 CY, Backfill W/Excavated Material	UOM:	CY	\$0.00	\$0.51	\$0.59	\$1.10
					Qty:	149	\$0	\$76	\$89
FSA:	ID: WTD	Name:	Water Distribution						
Facility Type:	Supporting	ID: 12	Name:	Water Distribution 1					
Assm:	17030401	Descr:	950, 3 CY, Backfill W/Excavated Material	UOM:	CY	\$0.00	\$0.51	\$0.59	\$1.10
					Qty:	1398	\$0	\$709	\$831
FSA:	ID: COM	Name:	Communications						
Facility Type:	Supporting	ID: 12	Name:	Communications 1					
Assm:	17030405	Descr:	950, 3 CY, Delivered & Dumped, Backfill W/Sand	UOM:	CY	\$20.09	\$2.14	\$2.08	\$24.30
					Qty:	32	\$643	\$68	\$66
FSA:	ID: GAD	Name:	Gas Distribution						
Facility Type:	Supporting	ID: 12	Name:	Gas Distribution 1					
Assm:	17030405	Descr:	950, 3 CY, Delivered & Dumped, Backfill W/Sand	UOM:	CY	\$20.09	\$2.14	\$2.08	\$24.30
					Qty:	97	\$1,949	\$207	\$201
FSA:	ID: UND	Name:	Underground Electrical Distribution						
Facility Type:	Supporting	ID: 12	Name:	Underground Electrical Distribution 1					

Paces

Project Summary Report

Date 07/26/2002

				Mat \$	Lab \$	Eqp \$	Ttl \$		
Assm:	17030405	Descr:	950, 3 CY, Delivered & Dumped, Backfill W/Sand	UOM:	CY	\$20.09	\$2.14	\$2.08	\$24.30
				Qty:	43	\$864	\$92	\$89	\$1,045
FSA:	ID: SAN	Name:	Sanitary Sewer						
Facility Type:	Supporting	ID:	12	Name:	Sanitary Sewer 1				
Assm:	17030405	Descr:	950, 3 CY, Delivered & Dumped, Backfill W/Sand	UOM:	CY	\$20.09	\$2.14	\$2.08	\$24.30
				Qty:	47	\$935	\$99	\$97	\$1,131
FSA:	ID: WTD	Name:	Water Distribution						
Facility Type:	Supporting	ID:	12	Name:	Water Distribution 1				
Assm:	17030405	Descr:	950, 3 CY, Delivered & Dumped, Backfill W/Sand	UOM:	CY	\$20.09	\$2.14	\$2.08	\$24.30
				Qty:	245	\$4,922	\$524	\$508	\$5,954
FSA:	ID: ARD	Name:	Access Roads						
Facility Type:	Supporting	ID:	12	Name:	Access Roads 1				
Assm:	17030501	Descr:	Compact Subgrade, 2 Lifts	UOM:	CY	\$0.00	\$1.51	\$0.04	\$1.55
				Qty:	14453	\$0	\$21,814	\$545	\$22,359
FSA:	ID: PRK	Name:	Parking Lots						
Facility Type:	Supporting	ID:	12	Name:	Parking Lots 1				
Assm:	17030501	Descr:	Compact Subgrade, 2 Lifts	UOM:	CY	\$0.00	\$1.51	\$0.04	\$1.55
				Qty:	477	\$0	\$720	\$18	\$738
Assm:	17030510	Descr:	Dry Roll Gravel, Steel Roller	UOM:	SY	\$0.00	\$0.47	\$0.19	\$0.66
				Qty:	1717	\$0	\$813	\$324	\$1,137
FSA:	ID: COM	Name:	Communications						

Project Summary Report

Date 07/26/2002

				<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>		
Facility Type:	Supporting	ID: 12	Name: Communications 1						
Assm:	17030511	Descr: Compact Soil W/Vibrating Plate	UOM:	CY	\$0.00	\$1.19	\$0.08	\$1.27	
				Qty:	112	\$0	\$133	\$10	\$143
FSA:	ID: UND	Name:	Underground Electrical Distribution						
Facility Type:	Supporting	ID: 12	Name: Underground Electrical Distribution 1						
Assm:	17030511	Descr: Compact Soil W/Vibrating Plate	UOM:	CY	\$0.00	\$1.19	\$0.08	\$1.27	
				Qty:	149	\$0	\$177	\$13	\$190
FSA:	ID: WTD	Name:	Water Distribution						
Facility Type:	Supporting	ID: 12	Name: Water Distribution 1						
Assm:	17030511	Descr: Compact Soil W/Vibrating Plate	UOM:	CY	\$0.00	\$1.19	\$0.08	\$1.27	
				Qty:	1398	\$0	\$1,663	\$119	\$1,782
FSA:	ID: GAD	Name:	Gas Distribution						
Facility Type:	Supporting	ID: 12	Name: Gas Distribution 1						
Assm:	17030511	Descr: Compact Soil W/Vibrating Plate	UOM:	CY	\$0.00	\$1.19	\$0.08	\$1.27	
				Qty:	456	\$0	\$543	\$39	\$581
FSA:	ID: SAN	Name:	Sanitary Sewer						
Facility Type:	Supporting	ID: 12	Name: Sanitary Sewer 1						
Assm:	17030511	Descr: Compact Soil W/Vibrating Plate	UOM:	CY	\$0.00	\$1.19	\$0.08	\$1.27	
				Qty:	245	\$0	\$292	\$21	\$312
FSA:	ID: COM	Name:	Communications						
Facility Type:	Supporting	ID: 12	Name: Communications 1						

Paces

Project Summary Report

Date 07/26/2002

						<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm:	17030515	Descr:	Compact With Pogosticks	UOM:	CY	\$0.00	\$6.32	\$0.41	\$6.73
				Qty:	32	\$0	\$202	\$13	\$215
FSA:	ID: SAN	Name:	Sanitary Sewer						
Facility Type:	Supporting	ID: 12	Name:	Sanitary Sewer 1					
Assm:	17030515	Descr:	Compact With Pogosticks	UOM:	CY	\$0.00	\$6.32	\$0.41	\$6.73
				Qty:	47	\$0	\$294	\$19	\$313
FSA:	ID: WTD	Name:	Water Distribution						
Facility Type:	Supporting	ID: 12	Name:	Water Distribution 1					
Assm:	17030515	Descr:	Compact With Pogosticks	UOM:	CY	\$0.00	\$6.32	\$0.41	\$6.73
				Qty:	245	\$0	\$1,549	\$99	\$1,649
FSA:	ID: UND	Name:	Underground Electrical Distribution						
Facility Type:	Supporting	ID: 12	Name:	Underground Electrical Distribution 1					
Assm:	17030515	Descr:	Compact With Pogosticks	UOM:	CY	\$0.00	\$6.32	\$0.41	\$6.73
				Qty:	43	\$0	\$272	\$17	\$289
FSA:	ID: GAD	Name:	Gas Distribution						
Facility Type:	Supporting	ID: 12	Name:	Gas Distribution 1					
Assm:	17030515	Descr:	Compact With Pogosticks	UOM:	CY	\$0.00	\$6.32	\$0.41	\$6.73
				Qty:	97	\$0	\$613	\$39	\$653
FSA:	ID: PRK	Name:	Parking Lots						
Facility Type:	Supporting	ID: 12	Name:	Parking Lots 1					

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm: 17030515	Descr: Compact With Pogosticks	UOM:	CY		\$0.00	\$6.32	\$0.41	\$6.73
		Qty:	26		\$0	\$164	\$11	\$175
FSA:	ID: COM	Name:	Communications					
Facility Type:	Supporting	ID: 12	Name:	Communications 1				
Assm: 17031002	Descr: 2" Dia Contractor's Trash Pump, 75 GPM	UOM:	DAY		\$37.68	\$7.38	\$0.00	\$45.06
		Qty:	3		\$113	\$22	\$0	\$135
FSA:	ID: ARD	Name:	Access Roads					
Facility Type:	Supporting	ID: 12	Name:	Access Roads 1				
Assm: 18010102	Descr: Gravel, Delivered & Dumped	UOM:	CY		\$14.43	\$1.60	\$1.09	\$17.12
		Qty:	10539		\$152,070	\$16,836	\$11,531	\$180,436
FSA:	ID: PRK	Name:	Parking Lots					
Facility Type:	Supporting	ID: 12	Name:	Parking Lots 1				
Assm: 18010102	Descr: Gravel, Delivered & Dumped	UOM:	CY		\$14.43	\$1.60	\$1.09	\$17.12
		Qty:	381		\$5,505	\$609	\$417	\$6,531
Assm: 18010202	Descr: Concrete Curb & Gutter, 6" x 24", Formed	UOM:	LF		\$10.55	\$4.78	\$0.00	\$15.33
		Qty:	495		\$5,221	\$2,366	\$0	\$7,587
Assm: 18010310	Descr: Prime Coat	UOM:	SY		\$0.29	\$0.02	\$0.01	\$0.33
		Qty:	1717		\$500	\$36	\$25	\$560
FSA:	ID: ARD	Name:	Access Roads					
Facility Type:	Supporting	ID: 12	Name:	Access Roads 1				
Assm: 18010310	Descr: Prime Coat	UOM:	SY		\$0.29	\$0.02	\$0.01	\$0.33
		Qty:	28907		\$8,415	\$601	\$416	\$9,432

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
FSA:	ID: PRK	Name:	Parking Lots						
Facility Type:	Supporting	ID: 12	Name:	Parking Lots 1					
Assm:	18010312	Descr:	Asphalt Wearing Course,1 Pass (Line Item Incl 5% Waste)	UOM:	TON	\$29.51	\$4.14	\$1.63	\$35.29
				Qty:	140	\$4,132	\$580	\$229	\$4,941
FSA:	ID: ARD	Name:	Access Roads						
Facility Type:	Supporting	ID: 12	Name:	Access Roads 1					
Assm:	18010312	Descr:	Asphalt Wearing Course,1 Pass (Line Item Incl 5% Waste)	UOM:	TON	\$29.51	\$4.14	\$1.63	\$35.29
				Qty:	3930	\$115,967	\$16,273	\$6,421	\$138,662
FSA:	ID: PRK	Name:	Parking Lots						
Facility Type:	Supporting	ID: 12	Name:	Parking Lots 1					
Assm:	18020205	Descr:	24" Dia, 5' Deep Precast Area Drain W/Grate	UOM:	EA	\$1,032.79	\$1,059.68	\$8.15	\$2,100.62
				Qty:	3	\$3,098	\$3,179	\$24	\$6,302
Assm:	18020401	Descr:	Parking Space Striping	UOM:	EA	\$2.56	\$3.26	\$0.62	\$6.45
				Qty:	34	\$87	\$111	\$21	\$219
FSA:	ID: FEA	Name:	Fencing						
Facility Type:	Supporting	ID: 12	Name:	Fencing 1					
Assm:	18040105	Descr:	Boundary Fence, 5' Galv	UOM:	LF	\$1.08	\$2.80	\$0.98	\$4.86
				Qty:	9880	\$10,692	\$27,647	\$9,691	\$48,031
FSA:	ID: WTD	Name:	Water Distribution						
Facility Type:	Supporting	ID: 12	Name:	Water Distribution 1					

Paces

Project Summary Report

Date 07/26/2002

						<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Assm:	19010211	Descr:	6", Class 150, PVC Piping	UOM:	LF	\$4.19	\$5.97	\$0.35	\$10.51
				Qty:	3000	\$12,573	\$17,914	\$1,047	\$31,533
FSA:	ID: SAN	Name:	Sanitary Sewer						
Facility Type:	Supporting	ID: 12	Name:	Sanitary Sewer 1					
Assm:	19020127	Descr:	8" PVC Pipe Sanitary	UOM:	LF	\$5.02	\$4.42	\$0.64	\$10.08
				Qty:	500	\$2,510	\$2,209	\$321	\$5,040
Assm:	19020201	Descr:	Precast, CIP Base, 4' Dia, 6' Deep, Manhole	UOM:	EA	\$466.14	\$423.30	\$56.61	\$946.05
				Qty:	2	\$932	\$847	\$113	\$1,892
FSA:	ID: PRK	Name:	Parking Lots						
Facility Type:	Supporting	ID: 12	Name:	Parking Lots 1					
Assm:	19030174	Descr:	12" RCP, Class 4, With Gaskets	UOM:	LF	\$11.59	\$7.13	\$0.46	\$19.18
				Qty:	99	\$1,143	\$703	\$46	\$1,891
Assm:	19030176	Descr:	18" RCP, Class 4, With Gaskets	UOM:	LF	\$14.46	\$11.51	\$0.75	\$26.73
				Qty:	37	\$541	\$431	\$28	\$1,000
FSA:	ID: ARD	Name:	Access Roads						
Facility Type:	Supporting	ID: 12	Name:	Access Roads 1					
Assm:	19030402	Descr:	34' Complete, 24" CMP Culvert W/Headwalls	UOM:	EA	\$2,687.02	\$1,776.01	\$519.28	\$4,982.31
				Qty:	7	\$18,809	\$12,432	\$3,635	\$34,876
FSA:	ID: GAD	Name:	Gas Distribution						
Facility Type:	Supporting	ID: 12	Name:	Gas Distribution 1					
Assm:	19070104	Descr:	4" Black Steel Pipe, Welded T & C Sch 40	UOM:	LF	\$3.90	\$2.54	\$0.02	\$6.47
				Qty:	1500	\$5,857	\$3,817	\$28	\$9,702

Project Summary Report

Date 07/26/2002

				Mat \$	Lab \$	Eqp \$	Ttl \$		
FSA:	ID: LTG	Name:	Lighting-Interstate, Roadway, Parking						
Facility Type:	Supporting	ID: 12	Name:	Lighting-Interstate, Roadway, Parking 1					
Assm:	20020501	Descr:	1/C #4 Copper Grd 600V DB, Wire	UOM:	LF	\$0.55	\$0.64	\$0.00	\$1.19
				Qty:	29256	\$16,012	\$18,855	\$0	\$34,867
Assm:	20020502	Descr:	1/C #6 Copper Grd 600V DB, Wire	UOM:	LF	\$0.38	\$0.64	\$0.00	\$1.03
				Qty:	20018	\$7,621	\$12,902	\$0	\$20,522
Assm:	20020503	Descr:	3/C #6, W/#6 Grd 5KV DB, Wire	UOM:	LF	\$3.42	\$2.86	\$0.35	\$6.64
				Qty:	17862	\$61,090	\$51,153	\$6,303	\$118,547
FSA:	ID: UND	Name:	Underground Electrical Distribution						
Facility Type:	Supporting	ID: 12	Name:	Underground Electrical Distribution 1					
Assm:	20020521	Descr:	15 KV, 3/0, Shielded Cable, Copper	UOM:	LF	\$2.61	\$1.60	\$0.20	\$4.41
				Qty:	4500	\$11,760	\$7,187	\$886	\$19,833
Assm:	20020546	Descr:	15 KV, 1/0 To 4/0 Conductor, Terminations & Splicing	UOM:	EA	\$131.16	\$413.79	\$0.00	\$544.95
				Qty:	6	\$787	\$2,483	\$0	\$3,270
FSA:	ID: COM	Name:	Communications						
Facility Type:	Supporting	ID: 12	Name:	Communications 1					
Assm:	20020610	Descr:	2" PVC Conduit	UOM:	LF	\$1.10	\$1.97	\$0.00	\$3.08
				Qty:	3000	\$3,314	\$5,916	\$0	\$9,230
FSA:	ID: UND	Name:	Underground Electrical Distribution						
Facility Type:	Supporting	ID: 12	Name:	Underground Electrical Distribution 1					
Assm:	20020612	Descr:	4" PVC Conduit	UOM:	LF	\$3.02	\$4.43	\$0.00	\$7.45
				Qty:	3000	\$9,053	\$13,286	\$0	\$22,340

Paces

Project Summary Report

Date 07/26/2002

					<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>	
Assm:	20020615	Descr:	Concrete Encasement For Ductbank	UOM:	CY	\$93.61	\$80.85	\$6.86	\$181.32
				Qty:	75	\$7,020	\$6,064	\$514	\$13,599
FSA:	ID: COM	Name:	Communications						
Facility Type:	Supporting	ID: 12	Name:	Communications 1					
Assm:	20020615	Descr:	Concrete Encasement For Ductbank	UOM:	CY	\$93.61	\$80.85	\$6.86	\$181.32
				Qty:	56	\$5,242	\$4,528	\$384	\$10,154
FSA:	ID: LTG	Name:	Lighting-Interstate, Roadway, Parking						
Facility Type:	Supporting	ID: 12	Name:	Lighting-Interstate, Roadway, Parking 1					
Assm:	20030102	Descr:	5/15KV - 277/480V, 75KVA Transformer, Oil, Pad Mtd	UOM:	EA	\$8,561.20	\$1,004.21	\$20.33	\$9,585.74
				Qty:	8	\$68,490	\$8,034	\$163	\$76,686
Assm:	20030303	Descr:	20' Brushed Aluminum Pole (Single Arm) W/Base	UOM:	EA	\$964.98	\$368.06	\$35.10	\$1,368.13
				Qty:	93	\$89,743	\$34,229	\$3,264	\$127,236
Assm:	20030601	Descr:	150W Hps Fixture	UOM:	EA	\$235.46	\$118.98	\$0.00	\$354.44
				Qty:	93	\$21,897	\$11,065	\$0	\$32,963
FSA:	ID: COM	Name:	Communications						
Facility Type:	Supporting	ID: 12	Name:	Communications 1					
Assm:	20040102	Descr:	51 Pair No. 22 Awg Wire, Comm Cable	UOM:	LF	\$3.93	\$1.35	\$0.00	\$5.28
				Qty:	3000	\$11,793	\$4,037	\$0	\$15,830
FSA:	ID: GAD	Name:	Gas Distribution						
Facility Type:	Supporting	ID: 12	Name:	Gas Distribution 1					
Assm:	20060101	Descr:	3-9 Lb Magnesium Anodes, Cathodic Protection Point	UOM:	EA	\$191.69	\$614.75	\$41.48	\$847.92
				Qty:	5	\$958	\$3,074	\$207	\$4,240

Project Summary Report

Date 07/26/2002

	<u>Mat \$</u>	<u>Lab \$</u>	<u>Eqp \$</u>	<u>Ttl \$</u>
Project Direct Cost: (M, L,E, T)	\$70,551,246	\$52,646,952	\$2,362,893	\$125,561,091
Pavement				\$0
Site				\$0
Utilities				\$0
Markups				\$52,096,620
Contingencies		5 %		\$8,882,886
SIOH		5.7 %		\$10,632,810
Total Project Cost:				\$197,173,400
Design Costs:		0 %		\$0
Total Project Cost With Design:				\$197,173,400